



# MID-CENTURY MODERN ACCESSORY DWELLING UNIT - PLAN 2A SAN LUIS OBISPO COUNTY, CA

## USER LICENSE AGREEMENT

BY USING THESE PERMIT READY ACCESSORY DWELLING UNIT CONSTRUCTION DOCUMENTS, THE USER AGREES TO RELEASE, HOLD HARMLESS, AND INDEMNIFY THE COUNTY OF SAN LUIS OBISPO, ITS ELECTED OFFICIALS AND EMPLOYEES, RRM DESIGN GROUP, AND THE ARCHITECT OR ENGINEER WHO PREPARED THESE CONSTRUCTION DOCUMENTS FROM ANY AND ALL CLAIMS, LIABILITIES, SUITS AND DEMANDS ON ACCOUNT OF ANY INJURY, DAMAGE OR LOSS TO PERSONS OR PROPERTY, INCLUDING INJURY OR DEATH, OR ECONOMIC LOSSES, ARISING OUT OF THE USE OF THESE CONSTRUCTION DOCUMENTS.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

SIGNATURE \_\_\_\_\_ DATE \_\_\_\_\_

## SHEET INDEX

G-021	TITLE SHEET - PLAN 2A
G-101	GENERAL NOTES
G-102	INDEX, ABBREVIATIONS, & SYMBOLS
G-103	2022 SINGLE-FAMILY RESIDENTIAL MANDATORY REQUIREMENTS
G-201	CAL GREEN RESIDENTIAL REQUIREMENTS
G-202	CAL GREEN RESIDENTIAL REQUIREMENTS
AS-102	ARCHITECTURAL SITE PLAN (EXAMPLE & INSTRUCTIONS)
A2-101	FLOOR PLAN
A2-111	FINISH, MECHANICAL, & ELECTRICAL PLANS
A2-121	ROOF PLAN & REFLECTED CEILING PLAN
A2-201	ELEVATIONS & BUILDING SECTIONS

A-901	ARCHITECTURAL DETAILS
A-902	ARCHITECTURAL DETAILS
A-903	ARCHITECTURAL DETAILS
A-911	ARCHITECTURAL DETAILS
A-912	ARCHITECTURAL DETAILS - ROOF
S-101	SHEET INDEX, ABBREVIATIONS & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	FOUNDATION PLAN - MID-CENTURY MODERN
S-202	ROOF FRAMING PLAN - MID-CENTURY MODERN
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-404	TYPICAL WOOD DETAILS
S-421	ROOF FRAMING DETAILS
S-422	ROOF FRAMING DETAILS

T24 - 201	ENERGY COMPLIANCE - PLAN 2A
T24 - 202	ENERGY COMPLIANCE - PLAN 2A
T24 - 203	ENERGY COMPLIANCE - PLAN 2A
T24 - 204	ENERGY COMPLIANCE - PLAN 2A
T24 - 213	ENERGY COMPLIANCE - PLAN 2
Grand total: 35	

## SPECIAL INSTRUCTIONS REQUIRED

OWNER/APPLICANT HAS COMPLETED SPECIAL INSPECTION FORM

OWNER/APPLICANT SIGNATURE: \_\_\_\_\_  
SEE SHEET S-103 FOR REQUIRED SPECIAL INSPECTIONS

A REGISTERED DESIGN PROFESSIONAL SHALL COMPLETE THE COUNTY OF SAN LUIS OBISPO STATEMENT OF REQUIRED SPECIAL INSPECTIONS CERTIFICATE (FORM BLD-1032) PRIOR TO PERMIT ISSUANCE. IDENTIFY THE TYPE OF WORK REQUIRING SPECIAL INSPECTIONS IN THE PLANS AND THE INDIVIDUALS OR FIRMS RESPONSIBLE FOR THE SPECIAL INSPECTION ELEMENT(S). FURTHER INSTRUCTIONS ARE IDENTIFIED IN THE STATEMENT OF SPECIAL INSPECTION AGREEMENT (FORM BLD-1031).

## VICINITY MAP

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

(TO BE PROVIDED BY OWNER/APPLICANT)

## PROJECT GENERAL NOTES

THESE NOTES APPLY TO ALL PORTIONS, PHASES AND SUBCONTRACTORS OF THIS PROJECT.  
APPLICABLE CODES AND STANDARDS:  
• 2022 CALIFORNIA BUILDING CODE AND ITS APPENDICES AND STANDARDS.  
• 2022 CALIFORNIA PLUMBING CODE AND ITS APPENDICES AND STANDARDS.  
• 2022 CALIFORNIA MECHANICAL CODE AND ITS APPENDICES AND STANDARDS.  
• 2022 CALIFORNIA FIRE CODE AND ITS APPENDICES AND STANDARDS.  
• 2022 CALIFORNIA ELECTRICAL CODE AND ITS APPENDICES AND STANDARDS.  
• 2022 CALIFORNIA BUILDING ENERGY EFFICIENCY STANDARDS.  
• 2022 CALIFORNIA GREEN BUILDING STANDARDS CODE AND ITS APPENDICES AND STANDARDS.

CURRENT COUNTY OF SAN LUIS OBISPO MUNICIPAL CODE.

## PROJECT DIRECTORY

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

APPLICANT (TO BE PROVIDED BY OWNER/APPLICANT)

ADDRESS: \_\_\_\_\_  
PROJECT ADDRESS: \_\_\_\_\_  
CONTACT: \_\_\_\_\_  
EMAIL: \_\_\_\_\_  
PHONE: \_\_\_\_\_

ARCHITECT  
ADDRESS: 3765 S HIGUERA ST, SUITE 102  
SAN LUIS OBISPO, CA 93401  
CONTACT: RANDY RUSSOM  
EMAIL: RWRUSSOM@RRMDESIGN.COM  
PHONE: P:(805) 543-1794

## SUPPORTING DOCUMENTS

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

UTILITY, GRADING, AND DRAINAGE PLAN TO BE PROVIDED BY OTHERS.

PLEASE PROVIDE THE WASTE RECYCLE FORM FILLED OUT AND SIGNED PRIOR TO ISSUANCE. THE OWNER/APPLICANT/CONTRACTOR/PERSON DOING THE WORK IS REQUIRED TO RECYCLE 75% OF ALL PROJECT CONSTRUCTION AND DEMOLITION DEBRIS.

ENERGY COMPLIANCE  
PREPARED BY: \_\_\_\_\_ IN BALANCE GREEN CONSULTING  
DATE PREPARED: \_\_\_\_\_ SEPTEMBER 27, 2023  
JOB NUMBER: \_\_\_\_\_ CF1R-PRF-01E

HERS QII  
HERS VCHP: HERS RATER WILL NEED TO FOLLOW THE VERIFICATION AND TESTING PROTOCOL FOR THE VARIABLE CAPACITY HEAT PUMP CREDIT REQUIREMENTS, INCLUDING BUT NOT LIMITED TO VERIFIED REFRIGERANT CHARGE, VERIFIED MINIMUM HSPF AND EER/SEER, AND CAPACITY, DUCTLESS INDOOR UNITS AND THE COMPONENTS ARE WITHIN THE CONDITIONED ENVELOPE, AND AIRFLOW PROVIDED TO ALL HABITABLE SPACES (BDRMS AND LIVING SPACE).

## SOILS & FOUNDATIONS

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

NOTE: THESE PRE-APPROVED PLANS ARE INTENDED FOR FLAT LOTS, WITHOUT THE PRESENCE OF EXPANSIVE OR LIQUEFIABLE SOILS. THE BUILDING OFFICIAL SHALL MAKE THIS DETERMINATION PRIOR TO ISSUING THE PERMIT. A NOTE HAS BEEN ADDED TO THE FOUNDATION PLAN AND FOUNDATION NOTES TO CLEARLY OUTLINE THIS REQUIREMENT. PLEASE REFER TO GENERAL FOUNDATION NOTE 11 ON S-102 AND FOUNDATION PLAN NOTE 17 ON S-201.

## PROJECT INFORMATION

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

PROJECT SCOPE:  
1. CONSTRUCTION OF A NEW DETACHED ONE STORY 768 SF ACCESSORY DWELLING UNIT WITH 3 BEDROOMS AND 1 BATH.  
2. ALL SITE WORK WITHIN THE PROPERTY LINE.  
3. ALL THE WORK SHOWN IN THE DRAWINGS AND SPECIFICATIONS.

SITE INFORMATION (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO):

STREET ADDRESS: \_\_\_\_\_  
APN: \_\_\_\_\_  
ZONING: \_\_\_\_\_  
LOT SIZE: \_\_\_\_\_  
LAND USE: \_\_\_\_\_  
EXISTING USE: \_\_\_\_\_  
PROPOSED USE: \_\_\_\_\_

FLOOR AREA RATIO (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO)  
MAXIMUM FAR: \_\_\_\_\_  
PROPOSED FAR: \_\_\_\_\_

LOT COVERAGE (TO BE PROVIDED BY OWNER / APPLICANT)  
BUILDING: \_\_\_\_\_  
HARDSCAPE/PAVING: \_\_\_\_\_  
LANDSCAPE: \_\_\_\_\_

SETBACKS (TO BE PROVIDED BY COUNTY OF SAN LUIS OBISPO)  
FRONT: \_\_\_\_\_  
REAR: 4' - 0" (A.B. NO. 86)  
SIDES: 4' - 0" (A.B. NO. 86)

BUILDING INFORMATION:  
NUMBER OF STORIES: 1  
OCCUPANCY GROUP: R-3.1 & 2 FAMILY DWELLINGS  
CONSTRUCTION TYPE: VB  
SPRINKLERED: SEE FIRE SPRINKLER SECTION ON SHEET  
IF YES, A SEPARATE REVIEW/PERMIT IS REQUIRED FOR AUTO SPRINKLER SYSTEM DESIGN (CRC R313.3)  
MAX. HEIGHT ALLOWED (PER CBC TABLE 504.3) 16' - 0"  
MAX. HEIGHT PROPOSED: 16' - 0"  
ROOF RATING: REFER TO 'WILDLAND-URBAN INTERFACE FIRE AREA' AND 'FIRE HAZARD SEVERITY ZONE LEVEL'  
HIGH FIRE ZONE: \_\_\_\_\_

## UTILITIES

WATER AND SEWER SERVICE COUNTY OF SAN LUIS OBISPO UTILITIES  
ELECTRICAL SERVICE PACIFIC GAS & ELECTRIC  
GAS SERVICE PACIFIC GAS & ELECTRIC  
TELEPHONE SERVICE \_\_\_\_\_  
GARBAGE SERVICE \_\_\_\_\_  
CABLE SERVICE \_\_\_\_\_

## BUILDING AREAS

AREAS - PLAN 2	
PLAN 2 - GROUND FLOOR	768 SF
FRONT PORCH OPTION (EXTERIOR)	60 SF
SIDE PORCH OPTION (EXTERIOR)	40 SF

## PROJECT CHECKLIST

\*FOR PLANNING STAFF ONLY  
INITIAL WHEN SECTION HAS BEEN REVIEWED. STAFF INITIALS: \_\_\_\_\_

WASTE WATER  SEWER  SEPTIC  \*A SEPARATE REVIEW & PERMIT IS REQUIRED FOR SEPTIC.

## FIRE SPRINKLERS

DOES THE PRIMARY RESIDENCE HAVE NFPA 13D SPRINKLERS?  
 NO  YES \*IF YES, A SEPARATE REVIEW & PERMIT IS REQUIRED FOR AUTOMATIC SPRINKLER SYSTEM DESIGN (CRC R313.3)  
REQUIRED AT PROPOSED ADU: COUNTY OF SAN LUIS OBISPO FIRE SPRINKLERS SYSTEM REQUIREMENTS FOR ADU BLD-3044  
 NO (NOT REQUIRED IF THE PRIMARY RESIDENCE IS UNSPRINKLERED)  
 YES (REQUIRED IF THE PRIMARY RESIDENCE IS SPRINKLERED)

## FIRE SPRINKLERS NOTES

- IF FIRE SPRINKLERS ARE REQUIRED AT PROPOSED ADU THEN THE FOLLOWING NOTES APPLY.
- AUTOMATIC FIRE SPRINKLER SYSTEM - AN AUTOMATIC FIRE SPRINKLER SYSTEM SHALL BE INSTALLED AS PER NFPA 13D THE MOST CURRENT EDITION. DETAILED SPRINKLER PLANS SHALL BE SUBMITTED TO THE FIRE PREVENTION BUREAU AND APPROVED PRIOR TO INSTALLATION. PLANS AND INSTALLATION MUST BE BY A C16 LICENSED SPRINKLER CONTRACTOR.
- SECTION 903.2.1 GROUP R AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 SHALL BE PROVIDED THROUGHOUT ALL BUILDINGS WITH A GROUP R FIRE AREA. THIS INCLUDES SINGLE FAMILY DWELLINGS, MULTI-FAMILY DWELLINGS AND ALL RESIDENTIAL CARE FACILITIES REGARDLESS OF OCCUPANT LOAD.
- SECTION 903.2.1.1 ADDITIONS AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH 903.3 MAY BE REQUIRED TO BE INSTALLED THROUGHOUT STRUCTURES WHEN THE ADDITION IS MORE THAN 50% OF THE EXISTING BUILDING OR WHEN THE ALTERED BUILDING WILL EXCEED A FIRE FLOW OF 1,500 GALLONS PER MINUTE AS CALCULATED PER SECTION 507.3. THE FIRE CODE OFFICIAL MAY REQUIRE AN AUTOMATIC SPRINKLER SYSTEM BE INSTALLED IN BUILDINGS WHERE NO WATER MAIN EXISTS TO PROVIDE THE REQUIRED FIRE FLOW OR WHERE A SPECIAL HAZARD EXISTS SUCH AS: POOR ACCESS ROADS, GRADE, BLUFFS AND CANYON RIMS, HAZARDOUS BRUSH AND RESPONSE TIMES GREATER THAN 5 MINUTES BY A FIRE DEPARTMENT.
- SECTION 903.2.1.2 REMODELS OR RECONSTRUCTION AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN ACCORDANCE WITH SECTION 903.3 MAY BE REQUIRED IF THE SCOPE OF WORK INCLUDES SIGNIFICANT MODIFICATION TO THE INTERIOR AND/OR ROOF OF THE BUILDING, AND THE COST OF THE INSTALLATION DOES NOT EXCEED 15 PERCENT OF THE CONSTRUCTION COSTS OF THE REMODEL.
- LOCATION AND SIZE OF WATER SERVICE UNDERGROUND SHALL BE INSTALLED AS SHOWN ON APPROVED FIRE SPRINKLER PLANS. A MINIMUM 1 INCH WATER SHALL BE INSTALLED.
- A FIRE UNDERGROUND FLUSH CERTIFICATION SHALL BE REQUIRED AT FINAL INSPECTION.
- A HYDRO INSPECTION OF THE FIRE SPRINKLER SYSTEM IS REQUIRED PRIOR TO FRAME INSPECTION. ONLY THE NEW PIPING SHALL BE TESTED.

## ONSITE PARKING REQUIRED

- NONE, EXCEPTION USED:
  - THE ADU IS LOCATED WITHIN 1/2 MILE OF PUBLIC TRANSIT.
  - OFF STREET PARKING PERMITS ARE REQUIRED BUT NOT OFFERED TO THE OCCUPANT OF THE ADU.
  - WHEN THERE IS A CAR SHARE VEHICLE LOCATED WITHIN ONE BLOCK OF THE ADU.
- ONE PARKING SPACE (STUDIO OR 1-BEDROOM ADU)
- TWO PARKING SPACES (2-BEDROOM ADU)

## WILDLAND-URBAN INTERFACE FIRE AREA

- PORTIONS OF THE COUNTY OF SAN LUIS OBISPO COUNTY ARE LOCATED IN WITHIN THE 'WILDLAND-URBAN INTERFACE FIRE AREA (AS DEFINED BY CRC R317.2).
  - AREA DEFINED BY STATE AS A "FIRE HAZARD SEVERITY ZONE" (FHSZ).
  - AREA DESIGNATED BY ENFORCING AGENCY TO BE AT A SIGNIFICANT RISK FROM WILDFIRES.
- MORE INFORMATION ABOUT FIRE HAZARD SEVERITY ZONES, INCLUDING AN INTERACTIVE MAP, BUILDING MATERIALS LISTINGS, AND WUI REQUIREMENTS CAN BE FOUND ON THE OFFICE OF THE STATE FIRE MARSHAL WEBSITE (HTTPS://OSFM.FIRE.CA.GOV).
- AN ADU WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE CRC SECTION R317.
- THIS PROTOTYPE PLAN PROVIDES DESIGNS THAT COMPLY WITH THE PROVISIONS REQUIRED BY THE CRC SECTION R337.

## FIRE HAZARD SEVERITY ZONE LEVEL

- NONE  MODERATE  HIGH  VERY HIGH
- IN ACCORDANCE WITH THE CFC SECTION 4904, STRUCTURES LOCATED IN THE VERY HIGH FIRE HAZARD SEVERITY ZONE SHALL PROVIDE & MAINTAIN A FUEL MODIFICATION ZONE. FUEL MODIFICATION ZONES: THE APPLICANT SHALL PROVIDE & MAINTAIN FIRE/FUEL BREAKS TO THE SATISFACTION OF THE LOCAL FIRE DEPARTMENT. FIRE/FUEL BREAKS SHALL BE SHOWN ON THE GRADING, MAP, AND BUILDING PLANS.

## OPTIONS SELECTIONS

\*OWNER OR APPLICANT REQUIRED TO PROVIDE SELECTIONS FOR EACH OF THE FOLLOWING CATEGORIES. ADDITIONALLY, OWNER/APPLICANT TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & W.U.I. PRODUCT LISTING (WHEN APPLICABLE) IN THE MATERIALS LEGEND.  
NOTE: OWNER/APPLICANT TO STRIKE THROUGH UNSELECTED OPTIONS THROUGHOUT THE PLAN SET WHEN APPLICABLE FOR CLARITY.

TRUSS SELECTION (SELECT ONE)  
 A) RAISED CEILING TRUSS PACKAGE REF: 313098  B) FLAT CEILING TRUSS PACKAGE REF: 313097

FRONT PORCH (SELECT ONE)  A) FRONT (COVERED) PORCH  B) NO FRONT PORCH  
SIDE PORCH (SELECT ONE)  A) SIDE PORCH W/ SLIDING DOOR  B) NO SIDE PORCH

RAKE & EAVE DETAILS (SELECT ONE)  A) ENCLOSED  B) OPEN EXPOSED

EXTERIOR RAKES, EAVES, & PORCH SOFFITS & OVERHANGS MATERIALS (MARK ALL THAT APPLY)  
 A) 2X TOUNGE & GROOVED (SOLID SAWN LUMBER)  
 B) FIBER CEMENT SOFFIT PANELS  
 C) HARDBOARD SOFFIT PANELS  
 D) EXT. GRADE FIRE RETARDANT TREATED SHEATHING

WALL COVERINGS (MARK ALL THAT APPLY)  
NOTE: WALL COVERINGS TO MEET ALL REQUIREMENTS OF CRC R703.3 SEE CRC TABLE R703.3(1) FOR MIN. ATTACHMENT AND MIN. THICKNESS REQUIREMENTS.  
 E) FIBER CEMENT HORIZONTAL LAP SIDING  
 F) EXT. GRADE WOOD HORIZONTAL LAP SIDING

EXTERIOR TRIM ELEMENTS (SELECT ONE)  A) FIBER CEMENT  B) EXT. GRADE WOOD

BASE TRIM 24/A-901 (SELECT ONE)  A) YES  B) NO

EXTERIOR LIGHT (SELECT ONE)  A) LNC - MODERN  B) LUTEC BARN LIGHT

DOOR MATERIAL (SELECT ONE)  
 A) VINYL  B) FIBERGLASS  C) WOOD  D) ALUMINUM CLAD WOOD

WINDOW MATERIAL (SELECT ONE)  
 A) VINYL  B) FIBERGLASS  C) WOOD  D) ALUMINUM CLAD WOOD

DECORATIVE FAUX GABLE VENTS (SELECT ONE)  A) NO  B) YES LABEL LOCATIONS ON ELEV.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TITLE SHEET - PLAN 2A

DATE  
09/28/2023  
SHEET  
G-021



# CLIMATE ZONE




FIGURE 100.1-A—CALIFORNIA CLIMATE ZONES  
Climate Zones for Residential and Nonresidential Occupancies

## SECTION 100.1 – DEFINITIONS AND RULES OF CONSTRUCTION

# ABBREVIATIONS


A/C	AIR CONDITIONING	EXT	EXTERIOR	MAX	MAXIMUM	SF	SQUARE FOOT
ABV	ABOVE	FACP	FIRE ALARM CONTROL PANEL	MDF	MEDIUM DENSITY FIBERBOARD	SHT	SHEET
ACOUS	ACOUSTICAL	FAUJ	FORCED AIR UNIT	MECH	MECHANICAL	SHTHG	SHEATHING
ACT	ACOUSTICAL CEILING TILE	FAWP	FLUID APPLIED WATERPROOFING	MEMB	MEMBRANE	SIM	SIMILAR
ADA	AMERICANS WITH DISABILITIES ACT	FD	FLOOR DRAIN	MEP	MECHANICAL, ELECTRICAL, PLUMBING	SM	SHEET METAL
AFCI	ARC FAULT CIRCUIT INTERRUPTER	FDC	FIRE DEPARTMENT CONNECTION	MFR	MANUFACTURER	SPEC	SPECIFICATION
AFF	ABOVE FINISH FLOOR	FE	FIRE EXTINGUISHER	MIN	MINIMUM	SQ	SQUARE
AL	ALUMINUM	FEC	FIRE EXTINGUISHER CABINET	MISC	MISCELLANEOUS	SS	SOLID SURFACE
ALT	ALTERNATE	FF	FINISHED FLOOR ELEVATION	MO	MASONRY OPENING	SSTL	STAINLESS STEEL
ARCH	ARCHITECT(URAL)	FG	FINISHED GRADE	MTD	MOUNTED	STC	SOUND TRANSMISSION CLASS
BD	BOARD	FH	FIRE HYDRANT	MTL	METAL	STD	STANDARD
BDRM	BEDROOM	FHC	FIRE HOSE CABINET	N	NORTH	STL	STEEL
BET	BETWEEN	FIN	FINISH	NIC	NOT IN CONTRACT	STOR	STORAGE
BIT	BITUMINOUS	FIXT	FIXTURE	NO	NUMBER	STRUCT	STRUCTURAL
BLDG	BUILDING	FLR	FLOOR	NOM	NOMINAL	SUSP	SUSPENDED
BLKG	BLOCKING	FLUOR	FLOURESCENT	NTS	NOT TO SCALE	SV	SHEET VINYL
BLW	BELOW	FND	FOUNDATION	O.P.	OVERFLOW PIPE	SYM	SYMMETRICAL
BM	BEAM	FO	FACE OF	OC	ON CENTER	T	TREAD
BOT	BOTTOM	FOC	FACE OF CONCRETE	OD	OVERFLOW DRAIN	T&G	TONGUE & GROOVE
BUR	BUILT UP ROOF	FOF	FACE OF FINISH	OFF	OFFICE	TEL	TELEPHONE
CB	CATCH BASIN	FOIC	FURNISHED BY OWNER INSTALLED BY CONTRACTOR	OH	OPPOSITE HAND	TEMP	TEMPERED
CBG	CALIFORNIA BUILDING CODE	FOM	FACE OF MASONRY	OPG	OPENING	TEL	TELEPHONE
CEM	CEMENT	FOS	FACE OF STUD	OPP	OPPOSITE	TER	TERRAZZO
CFM	CUBIC FEET PER MINUTE	FRP	FIBERGLASS REINFORCED PANELS	(P)	PROPOSED	THK	THICK
CIP	CAST IN PLACE	FT	FOOT OR FEET	PERM	PERIMETER	THR	THRESHOLD
CJ	CONTROL JOINT	FTG	FOOTING	PERP	PERPENDICULAR	TJI	TRUSS JOIST I-JOIST
CL	CENTER LINE	GA	GUAGE, GAGE	PL	PLATE, PROPERTY LINE	TO	TOP OF
CLG	CEILING	GALV	GALVANIZED	PLAM	PLASTIC LAMINATE	TOS	TOP OF SLAB
CLO	CLOSET	GB	GRAB BAR	PLBG	PLUMBING	TOW	TOP OF WALL
CLR	CLEAR	GC	GENERAL CONTRACTOR	PLYWD	PLYWOOD	TRANS	TRANSFORMER
CMU	CONCRETE MASONRY UNIT	GFCI	GROUND FAULT CIRCUIT INTERRUPTER	PNL	PANEL	TV	TELEVISION
CO	CLEAN OUT	GWB	GYPSON BOARD	PP	POWER POLE	TYP	TYPICAL
COL	COLUMN	GYP	GYPSON	PR	PAIR	UFAS	UNIFORM FEDERAL ACCESSIBILITY STANDARDS
CONC	CONCRETE	HB	HOSE BIBB	PRTN	PARTITION	UG	UNDERGROUND
CONST	CONSTRUCTION	HC	HOLLOW CORE	PSF	POUNDS PER SQUARE FOOT	UNFIN	UNFINISHED
CONT	CONTINUOUS	HDWD	HARDWOOD	PSI	POUNDS PER SQUARE INCH	UNO	UNLESS NOTED OTHERWISE
CONTR	CONTRACTOR	HDWR	HARDWARE	PSL	PARALLEL STRAND LUMBER	UV	ULTRAVIOLET
CPT	CARPET	HGT	HEIGHT	PT	PRESSURE TREATED	VCT	VINYL COMPOSITION TILE
CT	CERAMIC TILE	HM	HOLLOW METAL	PTD	PAINTED	VERT	VERTICAL
CTR	CENTER	HORIZ	HORIZONTAL	PV	PHOTO VOLTAIC	VIF	VERIFY IN FIELD
DBL	DOUBLE	HVAC	HEATING, VENTILATION, A/C	PVC	POLYVINYL CHLORIDE	VTR	VENT TERMINATION PIPE
DF	DRINKING FOUNTAIN	ID	INSIDE DIAMETER	PVMT	PLYWOOD	VWC	VINYL WALL COVERING
DIA	DIAMETER, DIAPHRAGM	IIC	IMPACT INSULATION CLASS	QTY	QUANTITY	W	WEST
DIM	DIMENSION	IN	INCH	R	RADIUS, RISER	W/	WITH
DN	DOWN	INCAND	INCANDESCENT	RB	RUBBER BASE	WD	WASHER DRYER
DR	DOOR	INSUL	INSULATION, INSULATED	RCP	REFLECTED CEILING PLAN	WO	WITHOUT
DS	DOWN SPOUT	INT	INTERIOR	RD	ROOF DRAIN	WC	WATERCLOSET
DTL	DETAIL	JC	JANITORS CLOSET	REF	REFRIGERATOR	WD	WOOD
DW	DISHWASHER	JT	JOINT	REIN	REINFORCED	WDW	WINDOW
DWG	DRAWING	LAM	LAMINATE	REQD	REQUIRED	WH	WATER HEATER
(E)	EXISTING	LAV	LAVATORY	RH	RIGHT HAND	WI	WROUGHT IRON
EA	EACH	LBS	POUNDS	RM	ROOM	WIN	WINDOW
EJ	EXPANSION JOINT	LEED	LEADERSHIP IN ENERGY AND ENVIRONMENTAL DESIGN	RO	ROUGH OPENING	WP	WATERPROOF(ING)
EL	ELEVATION	LF	LINEAR FEET	RTU	ROOF TOP UNIT (MECH)	WR	WEATHER RESISTIVE
ELEV	ELEVATION	LIN	LINEN CLOSET	S	SOUTH	WRB	WATER RESISTIVE BARRIER
ELEC	ELECTRIC	LINO	LINOLEUM	SAFB	SOUND ATTENUATION FIBER BATT	WSCT	WAINSCOT
ENCL	ENCLOSURE	LT(G)	LIGHT(ING)	SAWP	SELF ADHERING WATERPROOFING	WT	WEIGHT
EQ	EQUAL	LVL	LAMINATED VENEER LUMBER	SC	SCUPPER/SOLID CORE	WWF	WELDED WIRE FABRIC
EQUIP	EQUIPMENT	LVT	LUXURY VINYL TILE	SCHED	SCHEDULE	YD	YARD
EXH	EXHAUST	LW	LIGHTWEIGHT	SEAL	SEALANT		
EXP	EXPANSION			SECT	SECTION		



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

# FIRE HAZARD SEVERITY ZONES

DISCLAIMER: MAP IS FOR GENERAL REFERENCE ONLY. TO ACQUIRE ACCURATE INFORMATION FOR FIRE HAZARD SEVERITY IN SITE SPECIFIC LOCATION, REFER TO THE CALIFORNIA DEPARTMENT OF FORESTRY AND FIRE PROTECTION.



# SYMBOLS

VIEW NUMBER: 20  
VIEW TITLE: View Name  
SCALE: 1/8" = 1'-0"

VIEW SHEET LOCATION: A-101  
REFERENCE SHEET LOCATION: A-202

LEVEL DESIGNATION: Name 0'-0"

LEVEL ELEVATION: BUILDING LEVELS

SYMBOLS:

- NORTH ARROW
- GRID REFERENCE
- DOOR W/CLOSER
- BUILDING ELEVATION
- SECTION REFERENCE
- DOOR TAG
- INTERIOR ELEVATIONS
- DETAIL REFERENCE
- WINDOW TAG
- REVISION TAG
- CENTERLINE
- WALL TAG
- MATERIAL TAG

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

INDEX, ABBREVIATIONS, &  
SYMBOLS

DATE  
09/28/2023  
SHEET

G-102








# SITE PLAN TO BE PROVIDED BY APPLICANT

## SITE PLAN LEGEND



## SITE PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION.

## SITE PLAN CHECKLIST


- ELECTRICAL PANEL:**
- OPTION 1 -** NEW ELECTRICAL MAIN PANEL WITH 225 AMP MINIMUM BUSBAR RATING
  - OPTION 2 -** A NEW ELECTRICAL SUBPANEL CONNECTS TO THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME WITH A 225 AMP MINIMUM BUSBAR RATING. A SEPARATE ELECTRICAL PERMIT SHALL BE PULLED FOR THE ELECTRICAL MAIN PANEL OF THE PRIMARY HOME. ELECTRICAL LOAD CALCULATIONS IS REQUIRED.
- IS THE NEW ADU IS 5' - 0" OR LESS TO ANY PROPERTY LINE AND/OR ADU IS 10' - 0" OR LESS FROM ANY ADJACENT BUILDING OR STRUCTURE?**
- NO**
  - YES;** IF YES, 1-HR FIRE RATED WALL, 1-HR RATED ROOF, AND 1-HR RATED FIRE PROJECTS REQUIRED. SEE DETAILS: 21/A-903 & 24/A-903
- NOTE:** WHERE 1-HR FIRE-RESISTANCE RATED PROJECTIONS REQUIRED (NON-SPRINKLERED & FIRE SEPARATION DISTANCE ≥2'-0" - <5'-0")
- TABLE 302.1(1)**  
A. THE FIRE-RESISTANCE RATING SHALL BE PERMITTED TO BE REDUCED TO 0 HOURS ON THE UNDERSIDE OF THE EAVE OVERHANG IF FIREBLOCKING IS PROVIDED FROM THE WALL TOP PLATE TO THE UNDERSIDE OF THE ROOF SHEATING
- NOTE:**
    - A. A SEPARATE PERMIT FOR ONSITE WASTEWATER SYSTEM WILL BE REQ'D.
    - B. SOILS REPORT TO BE PROVIDED BY OTHERS.
    - C. UTILITY, GRADING, AND DRAINAGE PLAN TO BE PROVIDED BY OTHERS.
    - D. PROVIDE WASTE RECYCLE FORM FILLED OUT AND SIGNED PRIOR TO ISSUANCE. THE OWNER/APPLICANT/CONTRACTOR/PERSON DOING THE WORK IS REQUIRED TO RECYCLE 75% OF ALL PROJECT CONSTRUCTION AND DEMOLITION DEBRIS.
  - FOOTPRINT OF ALL EXISTING AND PROPOSED BUILDINGS**  
PLOT THE PROPOSED ADU BUILDING FOOTPRINT ALONG WITH ANY OTHER EXISTING BUILDINGS ONSITE. THIS INCLUDES ALL STRUCTURES / PORCHES / GAZEBOS. IF AN OPTIONAL COVERED PATIO IS SELECTED, PLEASE PLOT THAT AS WELL.
  - AREA OF EXISTING BUILDING**  
INDICATE THE SQUARE FOOTAGE OF THE EXISTING HOUSE.
  - FOOTPRINT OF PROPOSED ADU**  
REFER TO LEGEND FOR FOOTPRINT AT 10'=1" SCALE
  - DRAWING SCALE**  
SITE PLAN SHOULD BE DRAWN TO A MEASURABLE SCALE.
  - PROPERTY LINES**  
SHOW OUTLINE OF PROPERTY USING DASHED LINE IN LEGEND. INDICATE THE BEARING AND DISTANCE OF THE PROPERTY LINE.
  - LABEL YARDS**  
LABEL FRONT, REAR, SIDE YARDS, AS WELL AS DRIVEWAYS, PATHWAYS AND ANY OTHER HARDSCAPE.
  - SETBACKS**  
DIMENSION THE DISTANCE BETWEEN BUILDINGS AND PROPOERTY LINES, AS WELL AS BUILDINGS TO OTHER STRUCTURES. SETBACKS TO SIDE AND REAR PROPERTY SIDE SHALL BE A MINIMUM OF (4' - 0"). PROPOSED ADU SHALL BE LOCATED A MINIMUM OF (10' - 0") FROM EXISTING STRUCTURES.
  - EASEMENTS**  
REFER TO LEGEND. MUST INCLUDE ALL APPLICABLE EASEMENTS. SETBACK PROPOSED STRUCTURE HSALL COMPLY WITH EASEMENT REQUIREMENTS.
  - LOCATION OF RAIN WATER LEADERS**  
THE ROOF DRAINS SHOULD DRAIN AWAY FROM THE PROPERTY LINES AND INTO THE LANDSCAPE AREA.
  - LABEL STREETS & SIDEWALKS**
  - LABEL ADU AND ADDRESS LOCATION**  
ADU SHALL HAVE THE SAME ADDRESS AS THE PRIMARY RESIDENCE. THE ADDRESS IDENTIFICATION SHALL BE LEGIBLE AND PLACED IN A POSITION THAT IS VISIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. ADDRESS IDENTIFICATION CHARACTERS SHALL CONTRAST WITH THEIR BACKGROUND. ADDRESS SHALL COMPLY WITH CRC SECTION R319.
  - DIMENSION BUILDING SEPARATION**  
DIMENSION THE DISTANCE BETWEEN THE PROPOSED ADU AND ANY EXISTING STRUCTURES
  - ALL EXISTING/PROPOSED PLANTINGS AND HARDSCAPE SHOWN**
  - LOT COVERAGE CALCULATION**  
TOTAL FOOTPRINT AREA FOR STRUCTURES ON SITE / LOT AREA
  - SWIMMING POOLS**  
ALL EXISTING SWIMMING POOLS SHALL BE SHOWN ON THE SITE PLAN AND SHALL HAVE 10' - 0" MINIMUM SETBACK TO THE NEW ADU STRUCTURE.
  - PORCHES**  
THERE SHALL BE NO MORE THAN 30 INCHES MEASURED VERTICALLY TO THE FLOOR OR GRADE BELOW (INCLUDING FLOORS, STAIRS, RAMPS, AND LANDINGS) ANYWHERE MEASURED LESS THAN 36 INCHES HORIZONTALLY TO THE EDGE OF THE PORCH/SLAB/SURFACE OF THE RAIL. INSECT SCREENING SHALL NOT BE CONSIDERED AS A GUARD.
  - LOCATION OF EXISTING UTILITIES**  
UTILITIES, POLES, SEWER, DRAINS, ELECTRICAL, GAS METERS AND LINES AND ANY PHOTOVOLTAIC.
  - LOCATION OF PROPOSED UTILITIES**  
SANITARY SEWER FROM ADU TO EXISTING SEWER. SEWER LINE TO THE PROPOSED ADU SHALL BE CONNECTED TO THE MAIN LATERAL AT THE PROPERTY LINE OR BEHIND THE SIDEWALK. LATERAL POINT OF CONNECTION INCLUDING REQUIRED CLEANOUTS, WATER LINE TO ADU, ELECTRIC TO ADU INCLUDING ANY NEW METERS OR SUBPANELS, GAS LINE TO ADU.
    - A. TOTAL DEVELOPED LENGTH OF GAS SYSTEM FROM METER / REGULATOR TO MOST REMOTE GAS OUTLET.
    - B. TOTAL DEVELOPED LENGTH FOR EACH GAS BRANCH AND ITS CORRESPONDING DEMAND.
    - C. SHOW MECHANICAL, PLUMBING, AND KITCHEN GAS APPLIANCE LOCATION AND ITS DEMAND FACTORS.
    - D. SHOW THE LOCATION AND AMPACITY OF THE ELECTRICAL PANEL SERVING THE ADU. VERIFY COMPLIANCE WITH ALL APPLICABLE REQUIREMENTS OF THE 2022 CEC.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

**NOTE: THIS IS AN EXAMPLE SITE PLAN. EXACT LAYOUT, DIMENSIONS, AND BEARINGS SHALL BE PROVIDED BY OWNER/APPLICANT. (E) EXISTING (N) NEW**



**1 SITE PLAN EXAMPLE**  
SCALE: 1" = 20'-0"

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
SAN LUIS OBISPO, CA

**ARCHITECTURAL SITE PLAN**  
**(EXAMPLE & INSTRUCTIONS)**

**SITE PLAN**

SCALE:



DATE  
09/28/2023

SHEET

AS-102



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

FLOOR PLAN

DATE  
09/28/2023  
SHEET

A2-101

**FLOOR PLAN GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO STRUCTURAL PLANS FOR FURTHER INFORMATION.
- REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION IF PROVIDED.
- REFER TO MECHANICAL PLANS, DRAWINGS OR REPORTS FOR FURTHER INFORMATION.
- ALL FURNITURE AND EQUIPMENT IS BY OWNER AND IS SHOWN FOR COORDINATION PURPOSES ONLY.
- DIMENSIONS ARE TO FACE OF FRAMING UNLESS SPECIFICALLY NOTED OTHERWISE.
- PROVIDE ADEQUATE BLOCKING IN WALLS FOR CABINETS AND OTHER WALL MOUNTED ACCESSORIES INCLUDING BUT NOT LIMITED TO HANDRAILS, SHELVING AND BATHROOM FIXTURES.
- DOOR AND WINDOW DIMENSIONS ARE CENTERED AT OPENINGS.
- WHERE DOOR IS LOCATED WITHOUT DIMENSION AT THE CORNER OF A ROOM IT SHALL BE 4" FROM FACE OF FRAMING OF ADJACENT WALL TO ROUGH DOOR OPENING.
- WHERE RECESSED FIXTURES OCCUR IN WALLS OR HORIZONTAL ASSEMBLIES, THE FIRE RATING OF THOSE ASSEMBLIES SHALL BE MAINTAINED.
- AT ALL PENETRATIONS AND INTERSECTIONS OF FIRE-RATED PARTITIONS, PROVIDE FIRE SEALANT AND/OR FIRE STOPPING TO MAINTAIN CONTINUITY OF PARTITION RATING.
- PER CRC R311.3 FLOORS OR LANDINGS AT EXTERIOR DOORS SHALL BE AT LEAST AS WIDE AS DOOR SERVED AND SHALL PROVIDE A LENGTH IN THE DIRECTION OF TRAVEL EQUAL TO 36 INCHES MINIMUM. SLOPE OF EXTERIOR LANDINGS SHALL NOT EXCEED 1/4" PER FOOT (2% SLOPE).
- PER CRC 327.1.1 REINFORCEMENT FOR GRAB BARS SHALL BE PROVIDED IN AT LEAST ONE BATHROOM. 1. REINFORCEMENT SHALL BE SOLID LUMBER OR OTHER CONSTRUCTION MATERIALS APPROVED BY THE ENFORCING AGENCY. 2. REINFORCEMENT SHALL NOT BE LESS THAN 2X8 INCH NOMINAL LUMBER OR OTHER MATERIAL PROVIDING EQ. HT. AND CAPACITY. REINFORCEMENT ABOVE THE FINISHED FLOOR FLUSH WITH THE WALL FRAMING. 3. WATER CLOSET REINFORCEMENT SHALL BE INSTALLED ON BOTH SIDE WALLS OF THE FIXTURE, OR ONE SIDE WALL AND THE BACK WALL. 4. SHOWER REINFORCEMENT SHALL BE CONTINUOUS WHERE WALL FRAMING IS PROVIDED. 5. BATHTUB AND COMBINATION BATHTUB/SHOWER REINFORCEMENT SHALL BE CONTINUOUS ON EACH END OF THE BATHTUB AND THE BACK WALL. ADDITIONALLY, BACK WALL REINFORCEMENT FOR A LOWER GRAB BAR SHALL BE PROVIDED WITH THE BOTTOM EDGE LOCATED NO MORE THAN 6 INCHES ABOVE THE BATHTUB RIM.

**DOOR GENERAL NOTES**

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO PLANS FOR LOCATION OF DOORS.
- VERIFY ROUGH OPENING SIZE WITH DOOR MANUFACTURER SPECIFICATIONS PRIOR TO CONSTRUCTION.
- CONTRACTOR TO VERIFY ACTUAL DOOR SIZE TO FIT FINISH OPENING PRIOR TO FABRICATION OF DOOR AND FINISH OPENING.
- INSTALL PER MANUFACTURERS WRITTEN INSTRUCTIONS.
- REFER TO DOOR TYPES LEGEND FOR GLAZING.
- REFER TO T24 REPORT FOR GLAZING ENERGY REQUIREMENTS.
- GLAZING IN DOORS SHALL BE TEMPERED PER SECTION R308.4.1. PANES INDICATED IN DOOR LEGEND WITH (T).


**DOOR REMARKS**

- EXTERIOR DOOR.
- GLAZING PER DOOR TYPES. REFER TO GENERAL DOOR NOTE #8
- PROVIDE 100 SQ INCHES OF VENTING IN DOOR OR BY OTHER APPROVED MEANS.
- OPTIONAL DOOR.

**DOOR SCHEDULE**

NO.	TYPE	DOOR		REMARKS
		WIDTH	HEIGHT	
101	A1	3'-0"	6'-8"	1, 2
102	A2	2'-0"	6'-8"	1, 3
103	D	6'-0"	6'-8"	
104	C	3'-0"	6'-8"	
105	D	4'-0"	6'-8"	
106	C	3'-0"	6'-8"	
107	C	3'-0"	6'-8"	
108	D	4'-0"	6'-8"	
109	C	3'-0"	6'-8"	
110	E	2'-8"	6'-8"	3
111	B	6'-0"	6'-8"	2, 4


**DOOR LEGEND**



**KEYNOTES**

- A01 30" WIDE FREE STANDING ELECTRIC RANGE OVEN. VENT TO EXTERIOR, STAINLESS STEEL.
- A05 REFRIGERATOR LOCATION. PROVIDE 42" SPACE WITH ROUGH PLUMBING FOR ICE MAKER (RECESS IN WALL).
- A06 STACKED WASHER/DRYER MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
- B02 20" SINGLE COMPARTMENT UNDER-MOUNT KITCHEN SINK W/ GARBAGE DISPOSAL. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEET.
- B04 LAVATORY SINK. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS.
- B05 WATER CLOSET. REFER TO WATER EFFICIENCY REQUIREMENTS ON CALGREEN CODE NOTES SHEETS. REQ. AGING-IN-PLACE BLOCKING. SEE DETAIL 54/A-901.
- B06 32" x 60" x 72" TUB AND SHOWER COMBINATION. MODEL BY BUILDER. PROVIDE SHOWER ROD. REQ. AGING-IN-PLACE BLOCKING. SEE DETAIL 44/A-901.
- B18 ELECTRIC PANEL, 100AMP 240V.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- B47 40 GALLON HEAT PUMP WATER HEATER. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- C01 SINGLE WOOD SHELF AND POLE.
- C08 12" DEEP UPPER CABINET
- C14 TOWEL BAR. +54 INCHES ABOVE FLOOR. PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHMENTS
- C16 MIRROR. THE LENGTH OF THE VANITY OR PEDESTAL X 80" AFS. UNO. VERIFY WITH THE ELECTRICAL PLAN FOR LOCATION OF OUTLETS WHICH REQUIRE A CUT-OUT. PROVIDE 2X6 BACKING AT BATHROOM WALL ATTACHMENTS
- C20 PANTRY CABINET. PAINTED OPEN WOOD SHELVING
- M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.
- X01 OPTIONAL CABINET
- X27 OPTIONAL DISHWASHER

**WALL LEGEND**



NOTE: SEE MANUFACTURER'S PRODUCT LISTINGS FOR IMPROVED SOUND AND/OR MOISTURE/MOLD/MILDEW-RESISTANT PERFORMANCE. VISIT GYPSUM.ORG FOR MORE INFORMATION.

**WINDOW GENERAL NOTES**

- REFER TO GENERAL NOTES ON SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
- REFER TO FLOOR PLANS FOR WINDOW LOCATIONS.
- CONTRACTOR TO VERIFY EXACT ROUGH OPENING SIZES PRIOR TO FABRICATION OF ROUGH OPENINGS.
- INSTALL PER MANUFACTURERS WRITTEN INSTRUCTIONS.
- REFER TO ENERGY COMPLIANCE REPORTS FOR U-FACTOR, SHGC AND ADDITIONAL WINDOW REQUIREMENTS.
- ALL GLAZING IS DOUBLE PANE WITH A MINIMUM OF ONE TEMPERED PANE UNLESS OTHERWISE NOTED.
- EGRESS WINDOWS SHALL HAVE A CLEAR OPENING WITH A MAX. SILL HEIGHT OF 44" AFF. MIN NET CLEAR OPENING FOR EMERGENCY ESCAPE SHALL BE 5.7 S.F. EXCEPTION: MIN 5.5 S.F. AT GROUND FLOOR. MINIMUM NET CLEAR OPENING DIMENSIONS: HEIGHT: 24"; WIDTH: 20"
- GLAZING IN WALLS ADJACENT TO BATHTUB / SHOWER WHERE THE BOTTOM EXPOSED EDGE OF THE GLAZING IS LESS THAN 60" MEASURED VERTICALLY ABOVE ANY STANDING OR WALKING SURFACE SHALL BE SAFETY GLAZING. [CRC SEC. R308.4.5]

**WINDOW REMARKS**



- REQUIRED EGRESS WINDOW. REFER TO GENERAL NOTE #7 FOR ADDITIONAL INFORMATION.
- HAZARDOUS LOCATION. WINDOW INCLUDES BOTH PANES TEMPERED GLAZING.
- MULLED WINDOW ASSEMBLY.
- OPTIONAL WINDOW.
- OBSCURE OPTIONAL. VERIFY WITH OWNER/APPLICANT.

**WINDOW SCHEDULE**

NO.	TYPE	SIZE		HEAD HEIGHT	REMARKS
		WIDTH	HEIGHT		
101	B	5'-0"	5'-0"	6'-8"	1
102	B	5'-0"	5'-0"	6'-8"	1
103	B	5'-0"	5'-0"	6'-8"	1
104	B	3'-0"	2'-0"	6'-8"	2, 5
105	B	3'-0"	3'-0"	6'-8"	
106	B	6'-0"	5'-0"	6'-8"	
107	B	5'-0"	5'-0"	6'-8"	
108	B	4'-0"	5'-0"	6'-8"	2

NOTE: PLEASE CROSS THROUGH THE CLIMATE ZONE THAT IS NOT APPLICABLE  
CLIMATE ZONE 4 (C24) U-0.30 AND SHGC-0.23  
CLIMATE ZONE 5 (C25) U-0.30 AND SHGC-0.35

**WINDOW LEGEND**



**1 FLOOR PLAN**



A1-201 A2-101 SCALE: 1/4" = 1'-0"

**3 NO FRONT PORCH OPTION**

A1-201 A2-101 SCALE: 1/4" = 1'-0"

**2 OPTIONAL SIDE PORCH**

A1-201 A2-101 SCALE: 1/4" = 1'-0"








THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### GENERAL MEP NOTES

1. REFER TO ELECTRICAL NOTES ON SHEET G-101.
2. REFER TO MECHANICAL NOTES ON SHEET G-101.
3. REFER TO PLUMBING NOTES ON SHEET G-101.
4. REFER TO TITLE 24 COMPLIANCE NOTES ON SHEET G-101.
5. EXTERNALLY MOUNTED HEATING/COOLING UNITS SHALL BE SCREENED IF THEY ARE VISIBLE FROM A PUBLIC STREET.
6. ALL SMOKE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP, AND ALL SMOKE ALARMS MUST BE INTERCONNECTED AND SOUND AN ALARM CLEARLY AUDIBLE IN ALL BEDROOMS.
7. ALL CARBON MONOXIDE ALARMS TO BE HARD-WIRED WITH A BATTERY BACK-UP, AND ALL CARBON MONOXIDE ALARMS MUST BE INTERCONNECTED AND SOUND AN ALARM CLEARLY AUDIBLE IN ALL BEDROOMS.


### KEYNOTES

- A01 30" WIDE FREE STANDING ELECTRIC RANGE. VENT TO EXTERIOR, STAINLESS STEEL.
- A06 STACKED WASHER/DRYER MACHINE LOCATION. PROVIDE WASTE AND WATER IN RECESSED WALL BOX. PROVIDE DRYER VENT. VENT TO OUTSIDE AIR.
- B18 ELECTRIC PANEL, 100AMP 240V.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- B47 40 GALLON HEAT PUMP WATER HEATER. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION.
- B48 FAN COIL. REFER TO PLANS FOR LOCATION OF OUTDOOR CONDENSING UNIT. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE OUTLET.
- X27 OPTIONAL DISHWASHER



### 2 FINISH PLAN

A1-201 | A2-111 | SCALE: 1/4" = 1'-0"



### 1 ELECTRICAL PLAN


A1-201 | A2-111 | SCALE: 1/4" = 1'-0"

### FINISH PLAN GENERAL NOTES

1. REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS.
2. REFER TO ELECTRICAL PLANS FOR FURTHER INFORMATION.
3. REFER TO PLUMBING PLANS FOR FURTHER INFORMATION.
4. REFER TO DETAILS FOR FLOOR/CEILING ASSEMBLIES AND INTERIOR FINISH DETAILS.
5. ALL HARD SURFACE FLOORING SHALL BE SLIP RESISTANT AND MEET THE ANSI A326.3 STANDARD FOR MEASURING THE DYNAMIC COEFFICIENT OF FRICTION (DCOF).
6. ALL FLOORING MATERIALS SHALL COMPLY WITH CBC SEC. 804.1.
7. ALL WALL AND CEILING FINISHES SHALL COMPLY WITH CBC TABLE 803.13 FOR MAXIMUM FLAME SPREAD AND SMOKE DENSITY.

FINISH SCHEDULE PLAN 2				
NAME	FLOOR	WALL	CEILING	NOTES
LIVING	LVP	GWB	GWB	
KITCHEN	LVP	GWB	GWB	WR GWB BEHIND KITCHEN COUNTER
BATH 1	CT	WR GWB	WR GWB	AT CERAMIC TILE IN TUB/SHOWER AREAS, PROVIDE BACKER BOARD PER CRC TABLE R702.4.2
HALLWAY	LVP	GWB	GWB	
BED 3	CPT	GWB	GWB	
CL. 1	CPT	GWB	GWB	
BED 2	CPT	GWB	GWB	
CL. 2	CPT	GWB	GWB	
BED 1	CPT	GWB	GWB	
CL. 3	CPT	GWB	GWB	
LAUNDRY	LVP	GWB	GWB	
WH	EC	GWB	GWB	

### FINISH LEGEND



### VENTILATION SUMMARIES


1) LOCAL EXHAUST VENTILATION			
ROOM	OPTION A	OPTION B	
<b>BATHROOM</b>			
BATHROOM FAN FLOW (cfm)	50 CFM	50 CFM	
DUCT TYPE	FLEX DUCT	SMOOTH DUCT	
DUCT SIZE (in)	4"	4"	
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	105'	
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.			
<b>KITCHEN</b>			
KITCHEN FAN FLOW (cfm)	100 CFM	80 CFM	
DUCT TYPE	FLEX DUCT	SMOOTH DUCT	
DUCT SIZE (in)	5"	5"	
MAX. ALLOWABLE DUCT LENGTH (ft)	35'	85'	
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 3 SONES.			
2) WHOLE BUILDING VENTILATION			
PER ASHRAE STANDARD 62.2, CEC EQUATION 150.0-B			
BUILDING FAN FLOW (cfm)	80 CFM	80 CFM	
DUCT TYPE	FLEX DUCT	SMOOTH DUCT	
DUCT SIZE (in)	5"	4"	
MAX. ALLOWABLE DUCT LENGTH (ft)	70'	35'	
THIS EXHAUST FAN IS REQUIRED TO BE RATED FOR SOUND AT A MAX. OF 1 SONE.			
THIS EXHAUST FAN IS REQUIRED TO OPERATE CONTINUOUSLY TO ENSURE CONTINUOUSLY TO ENSURE INDOOR AIR QUALITY.			

**WHOLE DWELLING UNIT MECHANICAL VENTILATION**  
 PER SECTION 150.0(O)(C)(i) [ASHRAE 62.2-4.1.2]  
**3 BED - MINIMUM CUBIC FEET PER MINUTE (CFM)** (Equation 150.0-B)  
 $Q_{tot} = 0.03A_{floor} + 7.5(N_{br} + 1)$   $0.03(768 \text{ sf}) + 7.5(4) = 53.04 \text{ CFM} < 80 \text{ CFM}$

**EFFECTIVE ANNUAL AVERAGE INFILTRATION RATE**  
 PER SECTION 150.0(O)(C)(ii)  
 a. 1. (Equation 150.0-C)  $Q_{50} = Vdu(x) 2 \text{ ACH50} / 60 \text{ minutes}$   
 a. 2. (Equation 150.0-D)  $Q_{50} = Vdu(x) \text{ Verified ACH50} / 60 \text{ minutes}$   
 b. (Equation 150.0-E)  $Q_{tot} = 0.052(x) Q_{50} \times wsf \times [H/Hr]^z$  [ASHRAE 62.2-4.1.2.1]

**REQUIRED MECHANICAL VENTILATION RATE**  
 AND REQUIRED MECHANICAL VENTILATION RATE PER 150.0(O)(C)(iii)  
 [ASHRAE 62.2-4.1.2]  
 (Equation 150.0-F)  $Q_{fan} = Q_{tot}(\phi) \phi(Q_{inf}(x) A_{ext})$


NOTE: SIZE, DESIGN, AND SELECTION OF HVAC EQUIPMENT SHALL BE PROVIDED FOR PROJECT BY ONE OF THE FOLLOWING:  
 A. HEAT LOSS AND GAIN PER "RESIDENTIAL LOAD CALCULATION" [ANSI/ACCA 2 MANUAL J - 2011, ASHRAE]  
 B. DUCT SIZING PER "RESIDENTIAL DUCT SYSTEMS" [ANSI/ACCA 1 MANUAL D - 2014, ASHRAE]  
 C. SELECTION PER "RESIDENTIAL EQUIPMENT SELECTION" [ANSI/ACCA 3 MANUAL S - 2014]



### 3 MECHANICAL PLAN

A1-201 | A2-111 | SCALE: 1/4" = 1'-0"

### LEGEND



COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 FINISH, MECHANICAL, &  
 ELECTRICAL PLANS

DATE  
 09/28/2023  
 SHEET  
 A2-111



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### RCP GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS.
- HEIGHT OF CEILINGS SHALL BE MEASURED FROM TOP OF SLAB OR FLOOR TO FINISH FACE OF GWB, U.N.O.
- REFER TO ELECTRICAL PLANS FOR LIGHT FIXTURE AND EXHAUST LOCATIONS.
- DIMENSIONS ARE TO THE FACE OF FRAMING UNLESS OTHERWISE NOTED.
- LABEL MATERIAL SELECTIONS ON ALL RAKES, EAVES, PORCH SOFFITS, & OVERHANGS (A, B, C...).

### KEYNOTES

- F03 22" X 30" MINIMUM ATTIC ACCESS. PROVIDED SWITCH AND OUTLET AT ATTIC FOR FAU. PERMANENTLY ATTACH R-38 OR GREATER INSULATION TO ATTIC ACCESS DOOR USING ADHESIVE OR MECHANICAL FASTENERS CMC 150.0 (a). PROVIDE GASKETED ATTIC ACCESS TO PREVENT AIR LEAKAGE CMC 150.0 (a)1.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE. BUILDING LINE BELOW.
- H12 ATTIC VENT (LOW). PAINT OR FINISH TO MATCH ROOF COLOR. SEE VENTING CALCS.\*
- H13 ATTIC VENT (HIGH). PAINT OR FINISH TO MATCH ROOF COLOR. SEE VENTING CALCS.\*
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4
- M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.

### MATERIALS LEGEND

GRAPHICS LEGEND: OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:

- ROOFING: SEE MATERIALS LEGEND ON ELEVATION SHEET FOR MORE INFORMATION. CLASS A ROOF REQ. BY WUI.
- INTERIOR CEILING FINISH, TYP. 5/8" GYP. INSTALL PER MFR RECOMMENDATIONS. NOTE: SEE MANUFACTURER'S PRODUCT LISTINGS FOR IMPROVED SOUND AND/OR MOISTURE/MOLD/MILDEW-RESISTANT PERFORMANCE PRODUCTS. VISIT GYPSUM.ORG FOR MORE INFORMATION.
- EXTERIOR EAVES, PORCH SOFFITS, & OVERHANGS
  - A) 2X TONGUE & GROOVED (SOLID SAWN LUMBER)
  - B) FIBER CEMENT SOFFIT PANELS
  - C) HARDBOARD SOFFIT PANELS
  - D) EXT. GRADE FIRE RETARDANT TREATED SHEATHING (LABEL SELECTION ON REFLECTED CEILING PLAN)

- NOTES:
- SOFFIT MATERIALS TO MEET REQ. OF CRC 337 & CRC 704.
  - INSTALL ALL MATERIALS, FASTENERS, & COMPONENTS PER MANUFACTURER'S SPECIFICATIONS & RECOMMENDATIONS
  - INSTALL ADDITIONAL BLOCKING AS NEEDED TO MEET ATTACHMENT REQUIREMENTS PER CRC TABLE R702.3.5
  - A PROJECT SITE WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE CRC SECTION R337. IF WUI APPROVED PRODUCTS ARE REQUIRED, PROVIDE SELECTED PRODUCT LISTINGS IN THE SPACES PROVIDED.

### ROOF PLAN & RCP LEGEND

- XX'-X" CEILING HEIGHT (SEE PLAN FOR ACTUAL HEIGHTS)
- X : 12 ROOF SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
- X : 12 CEILING SLOPE (REFER TO PLANS FOR ACTUAL SLOPE)
- 22"X30" MIN. ATTIC ACCESS PANEL (WHERE REQ.)
- DORMER STYLE ROOF VENT. SEE ROOF VENTING CALCULATIONS
- OUTLINE OF WALL BELOW
- GUTTER, CONNECT TO DOWNSPOUT; SEE DETAIL: 12/A-901
- APPROXIMATE LOCATION OF DOWNSPOUT/LEADER TO ROOF OR SPLASHBLOCK BELOW; SEE DETAILS.
- XX SF AVAILABLE SOLAR ZONE LOCATIONS; PV SYSTEM UNDER SEPARATE PERMIT. SEE TITLE 24 REPORT FOR MORE INFORMATION
- AREA OF ATTIC WITH 30" HEIGHT OR GREATER. 22" X 30" CLEAR OPENING ACCESS REQUIRED IF TOTAL AREA GREATER THAN 30 SQ. FT. PER CRC R807.1

### ROOF PLAN GENERAL NOTES

- REFER TO GENERAL NOTES SHEET G-101 FOR ADDITIONAL REQUIREMENTS
- REFER TO STRUCTURAL PLANS FOR ROOF FRAMING INFORMATION INCLUDING MEMBER SIZES AND CONNECTION HARDWARE.
- REFER TO MECHANICAL/ELECTRICAL SHEETS FOR ROOF PENETRATION LOCATIONS.
- PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.
- WHERE THE ROOF PROFILE ALLOWS A SPACE BETWEEN THE ROOF COVERING AND DECKING, THE SPACES SHALL BE CONSTRUCTED TO PREVENT THE INTRUSION OF FLAMES AND EMBERS. BE FIRESTOPPED WITH APPROVED MATERIALS OR HAVE ONE LAYER OF MINIMUM 72 POUND MINERAL-SURFACED NONPERFORATED CAP SHEET OVER THE COMBUSTIBLE DECKING.
- ALL ROOFING MATERIALS TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE.
- ROOF COVERINGS AND UNDERLAYMENT SHALL BE APPLIED IN ACCORDANCE WITH (CRC R805), AND MANUFACTURER'S INSTALLATION INSTRUCTIONS
- ROOF VENTS SHALL BE APPLIED PER MANUFACTURER'S SPECIFICATIONS
- FURNISHED DIMENSIONS FOR VENTS ARE GUIDES ONLY. INSTALL PER MANUFACTURER'S SPECIFICATIONS AND ADJUST TO ACCOMMODATE TRUSS LOCATIONS, PLUMBING VENTS, AND SOLAR COLLECTORS.
- ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATION OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH MINIMUM AND 1/4 INCH MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES.
- THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC R806.2.
- IN THE INSTANCE OF UPPER VENTS, VENTS SHALL BE LOCATED NO MORE THAN 3 FT BELOW THE RIDGE OR HIGHEST POINT OF THE SPACE, MEASURED VERTICALLY. CRC R806.2
- FOR VENTED ROOF ASSEMBLIES: PROVIDE A MINIMUM OF 1 INCH OF AIRSPACE BETWEEN THE INSULATION AND ROOF SHEATHING.
- FOR UN-VENTED ROOF ASSEMBLIES: ROOF ASSEMBLY TO MEET CODE REQUIREMENTS OF CRC R806.5. PROVIDE MINIMUM 2" HIGH DENSITY CLOSE CELL INSULATION. PROVIDE ADDITIONAL INSULATION AS NEEDED TO MEET MINIMUM ROOF ASSEMBLY R-VALUE REQUIRED BY TITLE-24.
- ALL ROOFING TO BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- OVERHANG DIMENSIONS ARE FROM FACE OF EXTERIOR WALL FRAMING TO ROOF EDGE

### ROOF VENTING CALCULATIONS

UPPER & LOWER VENTS:

O'HAGIN TAPERED LOW PROFILE FIRE & ICE COMPOSITION SHINGLE FINISH TO MATCH ROOF  
72.0 SQ. IN. OF AIR MOVEMENT PER VENT = 72. SQ. IN. / 144 = 0.5 SF

"UPPER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) \* (0.5) / (0.5 SF)

"LOWER VENTS PROVIDED" = (TOTAL ATTIC AREA/300) \* (0.5) / (0.5 SF)

NOTE: ROOF VENTING SHALL COMPLY WITH CRC R806 & CRC 337.

- A) ENCLOSED ATTICS AND ENCLOSED RAFTER SPACES FORMED WHERE CEILINGS ARE APPLIED DIRECTLY TO THE UNDERSIDE OF ROOF RAFTERS SHALL HAVE CROSS VENTILATION FOR EACH SEPARATE SPACE BY VENTILATING OPENINGS PROTECTED AGAINST THE ENTRANCE OF RAIN OR SNOW. VENTILATION OPENINGS SHALL HAVE A LEAST DIMENSION OF 1/16 INCH MINIMUM AND 1/4 INCH MAXIMUM. OPENINGS IN ROOF FRAMING MEMBERS SHALL CONFORM TO THE REQUIREMENTS OF SECTION R802.7. REQUIRED VENTILATION OPENINGS SHALL OPEN DIRECTLY TO THE OUTSIDE AIR AND SHALL BE PROTECTED TO PREVENT THE ENTRY OF BIRDS, RODENTS, SNAKES AND OTHER SIMILAR CREATURES.
- B) THE MINIMUM NET FREE VENTILATING AREA SHALL COMPLY WITH CRC R806.2.
- C) PER CRC R902.1.3 ROOFING REQUIREMENTS FOR STRUCTURES LOCATED IN A WILDLAND-URBAN INTERFACE (WUI) FIRE AREA SHALL COMPLY WITH SECTION R337.5.
- D) THE PRODUCT ABOVE CAN BE FOUND IN THE CAL-FIRE STATE FIRE MARSHAL LISTED WILDLAND URBAN INTERFACE (WUI) PRODUCT HANDBOOK.


ATTIC	AREA	REQUIRED ATTIC VENTING (NFA)	UPPER VENTING REQUIRED (NFA)	LOWER VENTING REQUIRED (NFA)
ATTIC 1 - PLAN 2	768 SF	2.56 SF	1.28 SF	1.28 SF

	COUNT	VENT LENGTH	NET FREE AREA PER VENT	PROVIDED NET FREE AREA
LOWER O'HAGIN SHINGLE ROOF VENT (LOWER)	3	2' - 8"	0.50 SF	1.50 SF
UPPER O'HAGIN SHINGLE ROOF VENT (UPPER)	3	2' - 8"	0.50 SF	1.50 SF


COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ROOF PLAN & REFLECTED CEILING PLAN

DATE  
09/28/2023


SHEET  
A2-121




**2 SIDE PORCH OPTION**  
A1-201 | A2-121 | SCALE: 1/4" = 1'-0"



**1 ROOF PLAN**  
A1-201 | A2-121 | SCALE: 1/4" = 1'-0"



**4 NO FRONT PORCH OPTION**  
A1-201 | A2-121 | SCALE: 1/4" = 1'-0"



**3 REFLECTED CEILING PLAN**  
A1-201 | A2-121 | SCALE: 1/4" = 1'-0"



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

### GENERAL ELEVATION NOTES

1. REFER TO GENERAL NOTES SHEET G-102 FOR ADDITIONAL REQUIREMENTS
2. SEE DETAILS FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
3. REFER TO ROOF PLAN FOR OVERHANGS, FASCIA PER DETAILS. PROVIDE ALUMINUM GUTTER. SEE ROOF PLAN FOR APPROXIMATE DOWNSPOUT LOCATIONS. U10-Q.
4. REFER TO DOOR AND WINDOW SCHEDULES AND TYPES FOR DOOR AND WINDOW INFORMATION.
5. THE NOMINAL THICKNESS AND ATTACHMENT OF EXTERIOR WALL COVERINGS SHALL BE IN ACCORDANCE WITH CRC TABLE R703.3(1).
6. GYPSUM SHEATHING SHALL BE ATTACHED TO EXTERIOR WALLS IN ACCORDANCE WITH CRC TABLE R602.3.


### SECTIONS GENERAL NOTES

1. THE PURPOSE OF THESE DRAWINGS IS TO SHOW CONSTRUCTION MATERIALS/ASSEMBLIES. FOR SPECIFIC SIZES AND DETAILS REFER TO ARCHITECTURAL PLANS, ELEVATIONS, DETAILS, AND STRUCTURAL PLANS. KEYNOTES ONLY APPLY IF REFERENCED ON PLANS.
2. WALL ASSEMBLIES TO BE PER FLOOR PLAN.
3. DOORS AND WINDOWS TO BE PER APPLICABLE SCHEDULE. REFER TO FLOOR PLANS FOR IDENTIFICATION.
4. INSULATION: REFER TO TITLE 24 REPORT AND "INSULATION" NOTES ON SHEET FOR ADDITIONAL RATINGS, REQUIREMENTS, AND INFORMATION.
5. FIREBLOCKING TO BE LOCATED AT THE FOLLOWING LOCATIONS PER 2022 CRC SECTION R302.11:
  - A. SECTION R302.11.1 - FIREBLOCKING SHALL BE PROVIDED IN CONCEALED SPACES OF STUD WALLS AND PARTITIONS, INCLUDING FURRED SPACES AND PARALLEL ROWS OF STUDS OR STAGGERED STUDS, AS FOLLOWS:
    1. VERTICALLY AT CEILING AND FLOOR LEVELS
    2. HORIZONTALLY AT INTERVALS NOT EXCEEDING 10 FEET.
  2. AT INTERCONNECTIONS BETWEEN CONCEALED VERTICAL AND HORIZONTAL SPACES SUCH AS SOFFITS, DROP CEILINGS AND COVE CEILINGS.
  3. IN CONCEALED SPACES BETWEEN STAIR STRINGERS AT THE TOP AND BOTTOM OF THE RUN. ENCLOSED SPACES UNDER STAIRS SHALL COMPLY WITH SECTION R302.7.
  4. AT OPENINGS AROUND VENTS, PIPES, DUCTS, CABLES AND WIRES AT CEILINGS AND FLOOR LEVEL, WITH APPROVED MATERIAL TO RESIST THE FREE PASSAGE OF FLAME PRODUCTS OF COMBUSTION. THE MATERIAL FILLING THIS ANNULAR SPACE SHALL NOT BE REQUIRED TO MEET THE ASTM E136 REQUIREMENTS.
  5. FOR THE FIREBLOCKING OF CHIMNEYS AND FIREPLACES, SEE SECTION R1003.12.
  6. FIREBLOCKING OF CORNICES OF A TWO-FAMILY DWELLING IS REQUIRED AT THE LINE OF DWELLING-UNIT SEPARATION.
  - A. SECTION R302.11.1 - FIREBLOCKING MATERIALS SHALL CONSIST OF FOLLOWING MATERIALS:
    1. TWO-INCH NOMINAL LUMBER
    2. TWO THICKNESSES OF ONE-INCH NOMINAL LUMBER WITH BROKEN LAP JOINTS
    3. THE THICKNESS OF 0.719-INCH WOOD STRUCTURAL PANELS WITH JOINTS BACKED BY 0.719-INCH WOOD STRUCTURAL PANELS
    4. THE THICKNESS OF 0.75-INCH PARTICULATE BOARD WITH JOINTS BACKED BY 0.75-INCH PARTICULATE BOARD
    5. ONE-HALF-INCH GYPSUM BOARD
    6. ONE-FOURTH-INCH CEMENT-BASED MILLBOARD
    7. BATTS OR BLANKETS OF MINERAL WOOL, MINERAL FIBER OR OTHER APPROVED MATERIAL INSTALLED IN SUCH A MANNER AS TO BE SECURELY RETAINED IN PLACE
    8. CELLULOSE INSULATION INSTALLED AS TESTED IN ACCORDANCE WITH ASTM E119 OR UL 263, FOR THE SPECIFIC APPLICATION.
4. PER 2022 CRC SECTION R317 SLEEPERS AND SILLS ON A CONCRETE OR MASONRY SLAB THAT IS IN DIRECT CONTACT WITH GROUND, UNLESS SEPARATED BY AN IMPERVIOUS MOISTURE BARRIER SHALL BE NATURALLY DURABLE OR PRESERVATIVE-TREATED WOOD IN ACCORDANCE WITH ACPA U1.


### KEYNOTES

- B18 ELECTRIC PANEL, 100AMP 240V.
- B38 MULTI-ZONE HEAT PUMP CONDENSER UNIT. REFER TO PLANS FOR LOCATION OF INDOOR FAN COIL UNITS. REFER TO TITLE 24 FOR ADDITIONAL INFORMATION. PROVIDE CONCRETE PAD MIN. 6" LARGER THAN UNIT IN EACH DIRECTION, 3" MIN. ABOVE GRADE.
- H05 ROOF EDGE/FASCIA. SEE DETAILS FOR FASCIA TYPE.
- H12 ATTIC VENT (LOW). PAINT OR FINISH TO MATCH ROOF COLOR. SEE VENTING CALCS.\*
- H13 ATTIC VENT (HIGH). PAINT OR FINISH TO MATCH ROOF COLOR. SEE VENTING CALCS.\*
- K05 COMPOSITE ROOF SHINGLES. SEE MATERIALS LEGEND FOR MORE INFO.
- L14 LIGHT FIXTURE LOCATION, SEE DETAILS & ELECTRIC PLAN FOR MORE INFO.
- L15 WINDOW SURROUNDS
- L20 BUILDING SHALL HAVE ADDRESS NUMBERS PLACED IN A POSITION THAT IS PLAINLY LEGIBLE AND VISIBLE FROM STREET, MINIMUM OF 4" HIGH WITH A MIN. STROKE OF 1/2" (EXACT LOCATION PER OWNER/APPLICANT).
- M01 GUTTER. CONNECT TO DOWNSPOUT. PROVIDE MEANS TO PREVENT ACCUMULATION OF LEAVES AND DEBRIS IN GUTTER PER CRC R337.5.4
- M02 DOWNSPOUT. CONNECT TO STORM DRAIN SYSTEM OR APPROVED DRAINAGE SYSTEM BY COUNTY.
- S03 ROOF INSULATION, R-38 MIN.
- S04 2X6 WALL INSULATION, R-19 MIN.
- T14 6X6 POST, REFER TO STRUCTURAL
- U11 WOOD BEAM / HEADER, REFER TO STRUCTURAL.
- U13 FAUX OUTRIGGER. SEE STRUCTURAL AND DETAILS FOR MORE INFORMATION.


COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 ELEVATIONS & BUILDING SECTIONS




**3 FRONT ELEV. NO PORCH OPT.**  
 A5-101 | A2-201 SCALE: 1/4" = 1'-0"




**2 LEFT ELEVATION**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"




**1 FRONT ELEVATION**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"




**6 SIDE PORCH OPTION**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"




**5 RIGHT ELEVATION**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"




**4 REAR ELEVATION**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"



**9 SECTION 02 NO PORCH**  
 A2-201 SCALE: 1/4" = 1'-0"



**8 SECTION 02**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"



**7 SECTION 01**  
 A2-101 | A2-201 SCALE: 1/4" = 1'-0"

### MATERIALS LEGEND

1. COLOR SCHEMES AND FINISH OF PRODUCT SELECTIONS RECOMMENDED TO MATCH PRIMARY RESIDENCE. **INSTALL ALL MATERIAL SELECTIONS PER MANUFACTURER'S RECOMMENDATIONS.**
2. A PROJECT SITE WITHIN THE WILDLAND-URBAN INTERFACE FIRE AREA SHALL COMPLY WITH THE **CRC SECTION R337**. IF WUI APPROVED PRODUCTS ARE REQUIRED, PROVIDE SELECTED PRODUCT LISTINGS IN THE SPACES PROVIDED. WHEN NOT REQUIRED, WRITE "NOT APPLICABLE."
3. APPROVED PRODUCT LISTINGS CAN BE FOUND IN THE (CURRENT) CAL-FIRE STATE FIRE MARSHAL LISTED WILDLAND URBAN INTERFACE **WUI** PRODUCT HANDBOOK.
4. IF PROJECT SITE REQUIRES WUI COMPLIANCE, IN THE CASE THAT PRODUCT SELECTIONS ARE NOT BML LISTED, NOR IN THE HANDBOOK, MATERIALS SHALL COMPLY WITH THE PRESCRIPTIVE STANDARDS OF **CHAPTER 7A**.

### GRAPHICS LEGEND:


- F) FIBER CEMENT HORIZONTAL LAP SIDING (SHALL MEET ALL REQ. OF CRC 337 & CRC R703.10.2)**
- F) EXT. GRADE WOOD HORIZONTAL LAP SIDING (SHALL MEET ALL REQ. OF CRC 337 & CRC R703.5.3)**

### OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:

### GRAPHICS LEGEND:


- ASPHALT COMPOSITE ROOF SHINGLES (SHALL COMPLY WITH CRC 337 & CRC R905.2.4 & ASTM D3462)**
- CLASS-A ROOF ASSEMBLY REQ. PER WUI:**  
 YES  NO

### OWNER/APP. TO PROVIDE MANUFACTURER, COLOR/FINISH SPECIFICATIONS, & WUI (WHEN REQ.) PRODUCT LISTINGS:




**51 TYP. PORCH BEAM @ SOFFIT**

SCALE: 1/2" = 1'-0"




**41 RAILING CONNECTION DETAIL**

SCALE: 6" = 1'-0"




**32 SHED ROOF WITH KICKER (CONT. ROOF)**

SCALE: 1" = 1'-0"




**21 EXTERIOR DOOR THRESHOLD - TYPICAL**

SCALE: 6" = 1'-0"




**12 TYP. GUTTER TO EXT. DOWNSPOUT**

SCALE: 1/2" = 1'-0"




**42 TYPICAL POST**

SCALE: 3/4" = 1'-0"




**34 SHED ROOF WITH KICKER**

SCALE: 1" = 1'-0"




**23 TYP. FOUNDATION**

SCALE: 3" = 1'-0"




**12 TYP. GUTTER TO EXT. DOWNSPOUT**

SCALE: 1/2" = 1'-0"




**54 TOILET BLOCKING - AGING-IN-PLACE**

SCALE: 1/2" = 1'-0"




**44 TUB BLOCKING - AGING-IN-PLACE**

SCALE: 1/2" = 1'-0"



**25 DOOR-SLIDING GLASS - THRESHOLD**

SCALE: 3" = 1'-0"



**12 TYP. GUTTER TO EXT. DOWNSPOUT**

SCALE: 1/2" = 1'-0"



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA










ARCHITECTURAL DETAILS

DATE  
09/28/2023  
SHEET

A-901



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.








**52 BEAM TO WALL FLASHING**  
SCALE: 1" = 1'-0"

**43 FLASHING - PROTRUSIONS**  
SCALE: 1 1/2" = 1'-0"

**32 FLASHING - WINDOW CORNER TYP.**  
SCALE: 1/2" = 1'-0"

**22 FLASHING - FASCIA TO WALL TYP.**  
SCALE: 1 1/2" = 1'-0"

**12 ROOF TO WALL TYP. FLASHING 2**  
SCALE: 3" = 1'-0"






**53 FLASHING - G.I. VENT**  
SCALE: 1" = 1'-0"

**42 FLASHING - PROTRUSIONS**  
SCALE: 1 1/2" = 1'-0"

**33 FLASHING - DOOR AT GRADE**  
NTS

**23 FLASHING PAN @ DOOR THRESHOLD**  
SCALE: 3" = 1'-0"

**13 ROOF TO WALL TYP. FLASHING 3**  
SCALE: 3" = 1'-0"



**53 FLASHING - G.I. VENT**  
SCALE: 1" = 1'-0"

**43 FLASHING - DETAILED PROTRUSION**  
SCALE: 1 1/2" = 1'-0"

**34 FLASHING - DOOR AT W.P. DECK**  
NTS

**24 FLASHING - JAMB TO SILL TYP.**  
SCALE: 3" = 1'-0"

**14 ROOF TO WALL TYP. FLASHING**  
SCALE: 3" = 1'-0"


COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ARCHITECTURAL DETAILS

DATE  
09/28/2023  
SHEET  
A-902



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

**XHEZ.W-L-1166 WALL SYSTEM PENETRATION**  
F RATING - 1 AND 2 HR (SEE ITEM 1B)  
T RATING - 0 HR



**1. WALL ASSEMBLY**  
THE 1 OR 2 HR. FIRE RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES WALL AND PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION FEATURES:

**A. STUDS-**  
WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS OR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2 IN. BY 4 IN. LUMBER SPACED 16 IN. O.C. STEEL STUDS TO BE MIN. 3 1/2 IN. WIDE AND SPACED MAX. 24 IN. O.C.

**B. GYPSUM BOARD (BEARING THE UL CLASSIFICATION MARKING)-**  
THICKNESS, TYPE, NUMBER OF LAYERS AND FASTENERS AS REQUIRED IN THE INDIVIDUAL WALL AND PARTITION DESIGN. MAX. DIAM. OF OPENING IS 5 IN.

THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS EQUAL TO THE HOURLY FIRE RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED.

**2. THROUGH-PENETRANTS**  
ONE METALLIC PIPE, CONDUIT OR TUBING INSTALLED EITHER CONCENTRICALLY OR ECCENTRICALLY WITHIN THE FIRESTOP SYSTEM. THE ANNULAR SPACE BETWEEN THE PIPE, CONDUIT OR TUBING AND PERIPHERY OF THE OPENING SHALL BE MIN. OF 0 IN. (POINT CONTACT) TO A MAX. 1/8 IN. PIPE, CONDUIT OR TUBING TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF WALL ASSEMBLY. THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES, CONDUITS OR TUBING MAY BE USED:

**A. COPPER TUBING-**  
NOM. 4 IN. DIAM. (OR SMALLER) TYPE M (OR HEAVIER) COPPER TUBING.

**B. COPPER PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) REGULAR (OR HEAVIER) COPPER PIPE.

**C. STEEL PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) SCHEDULE 5 (OR HEAVIER) STEEL PIPE.

**D. CONDUIT-**  
NOM. 4 IN. DIAM. (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING OR RIGID STEEL CONDUIT


**E. IRON PIPE-**  
NOM. 4 IN. DIAM. (OR SMALLER) CAST OR DUCTILE IRON PIPE.

**3. FILL, VOID OR CAVITY MATERIALS (BEARING THE UL CLASSIFICATION MARKING) -**  
CAULK OR PUTTY MIN. 1/2 IN. DIAMETER BEAD CAULK OR PUTTY APPLIED CONTINUOUSLY AROUND THE PENETRANT ON THE WALL SURFACES ON BOTH SIDES OF THE WALL.

3M COMPANY - CP 25WB+ CAULK OR MPS-2+ PUTTY

**32 THROUGH PENETRATION @ WALL**  
SCALE: 1 1/2" = 1'-0"

**GA FILE NO. RC 2606 1-HOUR FIRE RATED**



R-38 BATT INSULATION. PLACE INSULATION ABOVE RESILIENT CHANNELS ALIGNED WITH THE TRUSS BOTTOM CORDS


RESILIENT CHANNELS

5/8" TYPE C GWB


ONE LAYER 5/8" PROPRIETARY TYPE X GYPSUM WALLBOARD OR GYPSUM VENEER BASE APPLIED AT RIGHT ANGLES TO RESILIENT FURRING CHANNELS 16" O.C. (12" O.C. WHEN INSULATION IS DRAPED OVER CHANNELS) WITH 1" TYPE S DRYWALL SCREWS 12" O.C. GYPSUM BOARD END JOINTS ATTACHED WITH SCREWS 8" O.C. TO ADDITIONAL PIECES OF CHANNEL 60" LONG LOCATED 3" BACK ON EITHER SIDE OF END JOINT. RESILIENT CHANNELS APPLIED AT RIGHT ANGLES TO BOTTOM CHORD OF PITCHED WOOD TRUSSES 24" O.C. WITH 1/4" TYPE S OR W SCREWS. GLASS FIBER INSULATION SECURED TO WOOD STRUCTURAL PANELS OR DRAPED OVER CHANNELS. TRUSSES SUPPORTING 15/32" WOOD STRUCTURAL PANELS APPLIED AT RIGHT ANGLES TO TRUSSES WITH CONSTRUCTION ADHESIVE AND 6D RING SHANK NAILS 12" O.C. OPTIONAL CEILING DAMPER (REFER TO MANUFACTURER FOR INFORMATION ON THE TYPE OF DAMPER).

**PROPRIETARY GYPSUM BOARD**  
UNITED STATES GYPSUM COMPANY - 5/8" SHEETROCK® BRAND FIRECODE® C CORE GYPSUM PANELS

**21 ROOF ASSEMBLY (1-HOUR)**  
SCALE: 1" = 1'-0"



**22 WATER HEATER MOUNTING**  
SCALE: 12" = 1'-0"



**1. WOOD STUDS**  
NOMINAL 2X6 SPACED 16" O.C. WITH (2) 2X6 TOP PLATES (1) 2X6 BOTTOM PLATE. STUDS LATERALLY-BRACED BY WOOD STRUCTURAL PANEL SHEATHING (ITEM 5) AND EFFECTIVELY FIRE STOPPED AT TOP AND BOTTOM OF WALL.

**2. GYPSUM BOARD**  
ANY CLASSIFIED 5/8" THICK, 48" WIDE, APPLIED VERTICALLY AND NAILED TO STUDS AND BEARING PLATES 7" O.C. WITH 6D CEMENT-COATED NAILS, 1 7/8" LONG WITH 1/4" DIAM. HEAD.

JOINTS AND NAILHEADS (NOT SHOWN) - WALLBOARD JOINTS COVERED WITH TAPE AND JOINT COMPOUND. NAIL HEADS COVERED WITH JOINT COMPOUND.

**3. BATTS AND BLANKETS**  
MINERAL FIBER OR GLASS INSULATION, 3 1/2" THICK. PRESSURE FIT TO FILL WALL CAVITIES BETWEEN STUDS AND PLATES. MINERAL FIBER INSULATION TO BE UNFACED AND TO HAVE A MIN. DENSITY OF 3 PCF. GLASS FIBER INSULATION TO BE FACED WITH ALUMINIUM FOIL OR FRAFT PAPER AND TO HAVE A MIN. DENSITY OF 0.9 PCF (MIN. R-13 THERMAL INSULATION RATING). FIBER SPRAYED - AS AN ALTERNATE TO BATTS AND BLANKETS (ITEM 4) - SPRAY APPLIED CELLULOSE INSULATION MATERIAL. THE FIBER IS APPLIED WITH WATER TO COMPLETELY FILL THE ENCLOSED CAVITY IN ACCORDANCE WITH THE APPLICATION INSTRUCTIONS SUPPLIED WITH THE PRODUCT. NOMINAL DRY DENSITY OF 3.0 LB/CU.FT.

**4. WOOD STRUCTURAL PANEL SHEATHING**  
MIN 7/16" THICK, 4 FT. WIDE WOOD STRUCTURAL PANELS, MIN. GRADE "C-D" OR "SHEATHING". INSTALLED WITH LONG DIMENSION OF SHEET (STRENGTH AXIS) OR FACE GRAIN OF PLYWOOD PARALLEL WITH OR PERPENDICULAR TO STUDS. VERTICAL JOINTS CENTERED ON STUDS. HORIZONTAL JOINTS BACKED WITH NOMINAL 2X4 WOOD BLOCKING. ATTACHED TO STUDS ON EXTERIOR SIDE OF WALL WITH 6D CEMENT COATED BOX NAILS SPACED 6" O.C. AT PERIMETER OF PANELS AND 12" O.C. ALONG INTERIOR STUDS.


**5. EXTERIOR FACING**  
INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTION. ONE OF THE FOLLOWING EXTERIOR FACINGS IS TO BE APPLIED OVER THE SHEATHING. REFER TO PLAN FOR INFOEMATION:

FIBER-CEMENT SIDING - FIBER-CEMENT EXTERIOR SIDING INCLUDING SMOOTH AND PATTERNED PANEL OR LAP SIDING.


**UL DES U305**  
AT INTERIOR WALL USE:  
5/8" SHEETROCK® FIRECODE CORE PANELS,  
5/8" SHEETROCK® ULTRALIGHT PANELS FIRE CODE X OR  
5/8" FIBEROCK PANELS  
2 X 6 WOOD STUD 16" OR 24" O.C.

**24 1-HR EXTERIOR RATED WALL ASSEMBLY**  
SCALE: 3" = 1'-0"


**11 DETAILED HEAD FLASHING**  
SCALE: 12" = 1'-0"



**12 DETAILED JAMB FLASHING**  
SCALE: 12" = 1'-0"



**13 DETAILED SILL FLASHING**  
SCALE: 12" = 1'-0"



**NOTE: DETAIL PROVIDED FOR ADDITIONAL VENTING WHEN REQUIRED BY SPECIAL CIRCUMSTANCES**

**14 WALL VENT**  
SCALE: 3" = 1'-0"

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ARCHITECTURAL DETAILS

DATE  
09/28/2023  
SHEET

A-903



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

LNC - MODERN FROSTED BLACK PORCH OUTER WALL SCONCE WITH MUSHROOM CLEAR SEEDED GLASS SHADE (VAFNYAHD13356V6) OR EQUAL

FRONT SIDE ABOVE




**LIGHT OPTION A**

LUTEC - BLACK SOLAR OUTDOOR BARN LIGHT SCONCE WITH DUSK TO DAWN (6940002012) OR EQUAL

FRONT SIDE ABOVE

**LIGHT OPTION B**

**NOTE: ALL EXTERIOR LIGHTING MUST BE DARK SKY COMPLIANT PER ZONING REGULATIONS SECTION 17.70.100.**







**41 TYP. LIGHT FIXTURES**  
SCALE: 1 1/2" = 1'-0"

**31 DOOR TRIM**  
SCALE: 3/4" = 1'-0"

**21 TRIM PROFILES**  
SCALE: 1 1/2" = 1'-0"

**11 TYP. MOUNTIN PAD**  
SCALE: 3" = 1'-0"







**42 DECORATIVE FAUX GABLE VENT (OPT.)**  
SCALE: 3/4" = 1'-0"

**32 WINDOW TRIM**  
SCALE: 3/4" = 1'-0"

**22 TYP. INSIDE CORNER**  
SCALE: 3" = 1'-0"

**12 TYP. WINDOW HEAD**  
SCALE: 3" = 1'-0"





**43 TYP. DOOR HEAD**  
SCALE: 3" = 1'-0"

**33 SCREENING ELEMENT**  
SCALE: 1" = 1'-0"

**23 TYP. OUTSIDE CORNER**  
SCALE: 3" = 1'-0"

**13 TYP. WINDOW JAMB**  
SCALE: 3" = 1'-0"



**44 TYP. DOOR JAMB**  
SCALE: 3" = 1'-0"

**24 DECORATIVE PORCH RAILING**  
SCALE: 1" = 1'-0"


**14 TYP. WINDOW SILL**  
SCALE: 3" = 1'-0"

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ARCHITECTURAL DETAILS


DATE  
09/28/2023  
SHEET  
A-911




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




**41 TYPICAL VALLEY DETAIL**  
SCALE: 3" = 1'-0"



**31 TYPICAL RIDGE/HIP DETAIL**  
SCALE: 3" = 1'-0"




**21 TYP. EAVE**  
SCALE: 1 1/2" = 1'-0"




**NOTE: WUI COMPLIANT; SEE CRC R337.7.5 OPEN ROOF EAVES**




**32 O'HAGIN ROOF VENT**  
SCALE: 3" = 1'-0"



**22 TYP. RAKE**  
SCALE: 1 1/2" = 1'-0"



**NOTE: WUI COMPLIANT; SEE CRC R337.7.5 OPEN ROOF EAVES**




**13 HEADWALL**  
SCALE: 3" = 1'-0"




**24 DECORATIVE OUTRIGGER**  
SCALE: 1 1/2" = 1'-0"



**14 SIDE WALL**  
SCALE: 3" = 1'-0"



**13 HEADWALL**  
SCALE: 3" = 1'-0"



**14 SIDE WALL**  
SCALE: 3" = 1'-0"

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ARCHITECTURAL DETAILS - ROOF

DATE  
09/28/2023

SHEET  
A-912



SYMBOLS

WALL TYPES

SHEET INDEX

	DETAIL REFERENCE BUBBLE WITH LEADER		INDICATES SHEAR WALL TYPE AND LENGTH. PER SHEAR WALL SCHEDULE		INDICATES TOP PLATE SPLICE NAILING PER SCHEDULE
	DETAIL REFERENCE BUBBLE		INDICATES SPAN AND DIRECTION OF PREFABRICATED ROOF TRUSS (BY OTHERS)		INDICATES SHEAR WALL STRAP / HOLD-DOWN TYPE PER SCHEDULE
	FULL HEIGHT SECTION INDICATOR		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST WITH WEB STIFFENER		INDICATES PAD FOOTING TYPE PER SCHEDULE
	ELEVATION OF WALL OR FRAME		INDICATES SPAN AND DIRECTION OF ROOF RAFTER OR FLOOR JOIST		INDICATES CONTINUOUS FOOTING TYPE PER SCHEDULE
	NORTH ARROW		INDICATES HEADER @ OPENING PER HEADER SCHEDULE		ANGLE BRACE
	TOP/BOTTOM OF ELEVATIONS		EARTH LAYER		DOUBLE ANGLE BRACE
	SLOPE		INDICATES SAND OR GROUT		DRAG STRUT CONNECTION
	WELDED WIRE FABRIC (WWF LAYER)		INDICATES GRAVEL		FULL HEIGHT STIFFENER CONNECTION
	STEPPED SURFACE: FLOOR DEPRESSION		STEEL IN CROSS SECTION		MOMENT CONNECTION
	SLOPED SURFACE		INDICATES BEARING WALL		MEMBER SPLICE
	STEPPED FOOTING		SHADED AREA INDICATES CALIFORNIA FRAMING		TOP OF STEEL ± ELEVATION
	BOTTOM STEPPED FOOTING		SHADED AREA INDICATES FOOTPRINT OF FLOOR ABOVE		NUMBER OF EVENLY SPACED SHEAR STUDS
			STEEL HSS TUBE COLUMN		SPECIAL STUD SPACING SEE TYPICAL STEEL DETAILS
			STEEL HSS OR PIPE COLUMN		BEAM CAMBER AT MID-SPAN
			WIDE FLANGE STEEL COLUMN		
			WOOD POST		

	INDICATES PLYWOOD SIDE FOR SHEARWALL
	INDICATES BEARING WOOD WALL BELOW
	INDICATES BEARING WOOD WALL ABOVE
	INDICATES NON-BEARING WOOD WALL BELOW
	INDICATES NON-BEARING WOOD WALL ABOVE
	INDICATES EXISTING BEARING WOOD WALL
	INDICATES EXISTING NON-BEARING WOOD WALL
	INDICATES BEARING CMU WALL BELOW
	INDICATES BEARING CMU WALL ABOVE
	INDICATES NON-BEARING CMU WALL BELOW
	INDICATES NON-BEARING CMU WALL ABOVE
	INDICATES EXISTING BEARING CMU WALL
	INDICATES EXISTING NON-BEARING CMU WALL
	INDICATES BEARING CONCRETE WALL BELOW
	INDICATES BEARING CONCRETE WALL ABOVE
	INDICATES NON-BEARING CONCRETE WALL BELOW
	INDICATES NON-BEARING CONCRETE WALL ABOVE
	INDICATES EXISTING BEARING CONCRETE WALL
	INDICATES EXISTING NON-BEARING CONCRETE WALL

S-101	SHEET INDEX, ABBREVIATIONS & SYMBOLS
S-102	GENERAL NOTES
S-103	GENERAL NOTES, SPECIAL INSPECTION & TESTS
S-201	FOUNDATION PLAN - MID CENTURY MODERN
S-202	ROOF FRAMING PLAN - MID CENTURY MODERN
S-301	TYPICAL CONCRETE DETAILS
S-311	CONCRETE DETAILS
S-312	CONCRETE DETAILS
S-401	TYPICAL WOOD DETAILS
S-402	TYPICAL WOOD DETAILS
S-403	TYPICAL WOOD DETAILS
S-404	TYPICAL WOOD DETAILS
S-421	ROOF FRAMING DETAILS
S-422	ROOF FRAMING DETAILS



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

ABBREVIATIONS

A & B	ABOVE AND BELOW	DBL	DOUBLE	HDR	HEADER	PA	POST ABOVE	T & B	TOP AND BOTTOM
AB	ANCHOR BOLT	DEPT	DEPTH	HGR	HANGER	PARA OR //	PARALLEL	T & G	TONGUE & GROOVE
ABV	ABOVE	DET	DETAIL	HP	HIGH POINT	PC	PRECAST: PIECE	TO	TOP OF
ACI	AMERICAN CONCRETE INSTITUTE	DF	DOUGLAS FIR/LARCH	HSH	HORIZONTALLY SLOTTED HOLES	PERP	PERPENDICULAR	TOC	TOP OF CURB; TOP OF CONCRETE
ADDL	ADDITIONAL	DIA OR Ø	DIAMETER	HT	HEIGHT	PLY	PLYWOOD INDEX	TOF	TOP OF FOOTING
ADJ	ADJACENT	DIAG	DIAGONAL	ID	INSIDE DIAMETER	R OR PL	R PLATE	TEMP	TEMPERATURE: TEMPORARY
AESS	ARCHITECTURAL EXPOSED STRUCTURAL STEEL	DIAPH	DIAPHRAGM	IF	INSIDE FACE	PL	PROPERTY LINE	THRU	THROUGH
AISC	AMERICAN INSTITUTE OF STEEL CONSTRUCTION	DN	DOWN	I-JST	I-JOIST	PLF	PONDS PER LINEAL FOOT	THK	THICKNESS/THICK
ALT	ALTERNATE	DO	DO OVER	IN	INCH	PLCS	PLACES	THR	THREADED
ALUM	ALUMINIUM	DWG	DRAWING	INCL	INCLUDE	PLY	PLYWOOD	TOP or 1	TOP
ANCH	ANCHOR	DWL	DOWEL	INFO	INFORMATION	PROP	PROPERTY	TOS	TOP OF STEEL/TOP OF SLAB
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE	EA	EACH	INSP	INSPECTION	PT	PRESSURE TREATED	TOW	TOP OF WALL
APA	ENGINEERED WOOD ASSOCIATION [FORMERLY THE AMERICAN PLYWOOD ASSOCIATION] APPROVED	EF	EACH FACE	INT	INTERIOR	PW	PLATE WASHER	TS	TRIMMER STUD
APPVD	APPROVED	EJ	EXPANSION JOINT	JST	JOIST	PJP	PARTIAL JOINT PENETRATION WELD	TYP	TYPICAL
APPROX	APPROXIMATE	EL	ELEVATION	JT	JOINT	PREFAB	PREFABRICATED	UNO	UNLESS NOTED OTHERWISE
ARCH	ARCHITECTURAL: ARCHITECT	ELEC	ELECTRICAL	K	KIPS	PSF	POUNDS PER SQUARE FOOT	UT	ULTRA-SONIC TEST
AWPA	AMERICAN WOOD PRESERVERS ASSOCIATION	ELEV	ELEVATOR	KS	KING STUD	PSI	POUNDS PER SQUARE INCH	VERT	VERTICAL
AWS	AMERICAN WELDING SOCIETY	EMBED	EMBEDMENT	KP	KING POST	PSL	PARALLEL STRAND LUMBER	VSH	VERTICAL SLOTTED HOLES
AITC	AMERICAN INSTITUTE OF TIMBER CONSTRUCTION	EN	EDGE NAIL	KSI	KIPS PER SQUARE INCH	PVMT	PAVEMENT	W/	WITH
ASTM	AMERICAN SOCIETY FOR TESTING MATERIALS	ENGR	ENGINEER	LB(S) OR #	POUND(S)	#	POUND; NUMBER	W/O	WITHOUT
BLDG	BUILDING	EQ	EQUAL OR EQUIVALENT	LF	LINEAL FOOT	REF	REFERENCE	WO	WHERE OCCURS
BLK	BLOCK	EQUIP	EQUIPMENT	LN	LINEAL: LINEAR	REINF	REINFORCE: REINFORCING	WD	WOOD
BLKG	BLOCKING	ES	EACH SIDE	LH	LONG LEG HORIZONTAL	REQD	REQUIRED	WP	WORK POINT; WATERPROOF
BM	BEAM	EW	EACH WAY	LLV	LONG LEG VERTICAL	RF	ROOF	WWF	WELDED WIRE FABRIC
BN	BOUNDARY NAIL	EXIST or (E)	EXISTING	LP	LOW POINT	RR	ROOF RAFTER		
BOT OR B	BOTTOM	EXT	EXTERIOR	LSH	LONG SLOTTED HOLES	Ø	ROUND: DIAMETER		
BRC	BRACE	FDN	FOUNDATION	LSL	LAMINATED STRAND LUMBER	SCHED	SCHEDULE	W	W SHAPE
BRG	BEARING	FIN	FINISH	LT WT	LIGHTWEIGHT	SEC	SECTION	C	AMERICAN STD CHANNEL SHAPE
BTRWN	BETWEEN	FJ	FLOOR JOIST	LVL	LEVEL OR LAMINATED VENEER LUMBER	SEP	SEPARATION	MC	MISC CHANNEL SHAPE
CANT	CANTILEVER	FLG	FLANGE	MAT	MATERIAL	SHT	SHEET	L	ANGLE SHAPE
CAMR OR C	CAMBER	FLR	FLOOR	MAS	MASONRY	SHTG	SHEATHING	WT, ST, MT	STRUCTURE SHAPE
CC	CENTER TO CENTER	FN	FIELD NAIL	MB	MACHINE BOLT	SIM	SMILAR	PIPE	STANDARD PIPE SHAPE
CG	CENTER OF GRAVITY	FOC	FACE OF CONCRETE	MECH	MECHANICAL	SOG	SLAB ON GRADE	PIPE-X	EXTRA STRONG PIPE SHAPE
CP	CAST-IN-PLACE	FOM	FACE OF MASONRY	MFR	MANUFACTURER	SN	SHEAR NAIL	PIPE-XX	DBL EXTRA STRONG PIPE SHAPE
CJ	CONSTRUCTION JOINT: CONTROL JOINT	FOS	FACE OF STUD	MIN	MINIMUM: MINUTE	SPCG	SPACING	HSS	HOLLOW STRUCTURAL SECTION
CL	CENTER LINE	FOW	FACE OF WALL	MISC	MISCELLANEOUS	SPECS	SPECIFICATIONS		
CLR	CLEARANCE: CLEAR	FRMG	FRAMING	(N)	NEW	SQ	SQUARE		
CMU	CONCRETE MASONRY UNIT	FT	FOOT: FEET	N	NORTH	SS	STAINLESS STEEL		
COL	COLUMN	FTA	FLOOR TIE ABOVE	NO or #	NUMBER	SSL	SHORT SLOTTED HOLES		
COMP	COMPRESSION	FTG	FOOTING	NTS	NOT TO SCALE	STD	STANDARD		
CONN	CONCRETE	GA	GAUGE	OC	ON CENTER	STGR	STAGGER		
CONN	CONNECTION: CONNECT	GALV	GALVANIZED	OD	OUTSIDE DIAMETER	STIFF	STIFFENERS		
CONSTR	CONSTRUCTION	GB	GRADE BEAM	OH	OUTSIDE FACE	STIRR	STIRRUP		
CONT	CONTINUE: CONTINUOUS	GLB	GLUED LAMINATED BEAM	OH	OPPOSITE HAND	STL	STEEL		
CONTR	CONTRACTOR	GR	GRADE	OPNG	OPENING	STRUCT	STRUCTURAL		
CJP	COMPLETE JOINT PENETRATION WELD	GRND	GROUND	OPP	OPPOSITE	SW	SHEAR WALL		
CTR	CENTER	H or HORIZ	HORIZONTAL	ORIG	ORIGINAL	SYM	SYMMETRICAL		
CTS&K	COUNTERSINK: COUNTERSUNK			OSB	ORIENTED STRAND BOARD	TB	TIE BEAM		
CU FT	CUBIC FOOT								

COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 SHEET INDEX,  
 ABBREVIATIONS & SYMBOLS

N:\2000\2727-01-cu22-alc-county\ad\Structural\Sheet\Plan\_2\mid century modern\2727-01-CU22-5101.dwg, PL AN 2, 5101, Sep 28, 2023, 4:30pm, alopez



REQUIRED VERIFICATION AND INSPECTIONS

WOOD CODE CHAPTER 17 AND REFERENCED 2018 NDS AND AWC SDPWS-2015. Table with columns: SPECIAL INSPECTION OR TEST, CONTINUOUS, PERIODIC, CBC REFERENCE. Includes items like High Load Diaphragm Wood Structural Panels, Field Gluing Operations, Wood Lateral Force-Resisting System, etc.

SOILS CODE TABLE 1705.6

Table with columns: SPECIAL INSPECTION OR TEST, CONTINUOUS, PERIODIC. Includes items like Verify Materials Below Shallow Foundations, Excavations, Compacted Fill Materials, etc.

CONCRETE CONSTRUCTION CODE TABLE 1705.3

Table with columns: SPECIAL INSPECTION OR TEST, CONTINUOUS, PERIODIC, REFERENCED STANDARD, CBC REFERENCE. Includes items like Inspect Anchors Cast in Concrete, Adhesive Anchors, etc.

STATEMENT OF SPECIAL INSPECTIONS

- 1. THIS STATEMENT OF SPECIAL INSPECTIONS HAS BEEN PREPARED PURSUANT TO SECTION 1704.3 OF THE CODE... A. GENERAL: a. STRUCTURAL VERIFICATIONS, INSPECTIONS AND TESTS SHALL BE PERFORMED... B. OWNER REQUIREMENTS: a. THE OWNER OR OWNER'S AGENT SHALL EMPLOY ONE OR MORE APPROVED AGENCIES... C. SPECIAL INSPECTOR QUALIFICATIONS: a. THE SPECIAL INSPECTORS SHALL PROVIDE WRITTEN DOCUMENTATION... D. CONTRACTOR REQUIREMENTS: a. SPECIAL INSPECTION IS IN ADDITION TO THE CONTRACTOR'S QUALITY CONTROL INSPECTIONS... E. SPECIAL INSPECTOR REPORT REQUIREMENTS: a. THE SPECIAL INSPECTOR SHALL KEEP RECORD OF INSPECTIONS...

SHOP FABRICATION

- 1. SHOP FABRICATION REQUIRES SPECIAL INSPECTION IN ACCORDANCE WITH CODE SECTION 1704.2.5. EXCEPTION: SHOP SPECIAL INSPECTIONS ARE NOT REQUIRED WHEN WORK IS DONE ON THE PREMISES OF FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK... A. STEEL BUILDINGS (OR STEEL ELEMENTS IN OTHER BUILDINGS): a. FOR GENERAL STEEL BUILDINGS OR ELEMENTS THE FABRICATOR SHALL BE AN AISC CERTIFIED FABRICATOR... b. OTHER ACCREDITATION DEEMED ACCEPTABLE BY THE AUTHORITY HAVING JURISDICTION... c. IF FABRICATION IS PERFORMED BY AN APPROVED FABRICATOR A CERTIFICATE OF COMPLIANCE MUST BE PROVIDED... d. IF FABRICATION IS NOT PERFORMED BY AN APPROVED FABRICATOR WELDING INSPECTION REPORTS MUST BE SUBMITTED... B. WOOD BUILDINGS: a. WOOD STRUCTURAL PANELS (SHEATHING) SHALL BE IDENTIFIED BY THE APA TRADEMARK...

PRE-FABRICATED WOOD TRUSS NOTES

- 1. THE DESIGN OF METAL PLATE CONNECTED WOOD TRUSSES SHALL BE IN ACCORDANCE WITH THE FOLLOWING: A. CODES AND STANDARDS: a. THE GOVERNING CODE LISTED IN THE PROJECT GENERAL NOTES... b. MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES (ASCE 7-16)... c. NATIONAL DESIGN STANDARD FOR WOOD CONSTRUCTION AND SUPPLEMENT (ANSI/AWC NDS 2018)... d. SPECIAL DESIGN PROVISIONS FOR WIND & SEISMIC (AWC SDPWS-2015)... e. THE NATIONAL DESIGN STANDARD FOR METAL PLATE CONNECTED WOOD TRUSS CONSTRUCTION (ANSI/TPI 1-2014)... B. DESIGN CRITERIA: a. TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING MINIMUM VERTICAL LOADS AND OTHER LOADS INDICATED ON THE CONSTRUCTION DOCUMENTS (ATTIC MECHANICAL UNITS, ETC.)... ROOF TRUSS LOADING: ASPHALT SHINGLE W/ GYP CEILING: TOP-CHORD DEAD LOAD: 13.0 PSF \* (11.9 PSF SUPERIMPOSED) BOT CHORD DEAD LOAD: 8.3 PSF (6.7 PSF SUPERIMPOSED) ROOF - LIVE LOAD: 20 PSF ASPHALT SHINGLE W/ STUCCO CEILING: TOP-CHORD DEAD LOAD: 13.0 PSF \* (11.9 PSF SUPERIMPOSED) BOT CHORD DEAD LOAD: 12.7 PSF (11.1 PSF SUPERIMPOSED) ROOF - LIVE LOAD: 20 PSF DEFLECTION CRITERIA: DEAD + LIVE LOAD: L/240 LIVE LOAD ONLY: L/360 \*INCLUDES 4 PSF ALLOWANCE FOR PV PANELS... b. ( ) INDICATES HORIZONTAL SEISMIC WIND LOAD ON COLLECTOR TRUSSES... 2. CONTRACTOR REQUIREMENTS: A. THE CONTRACTOR SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.4 OF ANSI/TPI 1-2014 INCLUDING THE FOLLOWING: a. MEANS AND METHODS: THE CONTRACTOR IS RESPONSIBLE FOR ALL MEANS AND METHODS, TECHNIQUES, SEQUENCES, PROCEDURES, PROGRAMS AND SAFETY IN CONNECTION WITH THE RECEIPT, STORAGE, HANDLING, INSTALLATION, RESTRAINING, AND BRACING OF THE TRUSSES... b. TRUSS INSTALLATION SHALL COMPLY WITH INSTALLATION TOLERANCES SHOWN IN BCSI-81... c. TEMPORARY INSTALLATION RESTRAINT/BRACING FOR THE TRUSS SYSTEM AND THE PERMANENT TRUSS SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH BCSI-82... d. CONSTRUCTION LOADING ON TRUSSES SHALL BE DONE IN ACCORDANCE WITH BCSI-84... e. TRUSS DAMAGE, JOBSITE MODIFICATIONS & INSTALLATION ERRORS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE EOR AND THE TRUSS DESIGNER, REFERENCE BCSI-85... f. SUBMIT THE DRAWINGS FROM THE TRUSS DESIGNER/MANUFACTURER TO THE BUILDING DEPARTMENT PRIOR TO FABRICATION FOR APPROVAL... 3. TRUSS DESIGNER REQUIREMENTS: A. THE TRUSS DESIGNER SHALL MEET ALL THE REQUIREMENTS LISTED IN SECTION 2.3.5 OF ANSI/TPI 1-2014 INCLUDING THE FOLLOWING: a. TRUSS DESIGNER SHALL SUPERVISE THE PREPARATION OF THE TRUSS DESIGN DRAWINGS WHICH SHALL CONTAIN THE INFORMATION LISTED IN SECTION 2.3.5.5 OF ANSI/TPI 1-2014... b. TRUSS DESIGNER SHALL COMPLY WITH THE REFERENCED CODE AND DESIGN CRITERIA ABOVE... c. TRUSS DESIGNER SHALL SHOW ALL HANGERS, BRACING AND RESTRAINTS AS WELL AS METHOD OF RESTRAINT/BRACING ON THE TRUSS PLANS TO MEET ANY SEISMIC AND WIND REQUIREMENTS OF THE CODE... d. SUBMIT TRUSS DESIGN DRAWINGS INCLUDING ALL RELEVANT DETAILS FOR THE FABRICATION OF THE TRUSSES AND PREPARE CALCULATIONS. ALL PLANS, DETAILS AND CALCULATIONS FOR THE TRUSSES SHALL BE STAMPED AND SIGNED BY A LICENSED PROFESSIONAL ENGINEER (CIVIL OR STRUCTURAL), LICENSED TO PRACTICE IN THE STATE OF CALIFORNIA.

WOOD STRUCTURAL PANELS (SHEATHING)

- 1. WOOD STRUCTURAL PANELS SHALL MEET THE FOLLOWING MINIMUM STANDARDS EXCEPT WHERE OTHERWISE NOTED:

WOOD STRUCTURAL PANEL PROPERTIES. Table with columns: USE, PLY, BOND CLASSIFICATION, SHEATHING GRADE, PERFORMANCE RATING, SPAN RATING, RATING, REFERENCE. Includes rows for ROOF, FLOOR, WALL.

- TABLE NOTES: A. WOOD STRUCTURAL PANELS SHALL CONFORM TO THE REQUIREMENTS FOR THEIR TYPE IN ACCORDANCE WITH THE FOLLOWING VOLUNTARY STANDARDS BY THE ENGINEERED WOOD ASSOCIATION (APA): a. VOLUNTARY PRODUCT STANDARD, STRUCTURAL PLYWOOD, PS 1-09... b. VOLUNTARY PRODUCT STANDARD, PERFORMANCE STANDARD FOR WOOD-BASED STRUCTURAL-USE PANELS, PS 2-10... B. WOOD STRUCTURAL PANELS SHALL BE IDENTIFIED BY THE APA TRADEMARK INDICATING CONFORMANCE TO THE APPLICABLE VOLUNTARY STANDARD... C. WHERE PANELS ARE EXPOSED TO REPEATED WETTING AND REDRYING, LONG-TERM EXPOSURE TO WEATHER, OR CONDITIONS OF SIMILAR SEVERITY, "EXTERIOR" APA RATED PLYWOOD SHEATHING SHALL BE USED... D. ORIENTED STRAND BOARD (OSB) WITH EQUIVALENT CLASSIFICATION AND RATINGS MAY BE USED IN LIEU OF PLYWOOD FOR WOOD STRUCTURAL PANEL WALL SHEATHING.

- 2. TRANSPORTATION, STORAGE, AND HANDLING: A. TRANSPORTATION: a. IN TRANSPORTING PANELS ON OPEN TRUCK BEDS, COVER THE BUNDLES WITH A TARP... B. STORAGE: a. ALWAYS STORE THE PANELS UNDER COVER WHENEVER POSSIBLE... b. WHEN STORING PANELS OUTSIDE STACK THEM ON A LEVEL SURFACE ON TOP OF STRINGERS OR OTHER BLOCKING, THREE STRINGERS MINIMUM... c. NEVER LEAVE PANELS IN CONTACT WITH THE GROUND... d. COVER THE STACK WITH A PLASTIC TARP, ENSURING THAT THE BUNDLE IS WELL VENTILATED TO PREVENT MILDEW... e. IF MOISTURE ABSORPTION IS EXPECTED, CUT THE STEEL BAND TO PREVENT DAMAGE... f. KEEP SANDED OR OTHER APPEARANCE GRADE PANELS AWAY FROM HIGH TRAFFIC AREAS... C. HANDLING: a. ALWAYS PROTECT ENDS AND EDGES, ESPECIALLY TONGUE AND GROOVE PRODUCTS, FROM PHYSICAL DAMAGE... b. ACCLIMATE THE PANELS FOR 24 HOURS MINIMUM BEFORE INSTALLATION BY STANDING THE PANELS ON EDGE WITH A GAP BETWEEN EACH TO ALLOW FOR AIR CIRCULATION OR PER MANUFACTURER'S RECOMMENDATIONS... 3. PLYWOOD ORIENTATION: A. ROOF AND FLOOR SHEATHING SHALL BE LAID WITH THE GRAIN OF THE OUTER PILES PERPENDICULAR TO THE FRAMING MEMBERS... B. PLYWOOD OR OSB WALL SHEATHING MAY BE APPLIED VERTICALLY OR HORIZONTALLY... 4. BLOCKING: A. ROOF: ALL ROOF SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS... B. ALL FLOOR SHEATHING SHALL BE BLOCKED UNLESS SPECIFICALLY ALLOWED ON PLANS... C. WALLS: ALL SHEAR WALLS SHALL BE FULLY BLOCKED AT PLYWOOD EDGES... 5. FASTENERS: A. USE SHEATHING NAILS SAME GAUGE AS COMMON WIRE NAILS WITH LENGTHS AT LEAST EQUAL TO SHEATHING THICKNESS PLUS REQUIRED PENETRATION PER AWS SDPWS TABLE 4.2A OR 4.3A... B. EQUIVALENT PNEUMATIC DRIVE NAILS OR STAPLES MAY BE USED IF FASTENER MANUFACTURER HAS RECEIVED ICC OR IAPMO APPROVAL... C. USE OF MACHINE NAILING IS SUBJECT TO A SATISFACTORY JOB SITE DEMONSTRATION... D. TYPICAL NAILING SHALL BE 10D AT 6" O.C. AT ALL SUPPORTED EDGES AND OVER SHEAR WALLS...



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED...

COUNTY OF SAN LUIS OBISPO ACCESSORY DWELLING UNIT SAN LUIS OBISPO, CA GENERAL NOTES, SPECIAL INSPECTION & TESTS

DATE 09/28/2023 SHEET





THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

**ROOF FRAMING NOTES**

- SEE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS AND ELEVATIONS INCLUDING, BUT NOT LIMITED TO THE FOLLOWING. ALL DIMENSIONS TO BE VERIFIED PRIOR TO CONSTRUCTION:
  - GRID DIMENSIONS AND HORIZONTAL CONTROL
  - ALL DIMENSIONS, ELEVATIONS, FINISH SURFACE, SLOPES, DRAINS, SLAB DEPRESSIONS, ETC
  - LOCATION AND EXTENT OF EXTERIOR WALL ASSEMBLIES AND OPENINGS
  - ALL NON STRUCTURAL WALLS
- REFER TO THE FOLLOWING SHEETS FOR TYPICAL DETAILS:
 

DESCRIPTION	SHEET (S)
SYMBOLS AND ABBREVIATIONS	S-101
STRUCTURAL GENERAL NOTES	S-102 - S-103
TESTING AND INSPECTION	S-103
TYPICAL CONCRETE DETAILS	S-301
TYPICAL WOOD DETAILS	S-401 - S-405
- SEE ARCHITECTURAL DRAWINGS FOR ALL TOP OF SHEATHING AND TOP OF WALL ELEVATIONS.
- SEE ARCHITECTURAL, PLUMBING, MECHANICAL AND ELECTRICAL DRAWINGS FOR SIZE AND LOCATION OF PIPES, DUCTS AND OTHER ROOF PENETRATIONS. FOR ROOF PENETRATIONS NOT SHOWN ON ROOF FRAMING PLAN, SEE DETAIL 23/S-403 FOR TYPICAL OPENINGS, UNO.
- ALL POSTS IN 6" WALLS SHALL BE 6x6, UNLESS NOTED OTHERWISE.  
 TYPICAL WALL FRAMING SHALL BE:  
 2x6 @ 16" OC @ ALL EXTERIOR WALLS, UNO  
 2x4 @ 16" OC @ ALL INTERIOR BEARING WALLS, UNO  
 2x4 @ 16" @ ALL INTERIOR NON-BEARING WALLS, UNO
- ALL INTERIOR WALLS NOT SHOWN ON THE STRUCTURAL FRAMING PLANS BUT SHOWN ON THE ARCHITECTURAL DRAWINGS SHALL BE CONSTRUCTED PER NON-BEARING PORTION WALL DETAIL 43/S-401, UNO.
- DIAPHRAGM TYPES:  
 ALL ROOF DIAPHRAGMS SHALL BE TYPE A, UNO REFER TO 12/S-403
- ALL LINES AND/OR MEMBERS INDICATED AS "STRUT" SHALL RECEIVE (2) ROWS OF BOUNDARY NAILING (BN), STGR.
- TRUSS MEMBERS AND COMPONENTS SHALL NOT BE CUT, NOTCHED, DRILLED OR OTHERWISE ALTERED IN ANY WAY WITHOUT WRITTEN CONCURRENCE AND APPROVAL OF A REGISTERED DESIGN PROFESSIONAL.
- ALTERATIONS RESULTING IN THE ADDITION OF LOADS TO ANY MEMBER (E.G. HVAC EQUIPMENT, WATER HEATER) SHALL NOT BE PERMITTED WITHOUT VERIFICATION THAT THE TRUSS IS CAPABLE OF SUPPORTING SUCH ADDITIONAL LOADING.

**SYMBOL LEGEND**

- INDICATES SHEAR WALL TYPE AND LENGTH. SEE SCHEDULE ON 13/S-402
- INDICATES BLOCKING & STRAPPING ABOVE & BELOW WINDOW OPENINGS PER DETAIL 44/S-402
- INDICATES HEADER @ OPENING. REFER TO 32/S-401 FOR HEADER SIZE, UNO ON PLANS
- INDICATES TOP PLATE SPLICE NAILING PER 33/S-403. NOTE THAT NAILING APPLIES TO ENTIRE LENGTH OF TOP PLATE. PROVIDE TYPE (C) SPLICE, UNO
- INDICATES STRAP PER 34/S-405, UNO

**SCHEDULES**

HOLDOWN SCHEDULE		
SPECIFIES HOLDOWN/STRAP DETAIL	INDICATES HOLDOWN/STRAP TYPE	DETAIL
	INDICATES SIMPSON SSB HOLDOWN TO: CONCR FOUNDATION:	22/S-311

ROOF BEAM SCHEDULE		
MARK	SIZE	REMARKS
B1	4x6 SELECT STRUCTURAL	
B2	4x10	
B3	6x10	

ROOF RAFTER SCHEDULE		
MARK	SIZE	REMARKS
R1	2x8 @ 16" OC	


HEADER SCHEDULE		
MARK	SIZE	REMARKS
H1	6x8	
H2	4x10	

**PREFABRICATED ROOF TRUSS**


1. FOR PREFABRICATED ROOF TRUSS NOTES SEE NOTES ON SHEET S-103

ROOF TRUSS SCHEDULE		
MARK	DESCRIPTION	REMARKS
RT	ROOF TRUSS (COMMON)	24" OC MAX
SGT	STRUCTURAL GABLE TRUSS	
MT	MONO PITCH TRUSS	24" OC MAX
JT	JACK TRUSS	24" OC MAX
VJT	VALLEY JACK TRUSS	24" OC MAX
CJT	CORNER JACK TRUSS	
GT	GIRDER TRUSS	
MGT	MONO PITCH GIRDER TRUSS	
DT (#)	DRAG TRUSS	
CGT	CALIFORNIA GIRDER TRUSS	
HR	HIP RAFTER / JACK RAFTER	
CHT	CALIFORNIA HIP TRUSS	24" OC MAX
SCT	SCISSOR TRUSS	24" OC MAX. CEILING SLOPE PER ARCH

(#) - EQUALS DRAG FORCE IN LBS. DRAG FORCE IS AT A FACTORED LEVEL (0.7E) DRAG FORCES CALCULATED IN ACCORDANCE WITH ASCE 7-16 12.10.1.1. IN STRUCTURES ENTIRELY BRACED BY LIGHT FRAME SHEAR WALLS OR PORTIONS THEREOF. DRAG MEMBERS SHALL BE DESIGNED TO RESIST FORCES USING THE LOAD COMBINATIONS OF ASCE 7-16 SECTION 12.4.2.3 IN ALL OTHER STRUCTURES DRAGS SHALL INCLUDE THE EFFECT OF OVER-STRENGTH PER ASCE 7-16 12.4.3.2



**1 ROOF FRAMING PLAN - MID CENTURY MODERN - NO PORCH OPT.**  
SCALE: 1/4" = 1'-0"



**2 ROOF FRAMING PLAN - MID CENTURY MODERN - PORCH**  
SCALE: 1/4" = 1'-0"

**3 PORCH OPT. ALT.**  
SCALE: 1/4" = 1'-0"

N:\2020\2727-01-cu29-alc-county\ad\Structural\ConDoc\Sheet\Plan\_2\mid century modern\2727-01-cu29-Plan 2.dwg, 5/2/2023, 4:30pm, obpaz


**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
SAN LUIS OBISPO, CA

**ROOF FRAMING PLAN - MID CENTURY MODERN**




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TYPICAL CONCRETE DETAILS




NOTES:

- IF SAW CUT CONTRACTION OR CONTROL JOINT IS USED, SAW-CUT WITHIN 24 HOURS. EARLY ENTRY SAWS MAY BE USED WITHIN 1-4 HOURS OF POUR, AND CONVENTIONAL SAWS 4-12 HOURS OF POUR DEPENDING ON WEATHER.
- FILL CONTRACTION JOINT WITH AN ELASTOMERIC JOINT COMPOUND RATED FOR ITS USE. FOR INDUSTRIAL FLOORS SUBJECTED TO HARD WHEELED TRAFFIC, USE SEALANTS RATED FOR SUCH APPLICATIONS BY THE MANUFACTURER.
- DOWELS IN INDUSTRIAL FLOOR APPLICATIONS SHOULD BE SMOOTH ALIGNED, AND SUPPORTED SO THEY WILL REMAIN PARALLEL IN BOTH HORIZONTAL AND VERTICAL PLANES DURING PLACING AND FINISHING.
- IN STEEL AND/OR CONC. BUILDINGS DO NOT POUR DIAMOND UNTIL STRUCTURAL STEEL AND CONCRETE ABOVE HAS BEEN INSTALLED.




COLUMN ISOLATION JOINT




CONTRACTION JOINT

CONSTRUCTION JOINT (TYPICAL)




ISOLATION JOINT



BAR SIZE	D
#3	1 1/2"
#4	2"
#5	2 1/2"


\* PROVIDE 10d<sub>s</sub> EXTENSIONS IN LIEU OF 4d<sub>s</sub> AT ALL FRAME COLUMNS, GIRDERS, SHEAR WALLS AND SHEAR WALL BOUNDARY MEMBERS



BAR SIZE	REINFORCING TENSION DEVELOPMENT LENGTH AND LAP SPICE SCHEDULE					
	DEVELOPMENT LENGTH L <sub>d</sub> (CLASS B LAP SPICE)			LAP SPICE L <sub>v</sub> (CLASS B LAP SPICE)		
	F <sub>c</sub> (psi)		F <sub>c</sub> (psi)	F <sub>c</sub> (psi)		F <sub>c</sub> (psi)
	2,500	3,000	4,000	2,500	3,000	4,000
#3	1'-6"	1'-5"	1'-3"	2'-0"	1'-10"	1'-7"
#4	2'-6"	1'-10"	1'-7"	2'-8"	2'-5"	2'-1"
#5	2'-6"	2'-4"	2'-0"	3'-3"	3'-0"	2'-7"
#6	3'-0"	2'-9"	2'-5"	3'-11"	3'-7"	3'-2"
#7	4'-5"	4'-0"	3'-6"	5'-9"	5'-2"	4'-6"
#8	5'-0"	4'-7"	4'-0"	6'-6"	5'-11"	5'-2"
#9	5'-8"	5'-2"	4'-6"	7'-4"	6'-9"	5'-10"
#10	6'-5"	5'-10"	5'-1"	8'-3"	7'-7"	6'-7"
#11	7'-1"	6'-6"	5'-7"	9'-2"	8'-5"	7'-3"


- NOTES:
- VALUES ABOVE ARE FOR REINFORCEMENT WITH THE FOLLOWING PARAMETERS:
    - GRADE 60 REINFORCEMENT
    - NORMAL WEIGHT CONCRETE
      - FOR LIGHTWEIGHT CONCRETE MULTIPLY THE VALUES ABOVE BY 1.3
    - NON-EPOXY COATED REINFORCEMENT
    - HORIZONTAL BARS WITHOUT 12" OF CONCRETE BELOW (BOTTOM BARS), AND VERTICAL BARS
      - FOR TOP BARS WITH 12" OR MORE OF CONCRETE BELOW THE BAR MULTIPLY THE VALUES ABOVE BY 1.3
    - CLEAR SPACING NOT LESS THAN d<sub>s</sub>, CLEAR COVER NOT LESS THAN d<sub>s</sub> AND STIRRUPS THROUGH L<sub>d</sub> NOT LESS THAN MIN
      - CLEAR SPACING NO LESS THAN 2d<sub>s</sub> AND CLEAR COVER NOT LESS THAN d<sub>b</sub>
      - FOR OTHER SPACING AND COVER CONDITIONS MULTIPLY THE VALUES ABOVE BY 1.5
    - REINFORCEMENT NOT IN SHEAR WALLS
      - FOR REINFORCEMENT IN SHEAR WALLS MULTIPLY THE VALUES ABOVE BY 1.25
  - THE MULTIPLIERS LISTED IN NOTE 1 ABOVE ARE CUMULATIVE INCREASES IN DEVELOPMENT/LAP SPICE LENGTH.
  - ALL LAP SPICES REFERENCED IN THE PLANS SHALL BE CLASS B UNLESS NOTED OTHERWISE.
  - WHEN REINFORCING BARS OF TWO SIZES ARE LAP SPICED IN TENSION, USE THE LARGER OF THE TENSION CLASS B, LAP SPICE LENGTH (L<sub>v</sub>) OF THE SMALLER BAR, AND THE CLASS A, TENSION DEVELOPMENT LENGTH (L<sub>d</sub>) OF THE LARGER BAR.

SLAB ON GRADE JOINTS




- NOTES:
- PREPARATION OF THE SLAB SUBGRADE SHALL BE BASED ON THE GEOTECHNICAL INVESTIGATION REPORT AS REFERENCED IN THE FOUNDATION GENERAL NOTES, THE FOLLOWING INFORMATION IS FOR REFERENCE ONLY.
    - OVER-EXCAVATION SHALL EXTEND 5 FEET BEYOND PERIMETER FOUNDATION, TO PROPERTY LINES OR EXISTING IMPROVEMENTS, WHICHEVER IS LEAST.
  - NATIVE MATERIALS
    - SHALL BE OVER-EXCAVATED 36" BELOW (E) GRADE OR 18" BELOW BOTTOM OF FOOTINGS, WHICHEVER IS GREATEST.
    - THE EXPOSED SURFACE SHALL BE SCARIFIED TO A DEPTH OF 6", MOISTURE CONDITIONED TO 3 PERCENT OVER OPTIMUM MOISTURE CONTENT AND COMPACTED TO A MINIMUM RELATIVE DENSITY OF 90 PERCENT (ASTM D1557)
  - ENGINEERED COMPACTED FILL
    - REFER TO THE GEOTECHNICAL INVESTIGATION REPORT FOR RECOMMENDATIONS FOR STRUCTURAL FILL
    - STRUCTURAL FILL SHALL BE PLACED IN HORIZONTAL LAYERS, EACH APPROXIMATELY 8" THICK BEFORE COMPACTION, AND SHOULD BE CONDITIONED WITH WATER TO PRODUCE A SOIL WATER CONTENT NEAR OPTIMUM MOISTURE AND COMPACTED TO A MINIMUM RELATIVE DENSITY OF 90 PERCENT (ASTM D1557)
  - 4" THICK, CLEAN FREE-DRAINING MATERIAL SUCH AS 1/2" COARSE AGGREGATE
  - REFER TO GEOTECH REPORT AND ARCH DRAWINGS FOR VAPOR BARRIER. INSTALL PER MANUFACTURERS RECOMMENDATIONS FOR SEALING OF PENETRATIONS, JOINTS AND EDGES.
    - VAPOR BARRIER IS NOT TO BE PUNCTURED DURING CONSTRUCTION OF SLAB ON GRADE.
  - 2" THICK OPTIONAL SAND LAYER, SHALL BE LIGHTLY MOISTENED PRIOR TO PLACING CONCRETE.


SLAB ON GRADE EDGE AND SUBGRADE PREP




STEP IN CONCRETE SLAB ON GRADE




DEEPEMED FTG @ ANCHOR BOLT




SLEEVE THROUGH FOUNDATION (SLAB TURN-DOWN)




SLAB ON GRADE DEPRESSION




STEPPED FOOTING (BOTTOM ONLY)




STEP FOOTING




STEPPED FOOTING (BOTTOM ONLY)



REIN TIES AND STIRRUPS




SOG OPENING



CONC REINF @ INTERSECTION

REIN DEVELOPMENT LENGTH AND SPLICES



BAR SIZE	D
#3 THRU #8	6d
#9 THRU #11	8d

BAR SIZE	D	STANDARD HOOK DEVELOPMENT LENGTH 1 <sub>h</sub>		
		NORMAL WEIGHT		
		2,500	3,000	4,000
#3	2 1/4"	6"	0'-9"	0'-9"
#4	3"	8"	1'-0"	0'-11"
#5	3 3/4"	10"	1'-3"	1'-0"
#6	4 1/2"	12"	1'-6"	1'-3"
#7	5 1/4"	1'-2"	1'-9"	1'-5"
#8	6"	1'-4"	2'-0"	1'-10"
#9	9 1/2"	1'-7 1/2"	2'-3"	2'-1"
#10	10 3/4"	1'-10"	2'-7"	2'-4"
#11	12"	2'-0 1/2"	2'-10"	2'-7"

- NOTES:
- ALL HOOKED BARS SHALL EXTEND AS FAR AS POSSIBLE WITH A MINIMUM 2" END COVER AND WITH EMBEDMENT NOT LESS THAN SHOWN ON THE SCHEDULE UNLESS NOTED OTHERWISE ON PLANS.
  - MINIMUM SIDE COVER = 2d<sub>s</sub>
  - FOR LIGHTWEIGHT CONCRETE MULTIPLY LENGTHS IN SCHEDULE BY 1.3.


REIN HOOK DEVELOPMENT LENGTH AND BENDS

DATE  
09/28/2023  
SHEET


S-301




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.



51 CONTINUOUS WALL FOOTING  
2272-01-C1022 - S311




31 PIPES PARALLEL TO FOOTINGS  
2272-01-C1022 - S311




TYPE	HOLDOWN	ANCHOR	DIA (IN)	FASTENERS	BOUNDARY MEMBER MIN THICKNESS (IN)	MIN EMBED 1 <sub>e</sub> (IN)	ALLOWABLE LOADS (R <sub>u</sub> )	
							CORNER	MIDWALL
ⓂA	HDU4-SDS2.5	SSB16		10-SDS 1/2" x 2 1/2"	3	12 3/4	3,780	3,780
ⓂB	HDU5-SDS2.5	SSB20	3/4	14-SDS 1/2" x 2 1/2"	3	16 3/4	4,785	4,785
ⓂC	HDU5-SDS2.5	SSB24		14-SDS 1/2" x 2 1/2"	3	20 3/4	5,645*	5,645*
ⓂD	HDQ8-SDS3	SSB28	1/2	20-SDS 1/2" x 3"	4 1/2	24 1/4	9,230*	9,230*

- MINIMUM EDGE DISTANCE IS SHOWN ABOVE. ANCHOR LOCATIONS PER PLAN
- MINIMUM ANCHOR TO ANCHOR SPACING IS 3L
- \* = CAPACITY LIMITED BY HOLDDOWN
- DEEPEN FOOTING AT HOLDDOWN ANCHOR AS REQ'D PER DETAIL 32/-




52 MINIMUM DISTANCE FROM GRADE TO WOOD FRAMING  
2272-01-C1022 - S311




32 PIPES PERPENDICULAR TO FOOTINGS W/ STEM WALL  
2272-01-C1022 - S311


21 SSB ANCHOR & HOLDDOWN @ FOUNDATION  
2272-01-C1022 - S311



53 SOG DEPRESSION @ FTG  
2272-01-C1022 - S311




43 EXTERIOR CONTINUOUS WALL FTG W/ CURB  
2272-01-C1022 - S311




33 PIPES PERPENDICULAR TO FOOTINGS  
2272-01-C1022 - S311




22 SSB ANCHOR & HOLDDOWN @ FOUNDATION  
2272-01-C1022 - S311




54 NON-BEARING WALL ANCHORAGE @ SOG  
2272-01-C1022 - S311



44 TYPICAL VERT PIPES OR COND THROUGH FOOTING  
2272-01-C1022 - S311



34 TYPICAL VERT PIPES OR COND THROUGH FOOTING  
2272-01-C1022 - S311



23 TYPICAL VERT PIPES OR COND THROUGH FOOTING  
2272-01-C1022 - S311

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
CONCRETE DETAILS


DATE  
09/28/2023  
SHEET

S-311


N:\2000\2272-01-c1022-01-county\ad\Structural\ConDoc\Sheet\2272-01-C1022-S311.dwg, PLAN 2 - S311, Sep 28, 2023 4:26pm, oadpex



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




51 41 SPREAD FOOTING @ BEARING WALL POST 3/4" = 1'-0" 11




POST SIZE	MIN. SIDE COVER
4x4	0'-3"
6x6	0'-3"
8x8	0'-3"

POST SIZE	MIN. SIDE COVER
4x4	0'-4"
6x6	0'-5"
8x8	0'-6"



52 42 53 43 PORCH PAD FOOTING 1/2" = 1'-0" 33 54 44 55 45 MOMENT BASE POST @ POLE FOOTING 1/2" = 1'-0" 23 56 46 GRADE BEAM NTS 13 57 47 DEPEND EXTERIOR FOOTING 3/4" = 1'-0" 14



COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA  
 CONCRETE DETAILS

DATE  
 09/28/2023  
 SHEET

S-312

N:\2000\2727-01-c029-00-county\ad\Structural\ConDoc\Sheet\2727-01-C1022-S312.dwg, PLAN 2, \$312, Sep 28, 2023, 4:26pm, onspz






THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

BEARING/SHEAR WALL HEADER SCHEDULE												
4 INCH WALLS				3-STORY			2-STORY			1-STORY		
OPENING WIDTH	4x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS	3-STORY	2-STORY	1-STORY	OPENING WIDTH	6x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS
UP TO 3'-0"	4x4	2x	2x4	2x4				UP TO 3'-0"	6x4	2x	2x6	2x6
3'-0" - 5'-0"	4x6	2x	2x4	2x4				3'-0" - 5'-0"	6x6	2x	2x6	2x6
5'-0" - 7'-0"	4x8	(2) 2x	(2) 2x4	(2) 2x4				5'-0" - 7'-0"	6x8	(2) 2x	2x6	(2) 2x6

BEARING/SHEAR WALL HEADER SCHEDULE												
8 INCH WALLS				3-STORY			2-STORY			1-STORY		
OPENING WIDTH	8x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS	3-STORY	2-STORY	1-STORY	OPENING WIDTH	8x HEADER	SILL AT WINDOW	POST / TRIMMER	KING STUDS
UP TO 3'-0"	6x8 FLAT	2x	2x6	2x6				UP TO 3'-0"	8x8 FLAT	2x	2x8	2x8
3'-0" - 5'-0"	6x8 FLAT	2x	2x6	2x6				3'-0" - 5'-0"	8x8 FLAT	2x	2x8	2x8
5'-0" - 7'-0"	6x8 FLAT	(2) 2x	2x6	(2) 2x6				5'-0" - 7'-0"	8x12	(2) 2x	2x8	(2) 2x8



NOTES:  
 1. THIS DETAIL APPLIES AT ALL EXT WALLS AND INT LOAD BEARING WALLS AND ALSO APPLIES TO SHEAR WALL FRAMING  
 A. FOR SHEAR WALLS SEE 3415-402 FOR ADD'L REQUIREMENTS.  
 B. FOR INTERIOR NON-BEARING PARTITIONS SEE DETAIL 431.  
 2. HEADERS, KING STUDS AND OTHER REFERENCES ON PLAN GOVERN OVER THIS TYPICAL SCHED/DETAILS  
 3. PROVIDE A34 @ 4" WALLS & A35 @ 6" OR GREATER WALLS (ICC-ESR 2353)





FASTENING SCHEDULE PER 2022 CBC 2304.10.1		
CONNECTION	FASTENING	LOCATION
1. BLOCKING BETWEEN CEILING JOISTS, RAFTERS OR TRUSSES TO TOP PLATE OR OTHER FRAMING BELOW	3-8d COMMON	EACH END, TOENAIL
2. BLOCKING BETWEEN RAFTERS OR TRUSSES NOT AT THE WALL TO TOP PLATE, TO RAFTER OR TRUSS	2-8d COMMON	EACH END, TOENAIL
3. FLAT BLOCKING TO TRUSS AND WEB FILLER	2-16d COMMON	END NAIL
4. CEILING JOIST TO TOP PLATE	1-6d COMMON @ 6" OC	FACE NAIL
5. CEILING JOIST NOT ATTACHED TO PARALLEL RAFTER, LAPS OVER PARTITIONS	3-8d COMMON	EACH JOIST, TOENAIL
6. CEILING JOIST ATTACHED TO PARALLEL RAFTER (HEEL JOINT)	3-16d COMMON	FACE NAIL
7. COLLAR TIE TO RAFTER	3-10d COMMON	FACE NAIL
8. RAFTER OR ROOF TRUSS TO PLATE	3-10d COMMON	TOENAIL <sup>2</sup>
9. ROOF RAFTER TO RIDGE VALLEY OR HIP RAFTER; OR ROOF RAFTER TO 2-INCH RIDGE BEAM	2-16d COMMON	END NAIL
10. STUD TO STUD AND ABUTTING STUDS AT INTERSECTING WALL CORNERS	3-10d COMMON	TOENAIL
11. BUILT-UP HEADER (2" TO 2" HEADER)	1-6d COMMON	1/4" OC EACH EDGE, FACE NAIL
12. CONTINUOUS HEADER TO STUD	4-10d COMMON	TOENAIL
13. TOP PLATE TO TOP PLATE	1-6d COMMON	1/4" OC FACE NAIL
14. TOP PLATE TO TOP PLATE, AT END JOINTS	8-16d COMMON	EACH SIDE OF END JOINT, FACE NAIL (MINIMUM 24" LAP SPURCE LENGTH EACH SIDE OF END JOINT)
15. BOTTOM PLATE TO JOIST, RIM JOIST, BAND JOIST OR BLOCKING	2-16d COMMON	1/4" OC FACE NAIL
16. STUD TO TOP OR BOTTOM PLATE	4-8d COMMON	TOENAIL
17. TOP PLATES, LAPS AT CORNERS AND INTERSECTIONS	2-16d COMMON	END NAIL
18. JOIST TO SILL, TOP PLATE, OR GIRDER	3-8d COMMON	FACE NAIL
19. RIM JOIST, BAND JOIST, OR BLOCKING TO TOP PLATE, SILL OR OTHER FRAMING BELOW	8d COMMON	TOENAIL
20. RIM JOIST, BAND JOIST, OR BLOCKING TO TOP PLATE, SILL OR OTHER FRAMING BELOW	8d COMMON	6" OC, TOENAIL
21. 1" x 6" SUBFLOOR OR LESS TO EACH JOIST	2-8d COMMON	FACE NAIL
22. 2" SUBFLOOR TO JOIST OR GIRDER	2-16d COMMON	FACE NAIL
23. BUILT-UP GIRDER AND BEAMS, 2" LUMBER LAYERS	20d COMMON (4" x 0.192)	3/2" OC FACE NAIL AT TOP AND BOTTOM STAGGERED ON OPPOSITE SIDE
24. LEDGER STRIP SUPPORTING JOIST OR RAFTERS	3-16d COMMON	EACH JOIST OR RAFTER, FACE NAIL
25. JOIST TO BAND JOIST OR RIM JOIST	3-16d COMMON	END NAIL
27. BRIDGING OR BLOCKING TO JOIST, RAFTER OR TRUSS	2-8d COMMON	EACH END, TOENAIL

NOTES:  
 a. THIS NAILING SCHEDULE SHALL ONLY BE USED IF CONDITION IS NOT OTHERWISE DETAILED OR SPECIFIED ON THE CONSTRUCTION DOCUMENTS. COMMON NAILS SHALL BE USED EXCEPT WHERE OTHERWISE STATED  
 b. WHERE A RAFTER IS FASTENED TO AN ADJACENT PARALLEL CEILING JOIST IN ACCORDANCE WITH THIS SCHEDULE AND THE CEILING JOIST IS FASTENED TO THE TOP PLATE IN ACCORDANCE WITH THIS SCHEDULE, THE NUMBER OF TOENAILS IN THE RAFTER SHALL BE PERMITTED TO BE REDUCED BY ONE NAIL



EXTERIOR WALL / INTERIOR WALL BEARING WALL FRAMING



INTERIOR NON-BEARING PARTITION WALL FRAMING



NAILING SCHEDULE



COUNTY OF SAN LUIS OBISPO  
 ACCESSORY DWELLING UNIT  
 SAN LUIS OBISPO, CA


TYPICAL WOOD DETAILS

DATE  
 09/28/2023  
 SHEET


S-401



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




**SHEAR WALL INTERSECTION** NTS 42




**TYPICAL SHEAR WALL ELEVATION AND SCHEDULE** NTS 13

WALL SYMBOL	STRUCT SHEATHING	FRAMING SIZE	NAILING				SILL NAILING		A35s	ANCHOR BOLTING	CAPACITY PER 2015 AWC SDPWS
			(2) 2x STUD	EDGE	INTERMEDIATE SUPPORTS	NAILS / LAG SCREWS	SDS SCREWS OPTION				
△	15/32' STRUCT 1 PLYWOOD	2x	10d @ 9" OC	8d @ 6" OC	8d @ 12" OC	16d @ 6" OC	12" OC	24" OC	5/8" DIA @ 48" OC	280 PLF	
△	15/32' STRUCT 1 PLYWOOD	2x	10d @ 8" OC	10d @ 6" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	12" OC	16" OC	5/8" DIA @ 48" OC	340 PLF	
△	15/32' STRUCT 1 PLYWOOD	2x	10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	8" OC	12" OC	5/8" DIA @ 32" OC	510 PLF	
△	15/32' STRUCT 1 PLYWOOD	2x	10d @ 4" OC	10d @ 3" OC	10d @ 12" OC	5/8" LAG SCREWS @ 16" OC	6" OC	8" OC	5/8" DIA @ 32" OC	665 PLF	
△	15/32' STRUCT 1 PLYWOOD	2x	10d @ 3" OC	10d @ 2" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	4" OC	8" OC	5/8" DIA @ 24" OC	860 PLF	
△	15/32' STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 5" OC	10d @ 4" OC	10d @ 12" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 8" OC *	6" OC	5/8" DIA @ 16" OC	1020 PLF	
△	15/32' STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 4" OC	10d @ 3" OC	10d @ 8" OC	5/8" LAG SCREWS @ 8" OC	(2) @ 6" OC *	A34 @ 4" OC	5/8" DIA @ 16" OC	1330 PLF	
△	15/32' STRUCT 1 PLYWOOD (EACH FACE OF WALL)	3x	(2) 10d @ 3" OC	10d @ 2" OC	10d @ 6" OC	5/8" LAG SCREWS @ 6" OC	(2) @ 4" OC *	LTP4 @ 4" OC	5/8" DIA @ 8" OC	1740 PLF	


- NOTES:
- ALL PLYWOOD SHALL BE 5 PLY MINIMUM WITH A SPAN RATING OF 32/16 AND ALL PANEL EDGES SHALL BE BLOCKED. PROVIDE 1/8" GAP AT ALL PANEL JOINTS.
  - ALL NAILS SHALL BE COMMON NAILS.
  - PROVIDE E.N. AT ALL END STUDS, STUDS/POSTS WITH HOLDOWNS OR TIE DOWN STRAPS, SILL PLATES AND TOP PLATES.
  - WHERE 10d NAILS ARE 3 INCHES ON CENTER OR LESS, NAILS SHALL BE STAGGERED.
  - NAILS SHALL BE 1/2" INCH MINIMUM FROM PLYWOOD PANEL EDGE AND 3/8" INCH MINIMUM FROM CONNECTING MEMBER EDGE WHERE SHEAR EXCEEDS 300 PLF.
  - USE 3x FRAMING AT BOTTOM SILL PLATES. BLOCKING AND ALL STUDS AT ADJACENT PANEL EDGES WHERE SHEAR EXCEEDS 300 PLF. STRUCTURALLY ACCEPTABLE TO USE (2) 2x INSTEAD OF 3x FRAMING AT BOTTOM SILL PLATES.
  - WHERE SILL SHEAR TRANSFER IS THROUGH LAG SCREWS, SILL PLATE SHALL BE A MINIMUM OF 2 1/2" THICK.
  - LAG SCREWS SHALL BE 6 INCHES LONG AND HOLES ARE TO BE PRE-DRILLED AS TO NOT SPLIT BLOCKING/RIM.
  - SEE ELEVATION ABOVE FOR TYPICAL CONSTRUCTION.
  - REFER TO PLATE WASHER DETAIL FOR REQUIREMENTS.
  - LENGTHY ANCHOR BOLTS AS REQUIRED FOR EMBEDMENT AND SILL PLATE THICKNESS.
  - ORIENTED STRAND BOARD (OSB) MAY BE SUBSTITUTED FOR PLYWOOD NOTED ABOVE PROVIDED IT IS RATED BY APA'S PERFORMANCE STANDARD RATING AND IS OF THE SAME NUMBER OF LAYERS AS PLYWOOD PLY INDICATED.
  - LIMITATIONS OF MECHANICAL PENETRATIONS IN SHEAR WALLS:
    - A. 4 1/2" MAX PENETRATION.
    - B. NO CUTS OR HOLES IN SHEATHING WITHIN 16" OF CORNERS. SQUARE PENETRATIONS SHALL RADIUS EDGES. DO NOT OVER CUT HOLE WITH SAW.
  - ASSUMES A 1 1/4" MIN LSI RIM BOARD. FASTENER EDGE DIST IS 5/8" MIN & 6" END DISTANCE MIN. 2" MIN PENETRATION INTO RIM BOARD.
  - WALL W/ DOUBLE SIDED PLYWOOD REQUIRE (2) RIM BOARDS.
  - SIMPSON LTP4 CLIP SHALL BE INSTALLED IN A HORIZONTAL ORIENTATION. IF CLIP IS INSTALLED OVER THE SHEATHING, 0.131" x 2 1/2" NAILS SHALL BE USED.




**STRAP AT STEP IN SHEAR WALL SILL PLATE** NTS 53 **TYPICAL BLOCKING DETAIL** NTS 43



**FORCE TRANSFER AROUND OPENINGS** NTS 44



**PLATE WASHER DETAIL** NTS 34



**DOUBLE SIDED SHEAR WALL** NTS 24 **2x STUD NAILING @ ADJOINING PANEL EDGES** NTS 14

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA  
**TYPICAL WOOD DETAILS**


DATE  
09/28/2023  
SHEET

**S-402**


N:\2020\2727-01-c022-ko-county-adu\Structural\Drawings\2727-01-C022-5402.dwg, PLAN 2 - 5402.dwg, Sep 28, 2023 4:26pm, odepce



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




51 DBL TOP PLATE SPLICE NAILING 2227-01-C102-1463 NTS 32




TYPE	LOCATION	SHEATHING THICKNESS	SHEATHING GRADE	SPAN RATING	BLOCKING	NAILS	BOUNDARY NAILING (BN)	EDGE NAILING AT CONT. PANEL EDGES (EN)	EDGE NAILING AT OTHER PANEL EDGES (EN)	FIELD NAILING (FN)	PANEL EDGE SUPPORT OR NOMINAL MEMBER WIDTH AT PANEL EDGES	LINES OF FASTENERS
A	ROOF	SEE NOTE 5	SHEATHING	32 / 16	NO	10d	6	-	6	12	H-CLIPS	1
B	FLOOR	3/4"	STURD-FLOOR	48 / 24	NO	10d	6	-	6	12	T&G	1
C	FLOOR	3/4"	STURD-FLOOR	48 / 24	YES	10d	2 1/2	2 1/2	4	12	2x4 FLAT	1

- NOTES:
- DIAPHRAGM SHALL BE GLUED TO FLOOR FRAMING PRIOR TO NAILING. REFER TO PROJECT GENERAL NOTES.
  - MINIMUM EDGE DISTANCE FOR NAILS SHALL BE 1/2" FROM SHEATHING EDGE AND 3/8" FROM LUMBER EDGE.
  - NAILS SHALL BE DRIVEN TIGHT TO TOP OF PLYWOOD SURFACE AND SHALL NOT PENETRATE THE TOP OF PLYWOOD MORE THAN COMMONLY EXPECTED WITH HAMMER DRIVEN NAILS.
  - WHERE H-CLIPS ARE SPECIFIED, THEY SHOULD BE INSTALLED AS FOLLOWS:
    - ONE H-CLIP SHALL BE PLACED BETWEEN ABUTTING PANELS AT A LOCATION MIDWAY BETWEEN EACH PAIR OF TRUSSES, RAFTERS OR JOISTS. HOWEVER, (2) H-CLIPS ARE REQUIRED BETWEEN SUPPORTS WHEN SPACED 48 INCHES ON CENTER.
    - USE THE SAME SIZE PANEL EDGE CLIP AS THE PANEL THICKNESS. H-CLIPS MUST FIT SNUGLY.
    - ABUTTING WOOD STRUCTURAL PANELS BE FITTED AS CLOSELY AS CLIPS PERMIT. OCCASIONAL MISFIT OF ABUTTING SHEETS MAY BE TOLERATED PROVIDING THAT GAPS DO NOT EXCEED MAXIMUM OPENING OF 1/4".
  - ROOF SHEATHING THICKNESS SHALL BE INSTALLED AS FOLLOWS:
    - 3/4" @ SINGLE PLY OR ASPHALT SHINGLES
    - 1/2" @ TILE
    - 3/4" @ TILE WITH MORTAR
  - STRUCTURALLY ACCEPTABLE TO USE "SHEATHING" SHEATHING GRADE @ FLOOR LOCATIONS WITHOUT GYPCRETE TOPPING


52 42 32 PLYWOOD DIAPHRAGM SHEATHING NTS 12



53 43 33 OPENING AT FRAMING NTS 23



54 44 34 TYP JOIST BLOCKING NTS 14



54 44 34 TYP JOIST BLOCKING NTS 14

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
TYPICAL WOOD DETAILS

N:\2000\2277-01-cu29-40-county\adu\structural\ConDoc\Sheet\2277-01-C102-1463.dwg, PLAN 2 - S403.dwg, 28-Sep-2023 4:26pm, oispet




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

	51	41	31

	52	42	32
--	----	----	----


	53	43	33
--	----	----	----

	54	44	34
--	----	----	----




HEADER OR BEAM DEPTH	MAX ROUND HOLE SIZE
9 1/2"	3"
11 7/8"	3 3/8"
14'-16"	4 3/8"

- 1.55E LSL NOTES:
- ALLOWED HOLE ZONE SUITABLE FOR HEADERS AND BEAMS WITH UNIFORM AND/OR CONCENTRATED LOADS ANYWHERE ALONG THE MEMBER.
  - ROUND HOLES ONLY.
  - NO HOLES IN HEADERS OR BEAMS IN PLANK ORIENTATION.




HEADER OR BEAM DEPTH	MAX ROUND HOLE SIZE
4 1/2"	1"
5 1/2"	1 3/4"
7 1/4' - 20'	2"

- LVL/PSL/1.3E LSL:
- ALLOWED HOLE ZONE SUITABLE FOR HEADERS AND BEAMS WITH UNIFORM LOADS ONLY.
  - ROUND HOLES ONLY.
  - NO HOLES IN CANTILEVERS.
  - NO HOLES IN HEADERS OR BEAMS IN PLANK ORIENTATION.



DO NOT CUT, NOTCH, OR DRILL HOLES IN HEADERS OR BEAMS EXCEPT AS INDICATED IN THE ILLUSTRATIONS AND TABLES


ALLOWABLE HOLES THRU ENGINEERED LUMBER HEADERS & BEAMS NTS 12



- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME JOIST CROSS SECTION WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
  - NOTCH WIDTHS GREATER THAN SHOWN IN TABLE NOT PERMITTED WITHOUT STRUCTURAL ENGINEER'S APPROVAL.
  - NO NOTCHES OR HOLES PERMITTED ANYWHERE IN CANTILEVERED ELEMENTS WITHOUT STRUCTURAL ENGINEER'S APPROVAL.


JOIST SIZE	MAX HOLE	MAX NOTCH DEPTH	MAX END NOTCH	MAX NOTCH LENGTH
2x4	NONE	NONE	NONE	NONE
2x6	1 1/2"	1/2"	1 3/8"	1 1/2"
2x8	2 3/8"	1 1/2"	1 3/8"	2 3/8"
2x10	3"	1 1/2"	2 3/8"	3"
2x12	3 3/4"	1 1/2"	2 3/8"	3 3/4"

SAWN LUMBER AND RAFTER JOIST NOTCHING AND BORING LIMITATIONS NTS 13



STUD SIZE (IN)	APPLICATION	MAX HOLE DIAMETER (IN)	MAX NOTCH DEPTH (IN)
2x4	NON-BEARING	2 3/8"	1 3/8"
	EXTERIOR/BEARING	1 3/8"	1/2"
2x6	NON-BEARING	3 1/4"	2 3/8"
	EXTERIOR/BEARING	2 3/8"	1 3/8"

- NOTES:
- NOTCHING AND BORING NOT PERMITTED IN THE SAME STUD SECTION.
  - NO MORE THAN 2 SUCCESSIVE DBL. STUDS ARE PERMITTED TO HAVE 60% MAX BORED HOLES.



TOP PL OR SILL PL	A	B	C	D	E	F
2x4	3/8"	1/2"	1/2"	1/2"	3/4"	6
2x6	1/2"	3/4"	3/4"	3/4"	1"	9
2x8	3/8"	3"	3/4"	3/4"	1 1/4"	12

TYP WALL NOTCH AND BORING LIMITATIONS NTS 24

TOP PL AND SILL NOTCH AND BORING LIMITATIONS NTS 14

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

TYPICAL WOOD DETAILS


DATE  
09/28/2023  
SHEET

S-404


N:\2000\2727-01\_c029-loc-county\adu\Structural\Sheet\Rev\2727-01\_C102-1\_5404.dwg, PLAN 2 - 5404.dwg, Sep 28, 2023 4:26pm, onpeter




THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.




DIAPH TRANSITION W/ OVERHANG  
2272-01-C1022-1461 1" = 1'-0" 51




INTERIOR DRAG TRUSS  
2272-01-C1022-1461 1" = 1'-0" 41




SHEATHING OVER ROOF RIDGE  
2272-01-C1022-1461 1" = 1'-0" 31




TRUSS TO GIRDER TRUSS  
2272-01-C1022-1461 1" = 1'-0" 32




GABLE END TRUSS  
2272-01-C1022-1461 NTS 23




DIAPH TRANSITION W/ OVERHANG  
2272-01-C1022-1461 1" = 1'-0" 52




INTERIOR SHEAR WALL (ROOF TRUSS PARALLEL)  
2272-01-C1022-1461 1" = 1'-0" 42




TRUSS TO GIRDER TRUSS W/ WALL BELOW  
2272-01-C1022-1461 1" = 1'-0" 33




CALIFORNIA FRAMING SLEEPER  
2272-01-C1022-1461 NTS 34




ROOF TRUSS PERP TO EXTERIOR WALL  
2272-01-C1022-1461 NTS 13




BEAM TO POST CONNECTION  
2272-01-C1022-1461 1" = 1'-0" 53




TRUSS OVER NON-BEARING PARTITION  
2272-01-C1022-1461 1" = 1'-0" 43




GABLE END TRUSS W/ LOOKOUT @ BEAM  
2272-01-C1022-1461 1" = 1'-0" 54




ROOF TRUSS PERP TO BEAM  
2272-01-C1022-1461 NTS 24




ROOF TRUSS PERP TO EXTERIOR WALL  
2272-01-C1022-1461 NTS 14




GABLE END TRUSS W/ LOOKOUT @ BEAM  
2272-01-C1022-1461 1" = 1'-0" 54




ROOF TRUSS PERP TO BEAM  
2272-01-C1022-1461 1" = 1'-0" 44



TRUSS INTERIOR BEARING WALL  
2272-01-C1022-1461 1" = 1'-0" 34



CALIFORNIA FRAMING SLEEPER  
2272-01-C1022-1461 NTS 25



ROOF TRUSS PERP TO EXTERIOR WALL  
2272-01-C1022-1461 NTS 15

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA

ROOF FRAMING DETAILS

DATE  
09/28/2023  
SHEET

S-421

N:\2000\2727-01-c1022-alo-county\adu\structural\ConDoc\Sheet\Roof\2727-01-C1022-1461.dwg, PLAN 2 - 5421, Sep 28, 2023, 4:26pm, odep



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

	51	41	<b>TRELLIS FRAMING</b> <small>2727-01-C1022-1402-31</small>	3/4" = 1'-0"	31		
	52	42	<b>POST TO BEAM CONNECTION (MODERN STYLE)</b> <small>2727-01-C1022-1402-32</small>	NTS	32	<b>ROOF TRUSS PERP TO EXTERIOR WALL</b> <small>2727-01-C1022-1402-22</small>	1" = 1'-0"
	53	43			33	<b>RAFTER @ RIDGE BM</b> <small>2727-01-C1022-1402-13</small>	1" = 1'-0"
	54	44	<b>RIDGE BM @ TRUSS</b> <small>2727-01-C1022-1402-24</small>	1" = 1'-0"	24	<b>RAFTER @ EXTERIOR SHEAR WALL</b> <small>2727-01-C1022-1402-14</small>	1" = 1'-0"

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA  
**ROOF FRAMING DETAILS**

DATE  
 09/28/2023  
 SHEET  
**S-422**

N:\2000\2727-01-c1022-acc-county\adu\structural\ConDoc\Sheet\2727-01-C1022-1402.dwg, PLAN 2 - 1402.dwg, 28. 2023 4:26pm, ospet

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 2 of 12)

ENERGY USE SUMMARY table with columns: Energy Use, Standard Design Source Energy (EDR1), Standard Design TDV Energy (EDR2), Proposed Design Source Energy (EDR1), Proposed Design TDV Energy (EDR2), Compliance Margin (EDR1), Compliance Margin (EDR2). Rows include Space Heating, Space Cooling, IAQ Ventilation, Water Heating, Self Utilization/Flexibility Credit, and North Facing Efficiency Compliance Total.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-03  
Report Generated: 2023-09-26 21:06:16

CF1R-PRF-01E  
(Page 2 of 12)

Project Name: Residential Building  
Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

ENERGY DESIGN RATINGS table with columns: Energy Design Ratings, Proposed Design, and Compliance Margins. Rows include Standard Design, North Facing, East Facing, South Facing, and West Facing.

HERS Provider: CZ-4-03  
Report Generated: 2023-09-26 21:06:16

CF1R-PRF-01E  
(Page 1 of 12)

Project Name: Residential Building  
Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

GENERAL INFORMATION table with columns: Project Name, Project Location, Project Description, etc. Rows include Project Name, Project Location, Project Description, etc.

HERS Provider: CZ-4-01  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 6 of 12)

REQUIRED PV SYSTEMS table with columns: DC System Size (kWdc), Exception, Module Type, Array Type, Power Electronics, CFI, Azimuth, Tilt, Array Angle, Tilt: (x in 12), Inverter Eff. (%), Annual Solar Access (%).

REQUIRED SPECIAL FEATURES  
The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.

HERS FEATURE SUMMARY  
The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis.

BUILDING - FEATURES INFORMATION table with columns: Project Name, Conditioned Floor Area (ft²), Number of Dwelling Units, Number of Bedrooms, Number of Zones, Number of Identification Cooling Systems, Number of Water Heating Systems.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-06  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 5 of 12)

ENERGY USE INTENSITY table with columns: Standard Design (kBtu/ft² · yr), Proposed Design (kBtu/ft² · yr), Compliance Margin (kBtu/ft² · yr), Margin Percentage. Rows include North Facing, East Facing, South Facing, and West Facing.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-05  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 4 of 12)

ENERGY USE SUMMARY table with columns: Energy Use, Standard Design Source Energy (EDR1), Standard Design TDV Energy (EDR2), Proposed Design Source Energy (EDR1), Proposed Design TDV Energy (EDR2), Compliance Margin (EDR1), Compliance Margin (EDR2). Rows include Space Heating, Space Cooling, IAQ Ventilation, Water Heating, Self Utilization/Flexibility Credit, and West Facing Efficiency Compliance Total.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-04  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 9 of 12)

BUILDING ENVELOPE - HERS VERIFICATION table with columns: Quality Insulation Installation (QII), High R-value Spray Foam Insulation, Building Envelope Air Leakage, CFM50, CFM50.

WATER HEATING SYSTEMS table with columns: Name, System Type, Distribution Type, Water Heater Name, Number of Units, Solar Heating System, Compact Distribution, HERS Verification, Water Heater Name (W).

WATER HEATERS - NECA HEAT PUMP table with columns: Name, # of Units, Tank Vol. (gal), NECA Heat Pump Brand, NECA Heat Pump Model, Tank Location, Duct Inlet Air Source, Duct Outlet Air Source.

WATER HEATING - COMPACT DISTRIBUTION table with columns: Dwelling Unit type, Water Heating System Name, Master Bath distance of furthest fixture to Water Heater (ft), Kitchen distance of furthest fixture to Water Heater (ft), Furthest Third furthest fixture to Water Heater (ft), Compactness Factor, HERS Verification.

WATER HEATING - HERS VERIFICATION table with columns: Name, Pipe Insulation, Parallel Piping, Compact Distribution, Compact Distribution Type, Recirculation Control, Shower Drain Water Heat Recovery.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-09  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 8 of 12)

FENESTRATION / GLAZING table with columns: Name, Type, Surface, Orientation, Azimuth, Width (ft), Height (ft), Mult., Area (ft²), U-factor, U-factor Source, SHGC, SHGC Source, Exterior Shading.

SLAB FLOORS table with columns: Name, Zone, Area (ft²), Perimeter (ft), Edge Insul. R-value and Depth, Edge Insul. R-value and Depth, Carpeted Fraction, Heated.

OPAQUE SURFACE CONSTRUCTIONS table with columns: Construction Name, Surface Type, Construction Type, Framing, Total Cavity R-value, Interior / Exterior Continuous R-value, U-factor, Assembly Layers.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-08  
Report Generated: 2023-09-26 21:06:16

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building  
Calculation Description: Title 24 Analysis

Calculation Date/Time: 2023-09-26T21:05:52-07:00  
Input File Name: 3 Bedrm Plan -Plan 2a CZ 4.rbd22x

CF1R-PRF-01E  
(Page 7 of 12)

ZONE INFORMATION table with columns: Zone Name, Zone Type, HVAC System Name, Zone Floor Area (ft²), Avg. Ceiling Height, Water Heating System 1, Status.

OPAQUE SURFACES table with columns: Name, Zone, Construction, Azimuth, Orientation, Gross Area (ft²), Window and Door Area (ft²), Tilt (deg).

ATTIC table with columns: Name, Construction, Type, Roof Rise (x in 12), Roof Reflectance, Roof Emittance, Radiant Barrier, Cool Roof.

FENESTRATION / GLAZING table with columns: Name, Type, Surface, Orientation, Azimuth, Width (ft), Height (ft), Mult., Area (ft²), U-factor, U-factor Source, SHGC, SHGC Source, Exterior Shading.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance  
Registration Date/Time: Report Version: 2022.0.000  
HERS Provider: CZ-4-07  
Report Generated: 2023-09-26 21:06:16



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ENERGY COMPLIANCE - PLAN 2A

DATE  
09/28/2023

SHEET  
T24 - 201

C:\Users\jacob\Documents\T24-01\_SLO County ADU\_CD\_CENTRAL\_2023\_jacob\REV1.dwg

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 12 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 11:05:52-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 4.ribd22x

**DOCUMENTATION AUTHOR'S DECLARATION STATEMENT**

1. I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Jennifer Rennick Documentation Author Signature: \_\_\_\_\_  
 Company: In Balance Green Consulting Signature Date: 9/26/2023  
 Address: \_\_\_\_\_ CEA/HERS Certification Identification (if applicable): \_\_\_\_\_  
 City/State/Zip: \_\_\_\_\_ Phone: \_\_\_\_\_

**RESPONSIBLE PERSON'S DECLARATION STATEMENT**

I certify the following under penalty of perjury, under the laws of the State of California:

- I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.
- I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
- The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with the building permit application.

Responsible Designer Name: \_\_\_\_\_ Responsible Designer Signature: \_\_\_\_\_  
 Company: \_\_\_\_\_ Date Signed: \_\_\_\_\_  
 Address: \_\_\_\_\_ License: \_\_\_\_\_  
 City/State/Zip: \_\_\_\_\_ Phone: \_\_\_\_\_

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance HERS Provider: **CZ-4-12**  
 Report Version: 2022.0.000 Report Generated: 2023-09-26 21:06:16  
 Schema Version: rev 20220901

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 11 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 11:05:52-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 4.ribd22x

**INDOOR AIR QUALITY (IAQ) FANS**

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status
SFam IAQVentRot	53	0.35	Exhaust	No	N/A / N/A	No	Yes	

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance HERS Provider: **CZ-4-11**  
 Report Version: 2022.0.000 Report Generated: 2023-09-26 21:06:16  
 Schema Version: rev 20220901

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 10 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 11:05:52-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 4.ribd22x

**SPACE CONDITIONING SYSTEMS**

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
HVAC System1	Heat pump heating cooling	Heat Pump System 1	4	Heat Pump System 1	4	n/a	n/a	Setback

**HVAC - HEAT PUMPS**

01	02	03	04	05	06	07	08	09	10	11	12	13		
Name	System Type	Number of Units	Heating			Cooling			Efficiency Type	SEER / SEER2	EER / EER / CEER	Zonally Controlled	Compressor Type	HERS Verification
			Efficiency Type	HSPF / HSPF2 / COP	Cap 47	Cap 17	Efficiency Type	SEER / SEER2						
Heat Pump System 1	VCHP-ductless	4	HSPF2	8	9000	7200	EER2SEER2	16	12.4	Not Zonal	Multi-speed	Heat Pump System 1-herstump		

**HVAC HEAT PUMPS - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-herstump	Not Required	0	Required	Required	Yes	Yes	Yes	Yes

**VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing &amp; Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance HERS Provider: **CZ-4-10**  
 Report Version: 2022.0.000 Report Generated: 2023-09-26 21:06:16  
 Schema Version: rev 20220901



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA

---

**ENERGY COMPLIANCE - PLAN 2A**

DATE  
09/28/2023

SHEET  
**T24 - 202**

CZ-4-16



CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 3 of 12)

ENERGY USE SUMMARY table with columns: Energy Use, Standard Design Source Energy (EDR1), Standard Design TDV Energy (EDR2), Proposed Design Source Energy (EDR1), Proposed Design TDV Energy (EDR2), Compliance Margin (EDR1), Compliance Margin (EDR2). Rows include Space Heating, Space Cooling, IAQ Ventilation, Water Heating, Self Utilization/Flexibility Credit, North Facing Efficiency Compliance Total, etc.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-03 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45

CF1R-PRF-01E (Page 2 of 12)
Calculation Date/Time: 2023-09-26T20:58:21-07:00
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x

Table with columns: Energy Design Option, Standard Design, Proposed Design. Rows include Space Heating, East Facing, South Facing, West Facing. Includes compliance margin and SHGC values.

ENERGY CODE COMPLIANCE SUMMARY
Compliance Margin
This certificate is provided by the County of San Luis Obispo. It is not to be used for any other purpose.
HERS Provider: Report Generated: 2023-09-26 20:58:45

CZ-5-02

CF1R-PRF-01E (Page 4 of 12)
Calculation Date/Time: 2023-09-26T20:58:21-07:00
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x

GENERAL INFORMATION table with columns: Field, Value. Rows include Project Name, Project Location, City, State, County, etc.

COMPLIANCE RESULTS table with columns: Item, Description, Status. Rows include Building Compliance with Comparison, This Building Incorporates Features that require Field Verification/Inspection, etc.

CZ-5-01

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 6 of 12)

REQUIRED PV SYSTEMS table with columns: Item, DC System Size (kWdc), Exception, Module Type, Array Type, Power Electronics, CFI, Azimuth (deg), Tilt Input, Array Angle (deg), Tilt: (x in 12), Inverter Eff. (%), Annual Solar Access (%).

- REQUIRED SPECIAL FEATURES: The following are features that must be installed as condition for meeting the modeled energy performance for this computer analysis.
Ceiling has high level of insulation
Variable capacity heat pump compliance option (verification details from VCHP Staff report, Appendix B, and PA3)

- HERS FEATURE SUMMARY: The following is a summary of the features that must be field-verified by a certified HERS Rater as a condition for meeting the modeled energy performance for this computer analysis.
Quality insulation installation (QI1)
Indoor air quality ventilation
Kitchen range hood
Verified EER/SEER2

BUILDING - FEATURES INFORMATION table with columns: Item, Value. Rows include Project Name, Conditioned Floor Area (ft²), Number of Dwelling Units, etc.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-06 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 5 of 12)

ENERGY USE INTENSITY table with columns: Orientation, Standard Design (kbtu/ft²-yr), Proposed Design (kbtu/ft²-yr), Compliance Margin (kbtu/ft²-yr), Margin Percentage. Rows include North Facing, East Facing, South Facing, West Facing.

Notes: 1. Gross EUI is Energy Use Total (not including PV) / Total Building Area. 2. Net EUI is Energy Use Total (including PV) / Total Building Area.

CZ-5-05

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 4 of 12)

ENERGY USE SUMMARY table with columns: Energy Use, Standard Design Source Energy (EDR1), Standard Design TDV Energy (EDR2), Proposed Design Source Energy (EDR1), Proposed Design TDV Energy (EDR2), Compliance Margin (EDR1), Compliance Margin (EDR2). Rows include Space Heating, Space Cooling, IAQ Ventilation, Water Heating, Self Utilization/Flexibility Credit, South Facing Efficiency Compliance Total, etc.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-04 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 9 of 12)

BUILDING ENVELOPE - HERS VERIFICATION table with columns: Item, Value. Rows include Quality Insulation Installation (QI1), High R-value Spray Foam Insulation, Building Envelope Air Leakage, CFM50.

WATER HEATING SYSTEMS table with columns: Item, Name, System Type, Distribution Type, Water Heater Name, Number of Units, Solar Heating System, Compact Distribution, HERS Verification, Water Heater Name (V).

WATER HEATERS - NECA HEAT PUMP table with columns: Item, Name, # of Units, Tank Vol. (gal), NECA Heat Pump Brand, NECA Heat Pump Model, Tank Location, Duct Inlet Air Source, Duct Outlet Air Source.

WATER HEATING - COMPACT DISTRIBUTION table with columns: Item, Dwelling Unit type, Water Heating System Name, Master Bath distance of furthest fixture to Water Heater (ft), Kitchen distance of furthest fixture to Water Heater (ft), Furthest Third furthest fixture to Water Heater (ft), Compactness Factor, HERS Verification.

WATER HEATING - HERS VERIFICATION table with columns: Item, Name, Pipe Insulation, Parallel Piping, Compact Distribution, Compact Distribution Type, Recirculation Control, Shower Drain Water Heat Recovery.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-09 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 8 of 12)

FENESTRATION / GLAZING table with columns: Item, Name, Type, Surface, Orientation, Azimuth, Width (ft), Height (ft), Mult., Area (ft²), U-factor, U-factor Source, SHGC, SHGC Source, Exterior Shading.

SLAB FLOORS table with columns: Item, Name, Zone, Area (ft²), Perimeter (ft), Edge Insul. R-value and Depth, Edge Insul. R-value and Depth, Carpeted Fraction, Heated.

OPAQUE SURFACE CONSTRUCTIONS table with columns: Item, Construction Name, Surface Type, Construction Type, Framing, Total Cavity R-value, Interior / Exterior Continuous R-value, U-factor, Assembly Layers.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-08 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45

CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD

Project Name: Residential Building Calculation Date/Time: 2023-09-26T20:58:21-07:00 CF1R-PRF-01E
Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x (Page 7 of 12)

ZONE INFORMATION table with columns: Item, Zone Name, Zone Type, HVAC System Name, Zone Floor Area (ft²), Avg. Ceiling Height, Water Heating System 1, Status.

OPAQUE SURFACES table with columns: Item, Name, Zone, Construction, Azimuth, Orientation, Gross Area (ft²), Window and Door Area (ft²), Tilt (deg).

ATTIC table with columns: Item, Name, Construction, Type, Roof Rise (x in 12), Roof Reflectance, Roof Emittance, Radiant Barrier, Cool Roof.

FENESTRATION / GLAZING table with columns: Item, Name, Type, Surface, Orientation, Azimuth, Width (ft), Height (ft), Mult., Area (ft²), U-factor, U-factor Source, SHGC, SHGC Source, Exterior Shading.

Registration Number: CA Building Energy Efficiency Standards - 2022 Residential Compliance Registration Date/Time: Report Version: 2022.0.000 HERS Provider: CZ-5-07 Scheme Version: rev 20220901 Report Generated: 2023-09-26 20:58:45



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRACT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO
ACCESSORY DWELLING UNIT
SAN LUIS OBISPO, CA
ENERGY COMPLIANCE - PLAN 2A

DATE: 09/28/2023

SHEET: T24 - 203

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 12 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 20:58:21-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x

**DOCUMENTATION AUTHOR'S DECLARATION STATEMENT**

1. I certify that this Certificate of Compliance documentation is accurate and complete.

Documentation Author Name: Jennifer Rennick Documentation Author Signature: \_\_\_\_\_  
 Company: In Balance Green Consulting Signature Date: 9/26/2023  
 Address: \_\_\_\_\_ CEA/HERS Certification Identification (if applicable): \_\_\_\_\_  
 City/State/Zip: \_\_\_\_\_ Phone: \_\_\_\_\_

**RESPONSIBLE PERSON'S DECLARATION STATEMENT**

I certify the following under penalty of perjury, under the laws of the State of California:

- I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the building design identified on this Certificate of Compliance.
- I certify that the energy features and performance specifications identified on this Certificate of Compliance conform to the requirements of Title 24, Part 1 and Part 6 of the California Code of Regulations.
- The building design features or system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, plans and specifications submitted to the enforcement agency for approval with the building permit application.

Responsible Designer Name: \_\_\_\_\_ Responsible Designer Signature: \_\_\_\_\_  
 Company: \_\_\_\_\_ Date Signed: \_\_\_\_\_  
 Address: \_\_\_\_\_ License: \_\_\_\_\_  
 City/State/Zip: \_\_\_\_\_ Phone: \_\_\_\_\_

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_ HERS Provider: **CZ-5-12**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-26 20:58:45  
 Schema Version: rev 20220901 Schema Version: rev 20220901

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 11 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 20:58:21-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x

**INDOOR AIR QUALITY (IAQ) FANS**

01	02	03	04	05	06	07	08	09
Dwelling Unit	Airflow (CFM)	Fan Efficacy (W/CFM)	IAQ Fan Type	Includes Heat/Energy Recovery?	IAQ Recovery Effectiveness - SRE	Includes Fault Indicator Display?	HERS Verification	Status
SFam IAQVentRot	52	0.35	Exhaust	No	n/a / n/a	No	Yes	

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_ HERS Provider: **CZ-5-11**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-26 20:58:45  
 Schema Version: rev 20220901 Schema Version: rev 20220901

**CERTIFICATE OF COMPLIANCE - RESIDENTIAL PERFORMANCE COMPLIANCE METHOD** CF1R-PRF-01E  
(Page 10 of 12)

Project Name: Residential Building Calculation Date/Time: 2023-09-26 20:58:21-07:00  
 Calculation Description: Title 24 Analysis Input File Name: 3 Bedrm Plan - Plan 2a CZ 5.rbd22x

**SPACE CONDITIONING SYSTEMS**

01	02	03	04	05	06	07	08	09
Name	System Type	Heating Unit Name	Heating Equipment Count	Cooling Unit Name	Cooling Equipment Count	Fan Name	Distribution Name	Required Thermostat Type
HVAC System1	Heat pump heating cooling	Heat Pump System 1	4	Heat Pump System 1	4	n/a	n/a	Setback

**HVAC - HEAT PUMPS**

01	02	03	Heating				Cooling			11	12	13
			Number of Units	Efficiency Type	HSPF / HSPF2 / COP	Cap 47	Cap 17	Efficiency Type	SEER / SEER2			
Heat Pump System 1	VCHP-ductless	4	HSPF2	8	6000	5400	EER2SEER2	16	12.4	Not Zonal	Multi-speed	Heat Pump System 1-herstump

**HVAC HEAT PUMPS - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09
Name	Verified Airflow	Airflow Target	Verified EER/EER2	Verified SEER/SEER2	Verified Refrigerant Charge	Verified HSPF/HSPF2	Verified Heating Cap 47	Verified Heating Cap 17
Heat Pump System 1-herstump	Not Required	0	Required	Required	Yes	Yes	Yes	Yes

**VARIABLE CAPACITY HEAT PUMP COMPLIANCE OPTION - HERS VERIFICATION**

01	02	03	04	05	06	07	08	09	10
Name	Certified Low-Static VCHP System	Airflow to Habitable Rooms	Ductless Units in Conditioned Space	Wall Mount Thermostat	Air Filter Sizing & Pressure Drop Rating	Low Leakage Ducts in Conditioned Space	Minimum Airflow per RA3.3 and SC3.3.4.1	Certified non-continuous Fan	Indoor Fan not Running Continuously
Heat Pump System 1	Not required	Required	Required	Required	Not required	Not required	Not required	Not required	Not required

Registration Number: \_\_\_\_\_ Registration Date/Time: \_\_\_\_\_ HERS Provider: **CZ-5-10**  
 CA Building Energy Efficiency Standards - 2022 Residential Compliance Report Version: 2022.0.000 Report Generated: 2023-09-26 20:58:45  
 Schema Version: rev 20220901 Schema Version: rev 20220901



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONSTRUCT THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

FOR USE IN THE COUNTY OF SAN LUIS OBISPO  
NOT FOR CONSTRUCTION

**COUNTY OF SAN LUIS OBISPO**  
**ACCESSORY DWELLING UNIT**  
 SAN LUIS OBISPO, CA

---

ENERGY COMPLIANCE - PLAN 2A

DATE  
09/28/2023

SHEET  
**T24 - 204**

CZ-5-16

GreenPoint Rated New Home Single Family Checklist Version 8.0. G2.2 Water-Efficient Fixtures. G3. Pre-Planning for Greener Systems. H. HEATING, VENTILATION, AND AIR CONDITIONING. H1. Sealed Combustion Units. H2. High-Performing Zoned Hydronic Radiant Heating System. H3. Effective Ductwork. H4. ENERGY STAR® Bathrooms Fans Per IPI Standards with Air Flow Verified. H5. Advanced Practices for Cooling. H6. Whole House Mechanical Ventilation Practices to Improve Indoor Air Quality. H7. Effective Range Hood Design and Installation. H8. High-Efficiency HVAC Filter (MERV 16+). H9. Advanced Refrigerants. H10. No Fireplace or Sealed Gas Fireplace. H11. Humidity Control Systems. H12. Register Design Per ACCA Manual T. I. RENEWABLE ENERGY. I1. Onsite Renewable Generation (Solar PV, Solar Thermal, and Wind). I2. Low Carbon Homes. I3. Energy Storage. J. BUILDING PERFORMANCE AND TESTING. J1. Third-Party Verification of Quality of Insulation Installation. J2. Supply and Return Air Flow Testing. J3. Mechanical Ventilation Testing. J4. All Electric or Combustion Appliance Safety Testing. J5. Building Performance Exceeds Title 24 Part 6. J6. Title 24 Prepared and Signed by a CABEC Certified Energy Analyst. J7. Participation in Utility Program with Third-Party Plan Review. J8. ENERGY STAR® for Homes. J9. EPA Indoor airPlus Certification. J10. Blower Door Testing. K. FINISHES. K1. Entryways Designed to Reduce Tracked-in Contaminants.

GreenPoint Rated New Home Single Family Checklist Version 8.0. G2.3 WaterSense Toilets with a Maximum Performance (MPF) Threshold of No Less Than 560 Gpm @ 1.29 gpf OR 1.1 gpf. G3.1 Pre-Planning for Greener Systems. H. HEATING, VENTILATION, AND AIR CONDITIONING. H1. Sealed Combustion Units. H2. High-Performing Zoned Hydronic Radiant Heating System. H3. Effective Ductwork. H4. ENERGY STAR® Bathrooms Fans Per IPI Standards with Air Flow Verified. H5. Advanced Practices for Cooling. H6. Whole House Mechanical Ventilation Practices to Improve Indoor Air Quality. H7. Effective Range Hood Design and Installation. H8. High-Efficiency HVAC Filter (MERV 16+). H9. Advanced Refrigerants. H10. No Fireplace or Sealed Gas Fireplace. H11. Humidity Control Systems. H12. Register Design Per ACCA Manual T. I. RENEWABLE ENERGY. I1. Onsite Renewable Generation (Solar PV, Solar Thermal, and Wind). I2. Low Carbon Homes. I3. Energy Storage. J. BUILDING PERFORMANCE AND TESTING. J1. Third-Party Verification of Quality of Insulation Installation. J2. Supply and Return Air Flow Testing. J3. Mechanical Ventilation Testing. J4. All Electric or Combustion Appliance Safety Testing. J5. Building Performance Exceeds Title 24 Part 6. J6. Title 24 Prepared and Signed by a CABEC Certified Energy Analyst. J7. Participation in Utility Program with Third-Party Plan Review. J8. ENERGY STAR® for Homes. J9. EPA Indoor airPlus Certification. J10. Blower Door Testing. K. FINISHES. K1. Entryways Designed to Reduce Tracked-in Contaminants.

GreenPoint Rated New Home Single Family Checklist Version 8.0. C13. Reduce Light Pollution. C14. Large Stature Trees. C15. Third-Party Landscape Program Certification. C16. Maintenance Contract with Certified Professional. D. STRUCTURAL FRAME AND BUILDING ENVELOPE. D1. Optimal Window Engineering. D2. Advanced Framing Measures. D3. Construction Material Efficiencies. D3.1 Engineered Lumber. D3.2 Engineered Beams and Headers. D3.3 Wood Joists or Wall Trusses for Floors. D3.4 OSB for Subfloors. D3.5 OSB for Wall and Roof Sheathing. D4. Insulated Headers. D5. FSC-Certified Wood. D6. Solid Wall Systems. D6.1 At Least 90% of Floors. D6.2 At Least 90% of Exterior Walls. D6.3 At Least 90% of Roofs. D7. Energy Heels on Roof Trusses. D8. Overhangs and Gutters. D9. Reduced Pollution Entering the Home from the Garage. D10. Structural Pest and Rot Controls. D11. Wood Framing Trusses With Barriers of Factory-Integrated, or Wall Materials Other Than Wood. D12. Moisture-Resistant Materials in Wet Areas (such as Kitchen, Bathrooms, Utility Rooms, and Basements). E. EXTERIOR. E1. Environmentally Preferable Decking. E2. Flashing Installation Third-Party Verified. E3. Rain Screen Wall System. E4. Durable and Non-Combustible Cladding Materials. E5. Durable Roofing Materials. E6. Vegetated Roof. F. INSULATION. F1. Insulation with 30% Post-Consumer or 60% Post-Industrial Recycled Content. F1.1 Walls and Floors. F1.2 Ceilings. F2. Insulation that Meets the CDPH Standard Method—Residential for Low Emissions. F2.1 Walls and Floors. F2.2 Ceilings. F3. Low GWP Insulation That Does Not Contain Fire Retardants. F3.1 Cavity Walls and Floors. F3.2 Ceilings. F3.3 Interior and Exterior. G. PLUMBING. G1. Efficient Distribution of Domestic Hot Water. G1.1 Insulated Hot Water Pipes. G1.2 WaterSense Volume Limits for Hot Water Distribution. G1.3 Increased Efficiency of Hot Water Distribution.

GreenPoint Rated New Home Single Family Checklist Version 8.0. N5.1 Residence Entires with Views to Country. N5.2 Entrances Visible from Street and/or Other Front Courts. N5.3 Porches Oriented to Street and Public Space. N6. Passive Solar Design. N6.1 Heating Load. N6.2 Cooling Load. N7. Adjustable Building. N7.1 Universal Design Principles in Units. N7.2 Full-Function Independent Rental Unit. N8. Resiliency. N8.1 Assessment. N8.2 Strategies to Address Assessment Findings. N9. Social Equity in Community. N9.1 Diverse Workforce. N9.2 Community Location. O. OFFICE. O1. GreenPoint Rated Checklist in Blueprints. O2. Pre-Construction Kickoff Meeting with Rater and Subcontractors. O3. Orientation and Training to Occupants—Conduct Educational Walkthroughs. O4. Builder's or Developer's Management Staff are Certified Green Building Professionals. O5. Home System Monitors. O5.1 Energy Home System Monitors. O5.2 Water Home System Monitors. O6. Green Building Education. O6.1 Marketing Green Building. O6.2 Green Building Signage. O7. Green Appraisal Addendum. O8. Detailed Durability Plan and Third-Party Verification of Plan Implementation. Summary. Total Available Points in Specific Categories: 205/205. Minimum Points Required in Specific Categories: 180/180. Total Points Achieved: 205/205.

GreenPoint Rated New Home Single Family Checklist Version 8.0. Points Targeted: 78. Certification Level Targeted: Certified. Compliance Pathway Targeted: Mixed Fuel Compliance Energy Design Rating. A. SITE. A1. Construction Footprint. A2. Job Site Construction Waste Diversion. A3. Recycled Content Base Material. A4. Heat Island Effect Reduction (Non-Roof). A5. Construction Environmental Quality Management Plan Including Flush-Out. A6. Stormwater Control: Prescriptive Path (water reaped at 3 points). A6.1 Permeable Paving Material. A6.2 Filtration and/or Bio-Retention Features. A6.3 Non-Leaching Roofing Materials. A6.4 Stormwater Street Design. A7. Stormwater Control: Performance Path. B. FOUNDATION. B1. Fly Ash and/or Slag in Concrete. B2. Pughon-Resilient Construction. B3. Foundation Drainage System. B4. Moisture Controlled Crawlspace. B5. Structural Pest Controls. B5.1 Termites Shields and Separated Exterior Wood-to-Concrete Connections. B5.2 Plant Trucks, Beams, or Slabs at Least 36 Inches from the Foundation. C. LANDSCAPE. C1. Plants Grouped by Water Needs (Hydrozoning). C2. Three Inches of Mulch in Planting Beds. C3. Resource Efficient Landscapes. C3.1 No Invasive Species Listed by Cal-IPC. C3.2 Plants Chosen and Located to Grow to Maturity. C3.3 Drought Tolerant, California Native, Mediterranean Species, or Other Appropriate Species. C4. Minimal Turf in Landscape. C4.1 No Turf on Slopes Exceeding 10% and No Overhead Sprinklers Installed in Areas Less Than Eight Feet Wide. C4.2 Turf on a Small Percentage of Landscaped Area. C5. Trees to Moderate Building Temperature. C6. High-Efficiency Irrigation System. C7. One Inch of Compost in the Top Six to Twelve Inches of Soil. C8. Rainwater Harvesting System. C9. Recycled Wastewater Irrigation System. C10. Submeter or Dedicated Meter for Landscape Irrigation. C11. Landscape Meets Water Budget. C12. Environmentally Preferable Materials for 70% of Non-Plant Landscape Elements and Fixing.

GreenPoint Rated New Home Single Family Checklist Version 8.0. K1.1 Individual Entryways. K2. Zero-VOC Interior Wall and Ceiling Paints. K3. Low-VOC Caulks and Adhesives. K4. Environmentally Preferable Materials for Interior Finish. K4.1 Cabinets. K4.2 Interior Trim. K4.3 Shelving. K4.4 Doors. K4.5 Countertops. K5. Formaldehyde Emissions in Interior Finish Exceed CARB. K5.1 Doors. K5.2 Cabinets and Countertops. K5.3 Interior Trim and Shelving. K6. Products That Comply With the Health Product Declaration Open Standard. K7. Indoor Air Formaldehyde Level Less Than 27 Parts Per Billion. K8. Comprehensive Inclusion of Low-Emitting Finishes. L. FLOORING. L1. Environmentally Preferable Flooring. L2. Low-Emitting Flooring Meets CDPH 2010 Standard Method—Residential. L3. Durable Flooring. L4. Thermal Mass Flooring. M. APPLIANCES AND LIGHTING. M1. ENERGY STAR® Dishwasher. M2. ENERGY STAR® Laundry Appliances. M2.1 CEER-Rated Clothes Washer. M2.2 ENERGY STAR® Dryer. M2.3 Solar Dryer/ Laundry Lines. M3. Size-Efficient ENERGY STAR® Refrigerator. M4. Permanent Centers for Waste Reduction Strategies. M4.1 Built-In Recycling Center. M4.2 Built-In Composting Center. M5. Lighting Efficiency. M5.1 High-Efficiency Lighting. M5.2 Lighting System Designed to Exceed Footcandle Standards or Designed by Lighting Consultant. N. COMMUNITY. N1. Smart Development. N1.1 VRS Site. N1.2 Designated Brownfield Site. N1.3 Conserve Resources by Increasing Density. N1.4 Cluster Homes for Land Preservation. N1.5 Home Size Efficiency. N2. Home(s) Development Located Near Transit. N2.1 Within 1 Mile of a Major Transit Stop. N2.2 Within 1/2 Mile of a Major Transit Stop. N3. Pedestrian and Bicycle Access. N3.1 Pedestrian Access to Services Within 1/2 Mile of Community Services. N3.2 Connection to Pedestrian Pathways. N3.3 Traffic Calming Strategies. N4. Outdoor Gathering Places. N4.1 Public or Semi-Public Outdoor Gathering Places for Residents. N4.2 Public Outdoor Gathering Places with Direct Access to Top 1 Community Services. N5. Social Interaction.



THESE PLANS ARE PROVIDED BY THE COUNTY OF SAN LUIS OBISPO AS PART OF THE PRE-APPROVED ADU PROGRAM AND ARE PUBLIC DOMAIN. THERE CANNOT BE A CHARGE TO PROVIDE THESE PLANS. NO ALTERATIONS TO THESE PLANS ARE ALLOWED. ALL ALTERATIONS MUST BE DONE UNDER A SEPARATE PERMIT ONCE THE BUILDING PERMIT FOR THE ADU HAS BEEN ISSUED AND FINAL INSPECTION COMPLETED. IF YOU DO NOT HAVE THE CONSTRUCTION KNOWLEDGE AND EXPERIENCE TO CONTRIBUTE THESE PLANS WITHOUT FURTHER DETAILS, IT IS RECOMMENDED YOU HIRE A CONTRACTOR TO DO THE CONSTRUCTION. THE CITY WILL NOT PROVIDE FURTHER INFORMATION OR DETAILS AND BUILDING INSPECTORS WILL NOT PROVIDE STEP BY STEP INSTRUCTIONS IN THE FIELD.

COUNTY OF SAN LUIS OBISPO  
ACCESSORY DWELLING UNIT  
SAN LUIS OBISPO, CA  
ENERGY COMPLIANCE - PLAN 2  
DATE  
09/28/2023  
SHEET  
T24 - 213