ROOM	ROOM NAME	FLOOR	BASE		WALLS		WAINSCOT		CHAIR RAIL	CEILING			REMARKS
			MAT	FINISH	MAT	FINISH	MAT	FINISH		MAT	FINISH	HEIGHT	
	PUBLIC AREAS												
101	ADOPTION LOBBY	SC	SS	–	GB	PSG	TPS	–	•	GYB	PSG	VARIES	–
101A	ADOPTION LOBBY	SC	SS	–	GB	PSG	TPS	–	•	ACT-1	–	9'-0"	–
101B	JANITORS ROOM	SC	SS	–	GB*	PSG	FRP	–	–	ACT-2	–	9'-0"	–
102	SMALL DOG PUPPIES	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	9'-0"	–
103	CAT HOLD 3	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	9'-0"	–
104	CAT HOLD 2	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	9'-0"	–
105	CAT HOLD 1	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	9'-0"	–
106	VOLUNTEERS	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
107	SURRENDER LOBBY	SV	SV	–	GB	PSG	TPS	–	•	ACT-1	–	9'-0"	–
108	SURRENDER CAGES	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
109	RECEPTION	SC	SS	–	GB	PSG	TPS	–	•	ACT-1	–	9'-0"	–
110	COUNSELING ROOM	SC	SS	–	GB	PSG	–	–	–	ACT-1	–	9'-0"	–
111	SMALL ANIMALS	SV	SV	–	GB*	PSG	FRP	–	•	ACT-3	–	9'-0"	–
112	CAT GET AQUAINTED	SV	SV	–	GB*	PSG	FRP	–	•	ACT-3	–	9'-0"	–
113	CAT COMMUNITY ROOM 1	SV	SV	–	GB*	PSG	FRP	–	•	ACT-3	–	9'-0"	–
113A	CAT PORCH	CONC	CONC	–	MS	–	–	–	–	CP	PSG	9'-0"	–
114	VESTIBULE	SV	SV	–	GB*	PSG	FRP	–	•	ACT-3	–	9'-0"	–
115	CAT COMMUNITY ROOM 2	SV	SV	–	GB*	PSG	FRP	–	•	ACT-3	–	9'-0"	–
115A	CAT PORCH	CONC	CONC	–	MS	–	–	–	–	CP	PSG	9'-0"	–
116	WOMEN'S TOILET	CT	CT	–	GB*/CT	–	–	–	–	GB	PSG	9'-0"	–
117	MEN'S TOILET	CONC	CONC	–	GB*/CT	–	–	–	–	GB	PSG	9'-0"	–
	EDUCATION AREAS												
118	AFTER HOURS VESTIBULE	SC	SS	–	GB	PSG	TPS	–	•	ACT-1	–	9'-0"	–
119	COMMUNITY MULTI-PURPOSE ROOM	RF	RF	–	GB	–	FRP	–	•	GB/ ACT-1	PSG/ –	10'-0"	–
	ADMINISTRATIVE AREAS												
120	ADMIN. ASSIST.	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
121	COPY ROOM	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
122	SR. ACCOUNT CLERK	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
123	ADMIN. SERVICE OFFICER	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
124	MANAGER	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
125	DISPATCH	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
126	ACOs	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
127	LEAD ACO	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
128	LOCKERS	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
129	ACO STORAGE	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
130	EXAM	SV	SV	–	GB*	PSG	FRP	–	–	ACT-2	–	9'-0"	–
131	VOL. COORD.	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
132	STAFF LOUNGE	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
133	ADMIN. HALLWAY	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
134	TOILET ROOM	CT	CT	–	GB*/CT	–	–	–	–	GB	PSG	9'-0"	–
135	SHOWER	CT	CT	–	GB*/CT	–	–	–	–	GB	PSG	9'-0"	–
136	IT ROOM	RT	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
	HOLDING/SUPPORT AREAS												
137	FERRAL CAT	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	8'-0"	–
138	SICK CATS 1	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	8'-0"	–
139	SICK CATS 2	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
140	QUARANT. CATS 1	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
141	QUARANT. CATS 2	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
142	MEDICAL TREATMENT ROOM	SV	SV	–	GB*	PSG	FRP	–	–	ACT-2	–	9'-0"	–
143	MEDICAL HALLWAY	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
144	EUTHANASIA HALLWAY	SV	SV	–	GB	PSG	–	–	•	ACT-2	–	9'-0"	–
145	EUTHANASIA HOLDING	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
146	EUTHANASIA	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
147	RABIES ALCOVE	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	–	ACT-2	–	8'-0"	–
148	CHEMICAL CLEANING	CONC	CONC	–	GB*	PSG	FRP	–	–	–	–	–	–
149	GENERAL & FOOD STORAGE	CONC	RB	–	GB*	PSG	FRP	–	–	–	–	–	–
150	DOG ISO 1	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
151	DOG ISO 2	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
152	DOG ISO 3	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
153	DOG ISO 4	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	8'-0"	–
154	DOG ISO STAFF	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
155	SHELTER MANAGER	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
156	HEALTHY ANIMALS FOOD PREP.	ERC-1	ERC-1	–	GB*	PSG	FRP	–	–	ACT-2	–	9'-0"	–
157	HONOR FARM	SV	SV	–	GB*	PSG	FRP	–	–	ACT-2	–	9'-0"	–
158	HONOR RESTROOM	SV	SV	–	GB*	PSG	FRP	–	–	GB	PSG	8'-0"	–
159	VEHICULAR SALLY PORT	CONC	CONC	–	GB*	EP	FRP	–	–	–	–	–	–
160	INTAKE EXAM	SV	SV	–	GB	PSG	FRP	–	–	ACT-2	–	9'-0"	–
161	PANTRY	CONC	RB	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
162	ISO F.P.	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
163	SUPPORT HALLWAY	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
164	LAUNDRY	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
165	GROOMING	SV	SV	–	GB	PSG	–	–	–	ACT-2	–	9'-0"	–
166	DOG GET AQUAINTED	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
167	ADOPTION WARD 1	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
168	ADOPTION WARD 2	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
169	ADOPTION WARD 3	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
170	ADOPTION WARD 4	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
171	ADOPTION WARD 5	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
172	ADOPTION WARD 6	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
173	QUARANT.	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–
174	PROTECT. CUSTODY	ERC-1	ERC-1	–	GB*/BB	ERC-2	ERC-2	–	•	ACT-2	–	9'-0"	–

FINISH SCHEDULE MATERIALS & COLORS - (TBD)

NOTES

FINISH SCHEDULE ABBREVIATIONS

ACF	ACRYLIC COLOR FINISH
ACT-1	2X2 ACOUSTICAL CEILING TILE NOT USED – ARMSTRONG "CIRRUS" W/ AM
ACT-2	2X4 ACOUSTICAL CEILING TILE – ARMSTRONG "CERAMAGUARD" W/ AM
ACT-3	1X1 ACT MASTIC APPLIED TO GYP. BD./PLYWOOD OVER METAL STUDS
ACT-4	COMBINATION OF EXPOSED STRUCTURE & 1X1 MASTIC APPLIED ACOUSTICAL CEILING TILES UNDER MEZZAINE – ARMSTRONG "FINE FISSURED" W/AM
ACT-5	2X4 ACOUSTICAL CEILING TILE – ARMSTRONG "SECOND LOOK" W/AM
AM	ANTI-MICROBIAL TREATED
AP	ACOUSTICAL PANELS
BB	CEMENT FIBER BACKER BOARD
BB/GB	CEMENT FIBER BACKER BOARD/GB* ON METAL STUDS ABOVE
CL	CLEAR LAQUER FINISH
CMU	CONCRETE MASONRY UNIT
CONC	CONCRETE SEALED
CP	CEMENT PLASTER
CT	CERAMIC TILE
(E)	EXISTING TO REMAIN
EP	EPOXY PAINT
ERC-1	EPOXY RESIN COATING: FLOOR APPLICATION
ERC-2	EPOXY RESIN COATING: WALL APPLICATION
EXP	EXPOSED
EXT.PNT	EXTERIOR PAINT
FF	FACTORY FINISH
FRP	FIBERGLASS REINFORCED PANEL
GB	GYPSUM BOARD
GB*	WATER RESISTANT GYPSUM BOARD
GS	GYPSUM SHEATHING
GL	GLASS/GLAZING
LVT	LUXURY VINYL TILE
MAT	MATERIAL
MS	METAL SIDING
MTL	METAL
NC	NO CEILING
OC	OPEN CEILING
OGC	OPEN GRID CEILING
PE	PAINT, EPOXY
~~PF~~	~~PAINT, FLAT~~
PL	PLASTIC LAMINATE
PNT	PAINT/PAINTED
PSG	PAINT, SEMI-GLOSS
QT	QUARRY TILE
RB	RUBBER BASE, 6" UON 4" @ CASEWORK TO KICKS
REM	RECESSED ENTRY MAT
RF	RUBBER FLOORING
RT	RUBBER TILE
SC	STAINED CONCRETE
SEALED	CLR SEALED
SS	STAINLESS STEEL
SSB	STAINLESS STEEL BASE
SL	SEALER
SS	4" STAINLESS STEEL BASE
SV	SHEET VINYL WITH WELDED SEAMS
TP	TRANSPARENT FINISH
TPS	THERMOPLASTIC WALL PANEL
TR	TRANSULCENT
TS	TRANSLUCENT SKYLIGHT
VWC	VINYL WALL COVERING TO MATCH EXISTING
V	VARIES
VCT	VINYL COMPOSITE TILE
WD	WOOD
WDD	(E) WOOD DECK EXPOSED & REFINISHED
WOM	WALK OFF MAT
SWD	SIMULATED WOOD PANEL

SWATT | MIERS ARCHITECTS

5845 Doyle Street, Suite 104
Emeryville, CA 94608
Tel: 510 985 9779
Fax: 510 985 0116
www.swattmiers.com

LICENSED ARCHITECT GEORGE MYERS No. C10467 STATE OF CALIFORNIA

SLO County Animal Care Facility

865 OKLAHOMA AVE.
SAN LUIS OBISPO, CA.

APN: 073-331-033

Issue

Rev	Date	By	Description

Drawn By ME
Checked By GM
Job No. 1109
Issue Date: 10/31/17
Scale AS NOTED

TRUE Reference North

Drawing Title

FINISH SCHEDULE

A9.1

Sheet

These plans, drawings and specifications are the property of Swatt | Miers Architects and any use and/or reuse thereof in part or in whole without the written permission of the Architect is prohibited. Copyright 2010 Swatt | Miers Architects