

July 24, 2020

Mr. Mark Reno
Quincy Engineering
11017 Cobblersrock Drive, Suite 100
Rancho Cordova, CA 95670

**Aerially Deposited Lead Assessment Report
Santa Margarita Creek Bridge on El Camino Real
San Luis Obispo County, California**

Dear Mr. Reno:

Haro Environmental, Inc. is pleased to present this letter report presenting the findings of a limited soil investigation performed to assess the potential for Aerially Deposited Lead (ADL) to be encountered during construction of the Santa Margarita Creek Bridge on El Camino Real project in San Luis Obispo County, California. The services performed by Haro Environmental have been performed at the request of Quincy Engineering who we understand has been contracted to complete replacement of the Santa Margarita Creek Bridge on El Camino Real, which includes soil work along both bridge approaches along El Camino Real. A Site Vicinity Map is provided on Plate 1 and an ADL Sampling Locations Map is provided on Plate 2. The primary objective of the limited ADL assessment was to screen soils within the project area that will be disturbed during construction of the project, and evaluate whether or not ADL is present in soils at concentrations that could require special handling and disposal.

The project description and objective, potential for ADL, scope of work, analytical results and discussion, statistical analysis, conclusions and recommendations, worker safety, and limitations are presented below.

PROJECT DESCRIPTION AND OBJECTIVE

Quincy Engineering, Inc., in cooperation with the California Department of Transportation (Caltrans) and San Luis Obispo County Public Works Department, proposes to replace the existing bridge over Santa Margarita Creek. The proposed projects includes improvement of roadways and intersections along El Camino Real extending approximately 1,050 feet northwest of the bridge (near the Sandoval Road intersection) and approximately 1,550 feet southeast of the bridge (near the Walnut Avenue intersection). Copies of the 95-percent project plans are provided in Attachment A.

The objective of this ADL assessment was to collect soil samples from areas within the project limits that will be disturbed, and to determine if lead concentrations exceed state and/or federal hazardous waste criteria, which could require special handling and disposal.

POTENTIAL FOR AERIALY DEPOSTED LEAD

Based on the historical use of leaded gasoline prior to 1987, there is a potential for elevated concentrations of lead to be present in shallow soils along roads and highways constructed prior to this date. Lead concentrations in soils near highways are often attributed to emissions from vehicles powered by internal-

combustion engines that previously used leaded gasoline. At roads where the adjacent subgrade has not been disturbed, the presence of ADL is generally limited to the upper 3 feet of soil and typically does not extend farther than 30 feet from the roadway.

Historic aerial photographs indicate El Camino Real has been present since at least 1937, and remained a main arterial highway until Highway 101 was constructed in the 1960s. As such, there is a potential that shallow soils adjacent to El Camino Real may contain concentrations of ADL.

SCOPE OF WORK

On October 11, 2019, Haro Environmental collected 16 soil samples from 8 locations within the project area. The GPS coordinates of the soil sample locations are provided on Table B-1 in Attachment B. Soil samples were collected from two depth intervals, 0-0.5 and 1.5-2 feet below ground surface (bgs), to assess the vertical limits of impacts, if detected. The sampling depths were adjusted in the field at two locations, ADL-5 and ADL-6, due to hand auger refusal and the samples were therefore collected from 0.5-1 foot bgs. The soil sampling locations were selected to assess representative soils potentially disturbed during construction of the project. The soil samples were collected using a stainless steel hand auger, transferred into laboratory-recommended plastic bags, placed into a cooler, and transferred under chain-of-custody protocol to Eurofins/Calscience Laboratories of Garden Grove, California, a State-certified analytical laboratory, for analysis of total lead using USEPA Test Method 6010B.

Based on the analytical results, total lead was detected in three samples at concentrations exceeding 50 milligrams per kilogram (mg/kg) and were further tested for soluble lead using the modified California Title 22 Waste Extraction Test (CA-WET) using citric acid as the extractant. In addition, one sample exceeded 100 mg/kg total lead and was further tested for soluble lead using the Toxicity Leaching Characteristic Procedure (TCLP; USEPA Test Method 1311).

During sampling, the equipment was decontaminated between each sampling location using the 3-bucket method, which consisted of an initial wash using an Alconox solution, followed by a rinse with potable water and then a final rinse with deionized water. Sampling locations were backfilled with soil cuttings, and wash and rinse water was discharged to the soil surface at the sampling locations.

ANALYTICAL RESULTS AND DISCUSSION

Title 22 of California Code of Regulations (CCR) states solid wastes with total lead concentrations equal to or exceeding 1,000 mg/kg [referred to as the Total Threshold Limit Concentration (TTLC)] are classified as California hazardous waste. Solid wastes with soluble lead concentrations as measured using the CA-WET extraction equal to or exceeding 5.0 milligrams per liter (mg/L), also referred to as the Soluble Threshold Limit Concentration (STLC), are classified as California hazardous waste under Title 22. Per California law, hazardous materials must be transported under a hazardous waste manifest and disposed of at an appropriately permitted facility. Wastes with lead concentrations less than both the TTLC and the STLC are not a California hazardous waste, and may be disposed of at a Class II or III facility, provided that site-specific disposal facility requirements are satisfied. Furthermore, according to federal law, as stipulated in the Resource Conservation and Recovery Act (RCRA), wastes that exceed 5.0 mg/L soluble lead, extracted using the federal TCLP, are classified as RCRA hazardous waste. Testing for TCLP is triggered when the total lead concentration exceeds 100 mg/kg. If the TCLP exceeds 5 mg/L, this material must be disposed of as RCRA hazardous waste if transported offsite.

Total lead was detected in all 14 of the 16 soil samples ranging from 0.598 mg/kg to 289 mg/kg. Total lead exceeded 50 mg/kg (i.e., ten times higher than the STLC limit of 5.0 mg/L) in three samples and were; therefore, further tested for soluble lead using the CA-WET method. Soluble lead results ranged from 0.693 mg/L to 4.31 mg/L; less than the STLC limit for lead of 5.0 mg/L.

Only one sample exceeded the 100 mg/kg threshold for total lead; therefore, this sample was further tested using the TCLP extraction and soluble lead was not detected above the laboratory reporting limit of 0.500 mg/L; less than the TCLP threshold of 5.0 mg/L for RCRA hazardous waste. Total lead, STLC lead, and TCLP lead results are summarized on Table 1, and a copies of the laboratory analytical reports are provided in Attachment C.

STATISTICAL ANALYSIS

A statistical analysis of the ADL sample data was performed using ProUCL 5.1 software to calculate the sample statistics as well as the 95 percent Upper Confidence Limit (UCL) on the mean¹. UCLs were calculated using standard bootstrap methodology and the data evaluated for goodness-of-fit against normal, gamma, and log normal distributions. Statistical outputs from the ProUCL software are summarized on Table 2 and provided in Attachment D. Based on the results of the statistical analysis, the data for all samples were assumed to follow a gamma distribution, for the 0-0.5 foot depth the data did not follow a normal, gamma, or log normal distribution and were analyzed using a normal distribution for nonparametric data per the recommendation of the ProUCL 5.0 users guide, and the 1.5-2 foot data appeared to follow a normal distribution.

Total Lead

The 95 percent UCL for total lead was calculated at 201 mg/kg for the 0.5-foot depth, 45.8 mg/kg for the 2-foot depth, and 116 mg/kg for all depths (Table 2). At all depth ranges, the 95 percent UCL for total lead was less than the TTLC threshold of 1,000 mg/kg.

Soluble Lead

Because of the limited size of the dataset available for the soluble lead results, a regression analysis was performed to predict the 95 percent UCL on the mean for CA-WET solubility. Excel software was used to perform the regression calculations by comparing the total lead and corresponding CA-WET data. A coefficient of determination (R^2) of -1.023 was calculated for the data set, indicating the regression line is a less efficient predictor than the mean, and; therefore, the mean of the STLC data was used.

The results presented in Table 2 indicate that the mean CA-WET results for soluble lead for all depths returned a lead level of 2.40 mg/L, below the 5.0 mg/L regulatory threshold and mainly driven by the soluble lead concentration detected in sample ADL-7-2 (4.31 mg/L).

CONCLUSIONS AND RECOMMENDATIONS

Near-surface soil within the project limits returned low levels of ADL. The results indicate total lead concentrations at or below 289 mg/kg, with the highest concentration detected along the eastern alignment of El Camino Real, closer to Walnut Avenue. Based on the mean and 95 percent UCL values shown in Table 2, the total lead concentrations in all depths are well below the TTLC of 1,000 mg/kg that defines the lower limit for hazardous waste.

Soluble lead was detected in three samples and the results ranged from 0.693 mg/L to 4.31 mg/L. None of the three samples analyzed returned soluble lead levels exceeding the individual STLC for lead of 5.0 mg/L. The regression analysis to predict soluble lead levels (CA-WET) returned a negative coefficient of determination; therefore, the mean of the STLC results of 2.40 mg/L was evaluated and is below the STLC threshold of 5.0 mg/L.

Regulatory criteria to classify a waste as "California Hazardous" for handling and disposal purposes are contained in CCR, Title 22, Division 4.5, Chapter 11, Article 3, subsection 66261.24. Federal criteria to

¹ United States Environmental Protection Agency (USEPA). 2016. *Statistical Software ProUCL 5.1.00 for Environmental Applications for Data Sets with and without Nondetect Observations*. Last updated June 20, 2016

classify a waste as "RCRA Hazardous Waste" are contained in Chapter 40 of the Code of Federal Regulations (40 CFR), Section 261. For a waste containing lead, the waste is classified as California Hazardous (non-RCRA) when:

- Total lead exceeds the TTLC of 1,000 mg/kg; or
- Soluble lead exceeds the STLC of 5.0 mg/L based on the standard CA-WET method.

Based on the analytical results, total and soluble lead concentrations did not exceed the waste criteria for non-RCRA or RCRA hazardous waste. Therefore, no additional testing appears warranted, and no special handling or disposal of soil encountered during the project appears warranted.

WORKER SAFETY

Because lead was detected at most locations within the project limits, we recommend that the contractor perform all grading operations in accordance with applicable Cal-OSHA requirements, including but not limited to, a project-specific worker Health & Safety Plan (HASP) as well as a project-specific Lead Compliance Plan (LCP) to prevent or minimize worker exposure to lead-impacted soil during construction. The LCP should include protocols for environmental and personnel monitoring, requirements for personal protective equipment, and other appropriate health and safety protocols and procedures for the handling of lead-impacted soil.

LIMITATIONS

This report has been prepared for and is intended for the exclusive use of Quincy Engineering. The services performed by Haro Environmental have been conducted in a manner consistent with the level of care and skill ordinarily exercised by members of our profession currently practicing under similar conditions in the site vicinity. No other warranty, express or implied, is offered.

Quincy Engineering can convey this report to an affiliate, related entity, subsidiary, lender, title insurer, regulatory/city agency or current property owner(s) and their agents, but further dissemination requires prior written approval from Haro Environmental.

Our conclusions regarding the Site are based on the results of a limited soil sampling program. The results of this evaluation are qualified by the fact that only limited sampling and analytical testing was conducted during this assessment. Haro Environmental offers no assurances and assumes no responsibility for site conditions or activities that were outside the scope of services outlined in this document.

The concentrations of chemicals detected at any given location may not be representative of conditions at other locations. Further, conditions may change at any particular location as a function of time in response to natural conditions, chemical reactions and other events. Conclusions regarding the condition of the Site do not represent a warranty that all areas within the Site are similar to those sampled.

During the course of the performance of Haro Environmental's services, hazardous materials may have been discovered. Haro Environmental assumes no responsibility or liability whatsoever for any claim, loss of property value, damage, or injury that results from pre-existing hazardous materials being encountered or present on the project site, or from the discovery of such hazardous materials. Nothing contained in this report should be construed or interpreted as requiring Haro Environmental to assume the status of an owner, operator, or generator, or person who arranges for disposal, transport, storage or treatment of hazardous materials within the meaning of any governmental statute, regulation or order. Quincy Engineering is solely responsible for directing notification of all governmental agencies, and the public at large, of the existence, release, treatment or disposal of any hazardous materials observed at the project site, either before or during performance of Haro Environmental's services. Quincy Engineering is responsible for directing all arrangements to lawfully store, treat, recycle, dispose, or otherwise handle hazardous materials, including cuttings and samples resulting from Haro Environmental's services.

July 24, 2020
Page 5 of 5

If you have any questions regarding the information presented in this report, please contact Elliot Haro at 805.204.4483.

Sincerely,

HARO ENVIRONMENTAL, INC.



Elliot R Haro,
Principal Scientist



Steve Elliott
Professional Geologist #9060




Plates: Plate 1 Site Vicinity Map
 Plate 2 ADL Sampling Locations Map

Tables: Table 1 Soil Analytical Testing Summary – Total Lead, STLC, TCLP
 Table 2 Statistical Analysis Results – Total Lead and STLC

Attachments: Attachment A – Preliminary Project Plans
 Attachment B – Sample Location Coordinates
 Attachment C – Laboratory Analytical Reports
 Attachment D – Statistical Analysis Output

Plates



0 1000 FEET 0 500 1000 METERS
 Map created with TOPO! ©2003 National Geographic (www.nationalgeographic.com/topo)

HARO
 ENVIRONMENTAL

872 Higuera Street
 San Luis Obispo, CA 93401
 Phone: 805 204 4483
 Fax: 805 831 6081

FILE NAME: SITE VICINITY MAP.DWG

SITE VICINITY MAP
 Santa Margarita Creek Bridge on El Camino Real
 San Luis Obispo County, California

PLATE:	1
SHEET:	of
REVISION NO:	0
DATE:	10/19



872 Higuera Street
 San Luis Obispo, California 93401
 Phone: 805.204.4483
 Fax: 805.832.6081

SALU MAP.dwg

SAMPLING LOCATIONS MAP

Santa Margarita Creek Bridge at El Camino Real
 San Luis Obispo County, California

PLATE:

2

REVISION NO:

DATE: 11/19

Tables

Table 1
Soil Analytical Testing Summary - Total Lead, STLC, TCLP
 Santa Margarita Creek Bridge at El Camino Real

Chemical name Analysis Name Analysis Method Leachate Method Units			Lead Total Lead (TTLC) USEPA 6010B -- mg/kg	Lead STLC USEPA 6010B CA-WET mg/L	Lead TCLP USEPA 6010B TCLP mg/L
Sample ID	Date Collected	Sample Depth (feet bgs)			
ADL-1-0.5	10/11/2019	0.5	18.8	--	--
ADL-1-2	10/11/2019	2	62.2	0.693	--
ADL-2-0.5	10/11/2019	0.5	18.7	--	--
ADL-2-2	10/11/2019	2	3.30	--	--
ADL-3-0.5	10/11/2019	0.5	6.55	--	--
ADL-3-2	10/11/2019	2	2.98	--	--
ADL-4-0.5	10/11/2019	0.5	9.84	--	--
ADL-4-2	10/11/2019	2	46.4	--	--
ADL-5-0.5	10/11/2019	0.5	<0.503	--	--
ADL-5-1	10/11/2019	1	0.598	--	--
ADL-6-0.5	10/11/2019	0.5	<0.495	--	--
ADL-6-1	10/11/2019	1	1.26	--	--
ADL-7-0.5	10/11/2019	0.5	289	2.20	<0.500
ADL-7-2	10/11/2019	2	71.6	4.31	--
ADL-8-0.5	10/11/2019	0.5	14.6	--	--
ADL-8-2	10/11/2019	2	18.9	--	--
State Waste Criteria			1,000	5	--
Federal Waste Criteria			--	--	5

Notes:

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

STLC = Soluble Limit Threshold Concentration

CA-WET = California Waste Extraction Test

TCLP = Toxicity Characteristic Leaching Procedure

2-foot samples from locations ADL-5 and ADL-6 collected from 1 foot below ground surface due to hand auger refusal

Table 2
Statistical Analysis Results - Total Lead
 Santa Margarita Creek Bridge at El Camino Real

Total Lead (mg/kg)							
Depth	No. of Samples	Min	Max	Mean	Median	Standard Deviation	95% UCL
0.5	8	6.55	289	59.6	16.7	112.5	201
2*	8	0.598	71.6	25.9	11.1	29.7	45.8
All Depths	16	0.598	289	40.3	16.7	75.1	116

CA-WET Lead (mg/L)							
Depth	No. of Samples	Min	Max	Mean	Median	Standard Deviation	95% UCL**
All Depths	3	0.693	4.31	2.40	2.20	1.48	1.28

Notes:

mg/kg = milligrams per kilogram

mg/L = milligrams per liter

Analysis: USEPA Test Method 6010B

CA-WET = California Waste Extraction Test

95% UCL = 95 percent upper confidence limit

* = 2-foot samples from locations ADL-5 and ADL-6 collected from 1 foot below ground surface due to hand auger refusal

** = 95% UCL calculated based on the slope of the regression line and the 95% UCL of the mean for total lead

1) Min, Max, Mean, Median, and Standard Deviation calculated using the detected data

 = coefficient of determination (e.g., R^2) was negative; use mean instead

Attachment A

INDEX OF PLANS

SHEET No. ROADWAY PLANS

- 1 TITLE SHEET
- 2-4 TYPICAL CROSS SECTIONS
- 5-6 LAYOUT
- 7-8 PROFILE AND SUPERELEVATION DIAGRAM
- 9 PROFILE
- 10-19 CONSTRUCTION DETAILS
- 20-22 RIGHT OF WAY MAP
- 23 TEMPORARY STREAM DIVERSION PLAN
- 24-25 EROSION CONTROL PLAN
- 26-27 TREE REMOVAL AND IMPACTS
- 28-29 UTILITY PLAN
- 30 UTILITY DETAIL
- 31-37 STAGE CONSTRUCTION
- 38-46 TRAFFIC HANDLING PLAN
- 47-48 DETOUR PLAN
- 49-50 PAVEMENT DELINEATION PLAN
- 51-52 SIGN PLAN

STRUCTURE PLANS


- 53 GENERAL PLAN
- 54 GENERAL NOTES
- 55 DECK CONTOURS
- 56 FOUNDATION PLAN
- 57 ABUTMENT 1 LAYOUT
- 58 ABUTMENT 4 LAYOUT
- 59 ABUTMENT DETAILS No. 1
- 60 ABUTMENT DETAILS No. 2
- 61 ABUTMENT DETAILS No. 3
- 62 PIER DETAILS No. 1
- 63 PIER DETAILS No. 2
- 64 TYPICAL SECTION
- 65 SUPERSTRUCTURE DETAILS No. 1
- 66 SUPERSTRUCTURE DETAILS No. 2
- 67 SUPERSTRUCTURE DETAILS No. 3
- 68 TUBULAR BICYCLE RAILING
- 69 LOG OF TEST BORINGS No. 1
- 70 LOG OF TEST BORINGS No. 2

THE STANDARD PLANS LIST APPLICABLE TO THIS CONTRACT IS INCLUDED IN THE NOTICE TO BIDDERS AND SPECIAL PROVISIONS BOOK.

THE CONTRACTOR SHALL POSSESS THE CLASS (OR CLASSES) OF LICENSE AS SPECIFIED IN THE "NOTICE TO BIDDERS."


SAN LUIS OBISPO COUNTY
DEPARTMENT OF PUBLIC WORKS TRANSPORTATION
PROJECT PLANS FOR CONSTRUCTION OF
SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL
 LOCATED 2.6 MILES NORTH
 OF SANTA MARGARITA
BRIDGE 49CO474
EXISTING BRIDGE 49CO310
FEDERAL AID BRIDGE REPLACEMENT
PROJECT #BRLO-5949(131)

TO BE SUPPLEMENTED BY STATE OF CALIFORNIA, STANDARD PLANS DATED 2015



SANTA MARGARITA

NO SCALE



95% SUBMITTAL

65% SUBMITTAL

DIRECTOR OF PUBLIC WORKS

PROJECT MANAGER REGISTERED CIVIL ENGINEER DATE



PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING	11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181
---------------------------	--

	COUNTY OF SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS 1050 MONTEREY STREET SAN LUIS OBISPO, CA 93408 PHONE: (805)781-5252
--	--

CONTRACT No. --

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	2	69

REGISTERED CIVIL ENGINEER DATE





PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL



DESIGN DATA:

V	=	60 MPH
ADT (2006)	=	5046
ADT (2026)	=	7500
R	=	TBD
TI	=	8.5

LEGEND:
 Bckg = BACKING
 SR = SUPERELEVATION RATE

- NOTES:**
- DIMENSIONS OF THE STRUCTURAL SECTION ARE SUBJECT TO THE TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
 - SUPERELEVATION RATE IS SHOWN ON THE SUPERELEVATION DIAGRAMS.

TYPICAL CROSS SECTIONS
 NO SCALE

X-1

REVISOR: E. MCPHERSON, G. MCLAUGHLIN
 CHECKED BY: MARK RENO
 CONSULTANT PROJECT MANAGER: MARK RENO
 SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

BORDER LAST REVISED 7/2/2010

USERNAME: GarrettM
 DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rca001.dwg



UNIT UNIT

PROJECT NUMBER & PHASE: S13201 - 65% SUBMITTAL

DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:22:18 PM, Garrett McLaughlin


Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	3	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE





THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P. 916.368.9181



65% SUBMITTAL

- NOTES:**
- DIMENSIONS OF THE STRUCTURAL SECTION ARE SUBJECT TO THE TOLERANCES SPECIFIED IN THE STANDARD SPECIFICATIONS.
 - SUPERELEVATION RATE IS SHOWN ON THE SUPERELEVATION DIAGRAMS.
 - FOR LEGEND, SEE "TYPICAL CROSS SECTIONS" SHEET X-1.
 - CLASS 2 AB TO EXTEND AT SAME DEPTH UNDER APPROACH SLAB.



TYPICAL CROSS SECTIONS
NO SCALE

X-2

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER: MARK RENO
 REVISIONS: E. MCPHERSON, G. MCLAUGHLIN
 CALCULATED-DESIGNED BY: E. MCPHERSON, G. MCLAUGHLIN
 CHECKED BY: E. MCPHERSON, G. MCLAUGHLIN
 REVISED BY: E. MCPHERSON, G. MCLAUGHLIN
 DATE REVISED:

BORDER LAST REVISED 7/2/2010

USERNAME: GarrettM
 DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rca002.dwg

RELATIVE BORDER SCALE IS IN INCHES
 0 1 2 3

UNIT UNIT PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:24:50 PM, Garrett McLaughlin
 LAST REVISION:


Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	5	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181



65% SUBMITTAL

- LEGEND:**
- SURVEY CONTROL POINT
 - CURVE NUMBER/LINE NUMBER
 - ROCK SLOPE PROTECTION
 - REMOVE ASPHALT CONCRETE PAVEMENT
 - TCE TEMPORARY CONSTRUCTION EASEMENT
 - PTE PERMISSION TO ENTER

- NOTE:**
1. THIS PLAN ACCURATE FOR ROADWAY LAYOUT ONLY.
 2. FOR DRIVEWAYS, SEE "CONSTRUCTION DETAILS".
 3. FOR INTERSECTIONS, SEE "CONSTRUCTION DETAILS".
 4. FOR FENCE REMOVAL AND NEW FENCE LIMITS AND LOCATIONS, SEE "CONSTRUCTION DETAILS".
 5. FOR UTILITY INFORMATION, SEE UTILITY SHEETS.



"E" LINE" CURVE DATA

Curve #	R	Δ	T	L
C1	1040.00'	43° 22' 15"	413.56'	787.24'

"E" LINE DATA

Line #	BEARING	DISTANCE
L1	N 02°13'00" E	501.82'
L2	N 41°09'15" W	428.29'

MISCELLANEOUS CURVE DATA

Curve #	R	Δ	T	L
C6	1005.00'	34° 05' 02"	308.07'	597.85'
C7	1065.00'	32° 56' 16"	314.84'	612.24'
C8	500.00'	8° 49' 40"	38.59'	77.04'
C9	1068.00'	6° 07' 15"	57.10'	114.09'

MISCELLANEOUS LINE DATA

Line #	BEARING	DISTANCE
L8	N 41°09'15" W	266.67'
L9	N 30°44'16" W	80.31'

SURVEY CONTROL DATA (NAVD 88)

No.	NORTHING	EASTING	ELEVATION	LINE	STATION	OFFSET	Rt/Lt	DESCRIPTION
CP-1	2352603.56	5785286.20	936.21	"E"	26+00.17	26.34'	Rt	MNT 4CP1
CP-2	2351390.25	5785811.36	935.78	"E"	12+13.12	46.13'	Lt	MNT CP2
CP-3	2352311.76	5785424.11	928.45	"E"	22+90.77	63.59'	Lt	5/8" REBAR AND CAP
CP-4	2352304.25	5785545.56	935.15	"E"	22+05.20	22.92'	Rt	SPIKE CP4

MATCH LINE STA "E" 24+50 SEE SHEET L-2

LAYOUT
SCALE: 1" = 50'

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER MARK RENO
 CALCULATED-DESIGNED BY CHECKED BY
 E. MCPHERSON G. MCLAUGHLIN
 REVISED BY DATE REVISED

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 E. MCPHERSON
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

NOTE:

1. THIS PLAN ACCURATE FOR ROADWAY LAYOUT ONLY.
2. FOR NOTES AND LEGEND, SEE "LAYOUT" L-1.


Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	6	69

REGISTERED CIVIL ENGINEER DATE
 REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE
 THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL



MISCELLANEOUS LINE DATA

Line #	BEARING	DISTANCE
L10	N 50°56'39" W	56.21'
L11	N 41°30'15" W	41.01'

"E" LINE DATA

Line #	BEARING	DISTANCE
L2	N 41°09'15" W	428.29'
L3	N 59°57'04" W	12359.63'

MISCELLANEOUS CURVE DATA

Curve #	R	Δ	T	L
C10	1852.25'	1° 30' 57"	24.50'	49.00'
C11	1845.00'	15° 24' 08"	249.49'	495.98'
C12	2145.00'	10° 57' 33"	205.77'	410.28'

"E" LINE" CURVE DATA

Curve #	R	Δ	T	L
C2	2000.00'	18° 47' 49"	331.05'	656.14'

LAYOUT
 SCALE: 1" = 50'

DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:26:08 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	7	69


REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA



SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	MARK RENO													
	CALCULATED-DESIGNED BY	CHECKED BY													
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	R. KOTAY	G. MCLAUGHLIN													
	REVISOR	DATE REVISED													
STATION	11+00	12+00	13+00	14+00	15+00	16+00	17+00	18+00	19+00	20+00	21+00	22+00	23+00	24+00	TOTAL
CY	Exc														
	Emb														



Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	8	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

65% SUBMITTAL 14%

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	MARK RENO	CALCULATED-DESIGNED BY	CHECKED BY	E. MCPHERSON	G. MCLAUGHLIN	REVISED BY	DATE REVISED								
SANTA MARGARITA CREEK BRIDGE REPLACEMENT							14%									
							12%									
							10%									
							8%									
							6%									
							4%									
							2%									
							0%									
							-2%									
							-4%									
							-6%									
							-8%									
							-10%									
							-12%									
							-14%									
		970						970								
		960						960								
		950						950								
		940						940								
		930						930								
		920						920								
		910						910								
		900						900								
STATION			25+00	26+00	27+00	28+00	29+00	30+00	31+00	32+00	33+00	34+00	35+00	36+00	37+00	TOTAL
CY	Exc															
	Emb															

DATE PLOTTED: Friday, February 16, 2018 TIME PLOTTED: 3:26:38 PM, Garrett McLaughlin



Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	9	69


REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

65% SUBMITTAL



SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	MARK RENO
	CALCULATED-DESIGNED BY	CHECKED BY
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	R. KOTÉY	G. MCLAUGHLIN
	REVISOR	DATE REVISOR
CY	Exc	
	Emb	

STATION	0+00	0+50	1+00	1+50	2+00	2+50	2+75	TOTAL
Exc								
Emb								


DATE PLOTTED: Friday, February 16, 2018 TIME PLOTTED: 3:26:51 PM, Garrett McLaughlin

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 C. POLGLASE
 G. MCLAUGHLIN
 REVISOR BY
 DATE REVISED

MISCELLANEOUS CURVE DATA				
Curve #	R	Δ	T	L
C21	60.00'	64° 27' 20"	37.82'	67.50'

"W" LINE DATA		
Line #	BEARING	DISTANCE
L4	S 68°22'28" W	236.17'

WALNUT AVE ELEVATION DATA TABLE						
Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
1	"E"	11+56.59	16.77'	Lt	937.52	BC, EP
2	"E"	11+74.67	23.22'	Lt	937.35	EP
3	"W"	1+49.98	15.83'	Lt	936.71	EP
4	"W"	1+68.07	9.40'	Lt	936.57	EC, EP
5	"E"	11+56.59	0.00'		937.63	PG
6	"W"	1+68.07	0.00'		936.76	PG
7	"W"	1+51.21	10.61'	Rt	936.60	BC, EP
8	"W"	1+29.37	15.43'	Rt	936.62	EP
9	"E"	12+40.99	21.17'	Lt	936.64	EP
10	"E"	12+62.96	17.00'	Lt	936.66	EC, EP
11	"W"	1+51.21	0.00'		936.81	PG
12	"E"	12+62.96	0.00'		937.32	PG



Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	10	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

NOTE:
SEE TYPICAL SECTIONS FOR HMA AND AB SECTION.

LEGEND:
 RP = RADIUS POINT
 (XX) = CURVE DATA TAG
 [XX] = ELEVATION DATA TAG


DATE PLOTTED: Friday, February 16, 2018 3:27:14 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	11	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING
11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P. 916.368.9181

65% SUBMITTAL

NOTE:
SEE TYPICAL SECTIONS FOR HMA AND AB SECTION.


LEGEND:
 RP = RADIUS POINT
 XX = ELEVATION DATA TAG
 ⊗ = CURVE DATA TAG

Curve #	R	Δ	T	L
C3	80.00'	31° 34' 19"	22.62'	44.08'
C4	80.00'	24° 19' 46"	17.25'	33.97'

Line #	BEARING	DISTANCE
L5	N 49°00'38" E	52.36'
L6	N 17°26'20" E	19.23'
L7	N 41°46'06" E	20.86'

Curve #	R	Δ	T	L
C23	30.00'	117° 39' 48"	49.60'	61.61'
C22	30.00'	86° 38' 13"	28.29'	45.36'

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
20	"E"	21+81.59	26.00'	Rt	937.17	BC, EP
21	"E"	21+96.08	29.73'	Rt	936.94	EP
22	"A"	0+40.04	16.67'	Rt	936.72	EP
23	"A"	0+54.02	12.08'	Rt	936.49	EC, EP
24	"E"	21+81.59	0.00'		936.65	PG
25	"A"	0+54.28	0.00'		936.72	PG
26	"A"	0+78.85	13.03'	Lt	935.24	BC, EP
27	"A"	0+54.58	13.76'	Lt	936.45	EP
28	"E"	22+47.80	37.01'	Rt	936.89	EP
29	"E"	22+66.77	30.25'	Rt	937.33	EC
30	"E"	22+66.77	0.00'		936.73	PG, BB



ASUNCION RD LAYOUT
1" = 10'

CONSTRUCTION DETAILS
SCALE: AS SHOWN

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 C. POLGLASE
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 C. POLGLASE
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

"S" LINE DATA		
Line #	BEARING	DISTANCE
L8	S 36°02'39" W	124.05'
L9	S 15°01'29" W	39.91'

MISCELLANEOUS CURVE DATA				
Curve #	R	Δ	T	L
C25	30.00'	103° 03' 04"	37.75'	53.96'
C26	30.00'	71° 04' 42"	21.43'	37.22'

SANTA MARGARITA DATA TABLE						
Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
30	"E"	25+10.89	30.25'	Lt	935.90	BC, EP
31	"E"	25+28.01	35.45'	Lt	935.63	EP
32	"S"	0+53.93	17.47'	Lt	935.28	EP
33	"S"	0+70.88	12.31'	Lt	934.93	EC, EP
34	"E"	25+10.89	0.00'		936.63	PG
35	"S"	0+70.88	0.00'		935.18	PG
36	"S"	0+45.68	25.05'	Rt	934.75	BC, EP
37	"S"	0+33.45	29.03'	Rt	935.29	EP
38	"E"	26+00.64	30.72'	Lt	935.83	EP
39	"E"	26+13.40	28.00'	Lt	936.04	EC, EP
40	"S"	0+45.67	0.00'		935.25	PG
41	"E"	26+13.40	0.00'		937.16	PG

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	12	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL

NOTE:
SEE TYPICAL SECTIONS FOR HMA AND AB SECTION.

LEGEND:
 RP = RADIUS POINT
 ⊗ = CURVE DATA TAG
 ⊗ = ELEVATION DATA TAG




CONSTRUCTION DETAILS
 SCALE: AS SHOWN
SANTA MARGARITA RD LAYOUT
 1" = 10'

DATE PLOTTED: Friday, February 16, 2018 3:28:01 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	13	69

REGISTERED CIVIL ENGINEER DATE
 PLANS APPROVAL DATE
 THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

DRIVEWAY 1 CURVE TABLE

Curve #	R	Δ	T	L
C30	10.00'	90° 09' 49"	10.03'	15.74'
C31	10.00'	89° 50' 11"	9.97'	15.68'

DRIVEWAY-1



Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
42	"E"	24+47.86	30.25'	Rt	937.18	EP, BC
43	"E"	24+52.86	31.59'	Rt	937.13	GB
44	"E"	24+56.53	35.27'	Rt	936.98	GB
45	"E"	24+57.86	40.28'	Rt	936.78	GB, EC
46	"E"	24+57.82	75.25'	Rt	933.00	CONFORM, MATCH EXISTING
47	"E"	24+69.82	75.25'	Rt	933.00	CONFORM, MATCH EXISTING
48	"E"	24+69.86	40.22'	Rt	936.78	GB, BC
49	"E"	24+71.21	35.23'	Rt	936.98	GB
50	"E"	24+74.86	31.58'	Rt	937.13	GB
51	"E"	24+79.86	30.25'	Rt	937.18	EP, EC

DRIVEWAY 1 CURVE TABLE


Curve #	R	Δ	T	L
C32	8.00'	88° 53' 44"	7.85'	12.41'
C33	10.00'	91° 06' 16"	10.19'	15.90'

DRIVEWAY-2

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
52	"E"	25+77.08	30.31'	Rt	938.12	EP, BC
53	"E"	25+81.08	30.79'	Rt	938.09	GB
54	"E"	25+84.32	33.23'	Rt	937.97	GB
55	"E"	25+85.94	36.97'	Rt	937.81	GB, EC
56	"E"	25+90.47	66.77'	Rt	935.00	CONFROM, MATCH EXISTING
57	"E"	26+01.99	65.20'	Rt	935.00	CONFORM, MATCH EXISTING
58	"E"	25+97.97	37.69'	Rt	937.74	GB, BC
59	"E"	25+98.56	32.49'	Rt	937.93	GB
60	"E"	26+01.67	28.31'	Rt	938.09	GB
61	"E"	26+06.44	26.30'	Rt	938.16	EP, EC



DRIVEWAY 1 DETAIL
 1" = 5'



DRIVEWAY 2 DETAIL
 1" = 5'

CONSTRUCTION DETAILS
 SCALE: AS SHOWN

C-4

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER Mark Reno
 CALCULATED-DESIGNED BY C. POLGLASE
 CHECKED BY G. MCLAUGHLIN
 REVISED BY DATE REVISED
 BORDER LAST REVISED 7/2/2010


DATE PLOTTED: Friday, February 16, 2018 TIME PLOTTED: 3:28:28 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	14	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

65% SUBMITTAL

DRIVEWAY 3 CURVE TABLE

Curve #	R	Δ	T	L
C34	10.00'	91° 41' 22"	10.30'	16.00'
C35	10.00'	87° 15' 35"	9.53'	15.23'

DRIVEWAY 3 ELEVATION DATA TABLE





Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
62	"E"	27+73.04	22.85'	Rt	939.88	EP, BC
63	"E"	27+78.06	24.21'	Rt	939.89	GB
64	"E"	27+81.70	27.97'	Rt	939.79	GB
65	"E"	27+82.93	33.09'	Rt	939.64	EP, EC
66	"E"	27+82.01	67.72'	Rt	936.00	CONFORM, MATCH EXISTING
67	"E"	27+95.56	67.61'	Rt	936.00	CONFORM, MATCH EXISTING
68	"E"	27+96.74	32.21'	Rt	939.82	GB, BC
69	"E"	27+98.15	27.40'	Rt	940.04	GB
70	"E"	28+01.70	23.89'	Rt	940.23	GB
71	"E"	28+06.50	22.59'	Rt	940.34	EP, EC

DRIVEWAY 4 CURVE TABLE

Curve #	R	Δ	T	L
C36	10.00'	81° 40' 35"	8.64'	14.26'
C37	10.00'	67° 06' 55"	6.63'	11.71'

DRIVEWAY 4 ELEVATION DATA TABLE

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
72	"E"	28+97.04	21.63'	Rt	939.82	EP, BC
73	"E"	29+01.57	22.70'	Rt	939.85	EP
74	"E"	29+05.11	25.74'	Rt	939.77	EP
75	"E"	29+06.87	30.08'	Rt	939.63	EP, EC
76	"E"	29+09.55	47.72'	Rt	938.14	EP, PI
77	"E"	29+09.72	61.47'	Rt	936.92	CONFORM, MATCH EXISTING
78	"E"	29+19.79	61.33'	Rt	936.90	CONFROM, MATCH EXISTING
79	"E"	29+19.59	45.89'	Rt	938.40	EP, PI
80	"E"	29+26.83	27.36'	Rt	940.00	EP, BC
81	"E"	29+28.92	24.11'	Rt	940.16	EP
82	"E"	29+32.08	21.91'	Rt	940.30	EP
83	"E"	29+35.83	21.10'	Rt	940.39	EP, EC



CONSTRUCTION DETAILS
SCALE: AS SHOWN

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER: MARK RENO
 CALCULATED-DESIGNED BY: C. POLGLASE
 CHECKED BY: G. MCLAUGHLIN
 REVISED BY: C. POLGLASE
 DATE REVISED: G. MCLAUGHLIN

DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:28:55 PM, Garrett McLaughlin

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

DRIVEWAY 5 CURVE TABLE

Curve #	R	Δ	T	L
C38	47.68'	27° 23' 59"	11.62'	22.80'
C39	36.06'	43° 54' 06"	14.53'	27.63'




DRIVEWAY-5

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
84	"E"	30+96.51	18.12'	Rt	943.19	EP, BC
85	"E"	31+01.57	23.73'	Rt	943.06	EP
86	"E"	31+05.65	30.10'	Rt	942.87	EP
87	"E"	31+08.66	37.04'	Rt	942.17	EP, EC
88	"E"	31+09.04	51.09'	Rt	940.92	CONFORM, MATCH EXISTING
89	"E"	31+16.78	50.89'	Rt	940.95	CONFORM, MATCH EXISTING
90	"E"	31+17.22	39.69'	Rt	942.10	EP, BC
91	"E"	31+20.19	31.01'	Rt	943.11	EP
92	"E"	31+25.24	23.39'	Rt	943.51	EP
93	"E"	31+32.08	17.33'	Rt	943.89	EP, EC


DRIVEWAY 6 CURVE TABLE

Curve #	R	Δ	T	L
C41	10.00'	52° 27' 29"	4.93'	9.16'
C42	29.76'	61° 20' 25"	17.65'	31.86'



DRIVEWAY-6

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
94	"E"	31+74.99	17.35'	Lt	944.87	EP, BC
95	"E"	31+79.08	17.84'	Lt	944.99	EP
96	"E"	31+82.88	19.42'	Lt	944.14	EP
97	"E"	31+86.11	21.98'	Lt	945.32	EP, EC
98	"E"	31+86.70	22.60'	Lt	945.37	EP, BC
99	"E"	31+88.45	25.10'	Lt	945.50	EP
100	"E"	31+89.36	27.99'	Lt	945.64	EP
101	"E"	31+89.36	31.03'	Lt	945.76	CONFORM, MATCH EXISTING, EC
102	"E"	32+03.26	32.48'	Lt	946.48	CONFORM, MATCH EXISTING, BC
103	"E"	32+09.81	24.20'	Lt	946.05	EP
104	"E"	32+18.84	18.70'	Lt	945.88	EP
105	"E"	32+29.21	16.67'	Lt	945.95	EP, EC



CONSTRUCTION DETAILS
 SCALE: AS SHOWN

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER MARK RENO
 CALCULATED-DESIGNED BY CHECKED BY
 C. POLGLASE G. MCLAUGHLIN
 REVISED BY DATE REVISED
 BORDER LAST REVISED 7/2/2010

TIME PLOTTED: Friday, February 16, 2018 3:29:24 PM, Garrett McLaughlin
 LAST REVISION

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	16	69

REGISTERED CIVIL ENGINEER DATE
 REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181



65% SUBMITTAL

DRIVEWAY 7 CURVE TABLE

Curve #	R	Δ	T	L
C42	15.00'	97° 02' 06"	16.96'	25.40'
C43	30.00'	65° 55' 26"	19.45'	34.52'

DRIVEWAY-7

Point #	LINE	STATION	OFFSET	Rt/Lt	ELEVATION	DESCRIPTION
106	"E"	29+05.46	21.72'	Lt	939.94	EP, BC
107	"E"	29+13.58	23.94'	Lt	940.02	EP
108	"E"	29+19.28	30.09'	Lt	940.01	EP
109	"E"	29+20.78	38.29'	Lt	939.89	EP, EC
110	"E"	29+20.38	42.48'	Lt	939.83	CONFORM, MATCH EXISTING
111	"E"	29+38.97	50.45'	Lt	939.84	CONFORM, MATCH EXISTING
112	"E"	29+44.31	38.81'	Lt	940.15	EP, BC
113	"E"	29+50.98	29.44'	Lt	940.43	EP
114	"E"	29+60.67	23.17'	Lt	940.69	EP
115	"E"	29+71.99	20.86'	Lt	940.90	EP, EC



CONSTRUCTION DETAILS
 SCALE: AS SHOWN

C-7

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 C. POLGLASE
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

CONSULTANT PROJECT MANAGER
 MARK RENO

CALCULATED-DESIGNED BY
 CHECKED BY

REVISOR BY
 DATE REVISED

C. POLGLASE
 G. MCLAUGHLIN

NOTE:
 1. THIS PLAN ACCURATE FOR FENCE LAYOUT ONLY.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	17	69

REGISTERED CIVIL ENGINEER DATE


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

65% SUBMITTAL

REGISTERED PROFESSIONAL ENGINEER
 Corrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA



CONSTRUCTION DETAILS
 SCALE: 1"=50'


DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:30:07 PM
 Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	18	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.







QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

- NOTES:**
1. THIS PLAN ACCURATE FOR CONTOUR GRADING WORK AND RSP PLACEMENT ONLY.
 2. PLACE RSP AT SPECIFIED LOCATIONS. ENGINEER TO DETERMINE EXCAVATION LIMITS AND IF RSP IS NOT NEEDED.
 3. PLACE RSP FABRIC AROUND ALL SIDES OF RSP INTERFACE TO NATIVE SOIL.
 4. RSP IS NOT TO BE PLACED ON SLOPES STEEPER THAN 1:1.
 5. CONTRACTOR SHALL PROTECT BRIDGE PIER COLUMNS AND SHAFTS. PLACE RSP BY BY HAND WITHIN THESE LOCATIONS.

REVISOR: E. MCPHERSON, G. MCLAUGHLIN
 CALCULATED/DESIGNED BY: E. MCPHERSON, G. MCLAUGHLIN
 CHECKED BY: G. MCLAUGHLIN
 CONSULTANT PROJECT MANAGER: MARK RENO
 SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT



CONSTRUCTION DETAILS
 SCALE: AS SHOWN

C-9

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	REVISOR	DATE
	REVISOR	DATE
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY
CONSULTANT PROJECT MANAGER	MARK	RENO
CALCULATED-DESIGNED BY	CHECKED BY	
G. MCLAUGHLIN	DES	CHK

NOTES:

1. THIS PLAN ACCURATE FOR CONTOUR GRADING WORK AND RSP PLACEMENT ONLY.
2. PLACE RSP AT SPECIFIED LOCATIONS. ENGINEER TO DETERMINE EXCAVATION LIMITS AND IF RSP IS NOT NEEDED.
3. PLACE RSP FABRIC AROUND ALL SIDES OF RSP INTERFACE TO NATIVE SOIL.
4. RSP IS NOT TO BE PLACED ON SLOPES STEEPER THAN 1:1.
5. CONTRACTOR SHALL PROTECT BRIDGE PIER COLUMNS AND SHAFTS. PLACE RSP BY BY HAND WITHIN THESE LOCATIONS.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	19	69




REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL



CONSTRUCTION DETAILS
SCALE: AS SHOWN

C-10

DATE PLOTTED: Friday, February 16, 2018 3:31:32 PM, Garrett McLaughlin

NOTE:
1. THIS PLAN IS FOR INFORMATION PURPOSES ONLY.

SURVEY CONTROL DATA (NAVD 88)								
No.	NORTHING	EASTING	ELEVATION	LINE	STATION	OFFSET	Rt/Lt	DESCRIPTION
CP-1	2352603.56	5785286.20	936.21	"E"	26+00.17	26.34'	Rt	MNT 4CP1
CP-2	2351390.25	5785811.36	935.78	"E"	12+13.12	46.13'	Lt	MNT CP2
CP-3	2352311.76	5785424.11	928.45	"E"	22+90.77	63.59'	Lt	5/8" REBAR AND CAP
CP-4	2352304.25	5785545.56	935.15	"E"	22+05.20	22.92'	Rt	SPIKE CP4
CP-529	2357445.71	5784019.13	0.00	"E"	61+21.97	3500.55'	Rt	AP-11
CP-600	2352370.99	5785486.79	933.54	"E"	22+94.12	22.59'	Rt	BRASS CAP
CP-613	2352478.85	5785415.54	933.76	"E"	24+22.22	39.92'	Rt	PT 5.5

65% SUBMITTAL

LEGEND:

- TEMPORARY CONSTRUCTION EASEMENT (TCE)
- SURVEY CONTROL POINT
- RIGHT OF WAY SURVEY MONUMENT (PER SLO COUNTY DETAIL M-1)
- APN ASSESSOR'S PARCEL NUMBER
- ROW POINT NUMBER
- TCE POINT NUMBER
- SURVEY MONUMENT POINT NUMBER
- CURVE DATA NUMBER
- PTE PERMISSION TO ENTER
- ROW TAKE AREA

"E" LINE" CURVE DATA				
Curve #	R	Δ	T	L
C1	1040.00'	43° 22' 15"	413.56'	787.24'

"E" LINE DATA		
Line #	BEARING	DISTANCE
L1	N 02°13'00" E	501.82'
L2	N 41°09'15" W	428.29'

SURVEYOR'S STATEMENT

This map correctly represents a survey made by me or under my direction in conformance with the requirements of the Land Surveyor's Act on JAN. 28, 2014.




JOSEPH T. MORRIS P.L.S. 6192
The field work occurred between Feb. 2013 and Jan. 2014

THE COORDINATE SYSTEM USED FOR THIS SURVEY IS BASED UPON GROUND MEASUREMENTS. A GRID COORDINATE AT THE FOUND BRASS CAP STAMPED "NWP CP 5.5", COUNTY POINT NUMBER 613, N: 2,352,478.85 E: 5,785,415.54 WAS HELD AS A GROUND COORDINATE VALUE. USE THE TABULATED GROUND COORDINATE VALUES SHOWN HEREON FOR THIS PROJECT.

THE BASIS OF BEARINGS FOR THIS MAP IS THE BEARING BETWEEN THE FOUND NACIMIENTO WATER PROJECT CONTROL POINT 5.5 PER THE RECORD OF SURVEY FILED IN 103/LS/83 (POINT NUMBER 613) AND THE FOUND AERIAL PANEL DESIGNATED AP-11, ESTABLISHED BY THE CANNON CORPORATION FOR THE COUNTY OF SAN LUIS OBISPO'S NACIMIENTO WATER PROJECT, ACCORDING TO THE SURVEY CONTROL MAP DATED 4/30/07 (POINT NUMBER 529) AND HAVING A BEARING OF N 15°42'11" W.

THE BENCHMARK FOR THIS PROJECT IS THE FOUND BRASS CAP AT POINT NUMBER 600, STAMPED "C25 RESET 1937", PID FV0164 AND HAVING A NAVD 88 ELEVATION OF 934.41 FEET PER THE NGS DATA SHEET



RIGHT OF WAY MAP
SCALE: 1" = 50'

MATCH LINE STA "E" 24+50 SEE SHEET RW-2

RW-1

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
SANTA MARGARITA CREEK BRIDGE REPLACEMENT

CONSULTANT PROJECT MANAGER
MARK RENO

CALCULATED-DESIGNED BY
CHECKED BY

E. MCPHERSON
G. MCLAUGHLIN


REVISOR BY
DATE REVISED

GM
2/13/2018

DATE

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 E. MCPHERSON
 G. MCLAUGHLIN
 REVISIONS
 GM
 2/13/2018
 DATE REVISED

65% SUBMITTAL



Line #	BEARING	DISTANCE
L2	N 41°09'15" W	428.29'
L3	N 59°57'04" W	12359.63'

Curve #	R	Δ	T	L
C2	2000.00'	18° 47' 49"	331.05'	656.14'

NOTE:
1. THIS PLAN IS FOR INFORMATION PURPOSES ONLY.

RIGHT OF WAY MAP
SCALE: 1" = 50'

RW-2

DATE PLOTTED: Friday, February 16, 2018 3:32:23 PM, Garrett McLaughlin

65% SUBMITTAL

ROW POINTS					
NO.	LINE	STATION	OFFSET	NORTHING	EASTING
1	E	15+10.89	41.09	2351692.0523	5785888.5481
2	E	21+74.70	56.27	2352303.2384	5785590.7411
3	E	22+35.24	145.41	2352407.4818	5785618.0157
4	E	18+79.52	-56.52	2352003.2477	5785676.7219
5	E	22+85.36	-86.78	2352292.4272	5785410.2090
6	E	23+70.42	74.04	2352462.3006	5785475.3221
7	E	24+28.61	71.29	2352504.3023	5785434.9523
8	E	24+71.33	56.99	2352527.0587	5785396.0774
9	E	26+06.84	55.35	2352628.4977	5785302.5021
10	E	26+06.94	44.34	2352620.9672	5785294.4774
11	E	25+22.40	-86.44	2352470.9543	5785254.6129

SURVEY MONUMENT POINTS						
NO.	LINE	STATION	OFFSET	NORTHING	EASTING	DESCRIPTION
1	E	12+19.83	0.00	2351395.1618	5785857.7201	"E" LINE = "W" LINE
2	E	13+01.82	0.00	2351477.0919	5785860.8916	BC
3	E	20+89.06	0.00	2352201.7304	5785604.7295	EC
4	E	22+23.75	0.00	2352303.1443	5785516.0916	"E" LINE = "A" LINE
5	E	22+23.60	52.36	2352337.4906	5785555.6175	BC
6	E	22+35.32	94.28	2352373.9022	5785579.4670	EC
7	E	22+45.56	111.05	2352392.6451	5785585.3546	BC
8	E	22+56.46	142.53	2352421.5618	5785601.8850	EC
9	E	25+17.38	0.00	2352524.2273	5785322.8605	BC
10	E	25+67.83	0.00	2352561.7922	5785289.1828	"E" LINE = "S" LINE
11	E	31+68.24	0.00	2352936.5978	5784823.0189	EC

TCE POINTS					
NO.	LINE	STATION	OFFSET	NORTHING	EASTING
1	E	20+84.35	57.86	2352236.0531	5785651.5593
2	E	20+92.63	186.12	2352326.8964	5785742.5245
3	E	22+38.00	180.12	2352432.4012	5785642.3397
4	E	22+70.81	87.97	2352396.4634	5785551.3637
5	E	23+67.70	80.28	2352464.3591	5785481.8060
6	E	24+47.83	64.85	2352514.5423	5785417.4592
7	E	24+47.82	80.11	2352524.5719	5785428.9559
8	E	20+27.71	-65.31	2352114.3619	5785592.0934
9	E	20+46.37	-209.77	2352037.5708	5785468.6817
10	E	22+90.34	-173.06	2352239.3868	5785341.9691
11	E	22+86.52	-106.77	2352280.1341	5785394.3931
12	E	24+81.12	80.32	2352549.7864	5785407.1986
13	E	24+81.27	56.72	2352534.3701	5785389.3327
14	E	25+61.93	55.04	2352594.5755	5785333.7946
15	E	25+68.90	78.11	2352615.4764	5785345.9283
16	E	26+06.75	65.42	2352635.3898	5785309.8465
17	E	27+73.30	45.96	2352740.0503	5785173.0540
18	E	27+73.03	75.51	2352761.9828	5785192.8472
19	E	28+00.54	75.25	2352780.5712	5785171.1702
20	E	28+07.60	75.25	2352785.3374	5785165.6121
21	E	28+07.87	46.31	2352763.5185	5785146.5940
22	E	28+99.43	47.21	2352823.4551	5785074.5719
23	E	28+99.25	66.67	2352838.6900	5785086.6718
24	E	29+26.81	66.27	2352855.7110	5785063.8409
25	E	29+26.98	47.49	2352840.8453	5785052.3641
26	E	31+03.28	49.26	2352944.7547	5784904.7675
27	E	31+03.27	59.29	2352953.2547	5784910.0920
28	E	31+22.65	59.51	2352963.9546	5784893.2526
29	E	31+22.79	49.45	2352955.4546	5784887.8701
30	E	25+19.35	-106.45	2352455.5772	5785241.4848

NOTE:
1. THIS PLAN IS FOR INFORMATION PURPOSES ONLY.

RIGHT OF WAY MAP
NO SCALE

RW-3

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 E. MCPHERSON
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

NOTES:






1. THIS PLAN ACCURATE FOR TEMPORARY STREAM DIVERSION ONLY.
2. EXACT LENGTH AND LOCATION OF PIPES TO BE DETERMINED IN THE FIELD BY THE ENGINEER.
3. EXACT LOCATION OF DIVERSION DAMS TO BE APPROVED IN THE FIELD BY THE ENGINEER.
4. CONTRACTOR TO SUBMIT STREAM DIVERSION PLAN THAT SHALL BE APPROVED BY THE ENGINEER.
5. STREAM DIVERSION SHALL BE REMOVED DURING WINTER SUSPENSION.
6. DIVERSION SYSTEM SHALL BE PROTECTED DURING ALL BRIDGE CONSTRUCTION AND REMOVAL.
7. ANY FILL ASSOCIATED WITH THE DIVERSION WILL BE CLEAN AND BE REMOVED WHEN NO LONGER REQUIRED.

LEGEND:

- ⊙ INDICATES 48" CIDH PILE
- ⎓ INDICATES EXISTING FOOTINGS TO BE REMOVED

65% SUBMITTAL

TEMPORARY DIVERSION PIPES		
MIN PIPE DIAMETER	QUANTITY OF PIPES	DESIGN FLOW
18 INCHES	2	100 CFS



SEASONAL TEMPORARY STREAM DIVERSION
SCALE: AS SHOWN

THIS SHEET IS FOR INFORMATION PURPOSES ONLY


TSD-1

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	24	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING

11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P. 916.368.9181


65% SUBMITTAL

NOTE:

- THIS PLANS ACCURATE FOR EROSION CONTROL WORK ONLY.
- FOR COMPLETE RIGHT OF WAY AND ACCURATE ACCESS DATA, SEE RIGHT OF WAY RECORD MAPS AT THE COUNTY OFFICE.
- LOCATION OF FIBER ROLLS ARE SCHEMATIC. ACTUAL PLACEMENT LOCATIONS OF FIBER ROLLS SHALL BE IN ACCORDANCE WITH SPECIAL PROVISIONS.
- EROSION CONTROL (HYDROSEED) SHALL NOT BE PLACED WITHIN ACTIVE CREEK.
- NO COMPOST OR MANURE TO BE USED ON THIS PROJECT.


LEGEND:

- FIBER ROLL
- xx --- TSF --- TEMPORARY SILT FENCE
- TFESA --- TEMPORARY FENCE (TYPE ESA)
- EROSION CONTROL (HYDROSEED)



HYDROSEED SEED MIX	
BOTANICAL NAME (COMMON NAME)	POUNDS PURE LIVE SEED PER ACRE (SLOPE MEASUREMENT)
BROMUS CARINATUS (CUCAMONGA BROME)	20
TRIFOLIUM TRIDENTATUM (TOMCAT CLOVER)	4
VULPIA MICROSTACHYS (SMALL FESCUE)	8
TOTAL	32

EROSION CONTROL - HYDROSEED				
ITEM	SEQUENCE	MATERIAL		NOTES
		DESCRIPTION	TYPE	
HYDROSEED	STEP 1	SEED	SEED MIX	32 LB/ACRE
	STEP 2	FIBER	WOOD	1200 LB/ACRE
	STEP 3	TACKIFIER	PSYLLIUM	150 LB/ACRE



EROSION CONTROL PLAN

SCALE: 1" = 50'

EC-1

DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:33:31 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	26	69



65% SUBMITTAL

NOTES:

1. THIS PLAN ACCURATE FOR TREE REMOVAL WORK ONLY.
2. (N) – NOT A SEPARATE PAY ITEM, FOR INFORMATION ONLY.
3. TREES TO BE IMPACTED SHALL BE TRIMMED UNDER THE DIRECTION OF THE RESIDENT ENGINEER.
4. ADDITIONAL TREE REMOVAL AND TREE TRIMMING MAY BE REQUIRED FOR PROJECT CONSTRUCTION AND SHALL BE INCLUDED AS CLEARING AND GRUBBING.
5. FOR TREE DATA TABLES, SEE DRAWING EC-4

LEGEND:

- TFESA — TEMPORARY HIGH VISIBILITY FENCE (TYPE ESA)
- MT MULTI TRUNK
- ☀ TREE SYMBOL
- ☀ (with slash) TREE TO BE REMOVED
- (No.) TREE NUMBER



TREE REMOVAL AND IMPACTS

SCALE: 1" = 20'

TI-1

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 E. MCPHERSON
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

CONSULTANT PROJECT MANAGER
 MARK RENO

CALCULATED-DESIGNED BY
 CHECKED BY

E. MCPHERSON
 G. MCLAUGHLIN

REVISOR BY
 DATE REVISED

GM
 2/13/2018

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	28	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

65% SUBMITTAL

LEGEND:

- gs---gs---gs EXISTING UNDERGROUND GAS
- com---com---com EXISTING UNDERGROUND COMMUNICATION
- (OH)e---(OH)e---(OH)e EXISTING OVERHEAD ELECTRICAL
- ohc---ohc---ohc EXISTING OVERHEAD COMMUNICATION
- GS---GS---G RELOCATED GAS
- W---W---W RELOCATED WATER
- ohc---ohc---ohc RELOCATED OVERHEAD COMMUNICATION
- COM---COM---COM RELOCATED UNDERGROUND COMMUNICATION
- X X X X X REMOVE OR ABANDON UTILITY
- ** WORK TO BE PERFORMED BY OTHERS



- NOTE:**
1. THIS PLAN ACCURATE FOR UTILITY RELOCATION WORK ONLY.
 2. UTILITY TO BE PROTECTED IN PLACE UNLESS OTHERWISE NOTED.
 3. UTILITY LOCATIONS SHOWN ARE APPROXIMATE. CONTRACTOR TO VERIFY LOCATION OF UTILITIES PRIOR TO CONSTRUCTION AND MUST NOTIFY THE ENGINEER OF ANY UNIDENTIFIED CONFLICTS PRIOR TO CONSTRUCTION.
 4. UTILITIES IDENTIFIED AS "ABANDON" OR "ABANDONED" THAT CONFLICT WITH CONSTRUCTION ARE TO BE REMOVED BY CONTRACTOR.

UTILITY TABLE			
NAME	UTILITY TYPE	CONTACT NAME	CONTACT PHONE No.
AT&T TRUNK & TOLL	COMMUNICATION	EMILIO DIAZ	805-645-2929
AT&T LEGACY	COMMUNICATION	JOSEPH FORKERT	
ATASCADERO MUTUAL WATER	POTABLE WATER	JOHN NEIL	805-464-5351
PG&E	ELECTRIC	CLAIRE MASTIN	805-546-3888
THE GAS COMPANY	NATURAL GAS	CLAUDIA TURNER	
GARDEN FARMS COMMUNITY WATER DISTRICT		JANICE MAXWELL	805-434-8564

UTILITY PLAN
 SCALE: 1" = 50'

MATCH LINE STA "E" 24+50 SEE SHEET U-2

NOTE:

1. THIS PLAN ACCURATE FOR UTILITY RELOCATION WORK ONLY.
2. UTILITY TO BE PROTECTED IN PLACE UNLESS OTHERWISE NOTED.
3. UTILITY LOCATIONS SHOWN ARE APPROXIMATE. CONTRACTOR TO VERIFY LOCATION OF UTILITIES PRIOR TO CONSTRUCTION AND MUST NOTIFY THE ENGINEER OF ANY UNIDENTIFIED CONFLICTS PRIOR TO CONSTRUCTION.
4. UTILITIES IDENTIFIED AS "ABANDON" OR "ABANDONED" THAT CONFLICT WITH CONSTRUCTION ARE TO BE REMOVED BY CONTRACTOR.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	29	69



REGISTERED CIVIL ENGINEER _____ DATE _____

PLANS APPROVAL DATE _____

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL



SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	CHECKED BY	REVISOR	DATE
	MARK RENO	G. MCLAUGHLIN	E. MCPHERSON	2/13/2018
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CALCULATED-DESIGNED BY	DATE REVISION	GM	

BORDER LAST REVISED 7/2/2010

USERNAME Garrettm
DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rka002.dwg



UNIT UNIT

PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

UTILITY PLAN
SCALE: 1" = 50'

U-2

DATE PLOTTED: Friday, February 16, 2018 3:35:24 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	30	69

REGISTERED CIVIL ENGINEER DATE

Garrett McLaughlin
No. C67687
CIVIL
STATE OF CALIFORNIA

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181

65% SUBMITTAL

- NOTE:**
1. THIS PLAN ACCURATE FOR UTILITY RELOCATION WORK ONLY.
 2. UTILITY TO BE PROTECTED IN PLACE UNLESS OTHERWISE NOTED.
 3. UTILITY LOCATIONS SHOWN ARE APPROXIMATE. CONTRACTOR TO VERIFY LOCATION OF UTILITIES PRIOR TO CONSTRUCTION AND MUST NOTIFY THE ENGINEER OF ANY UNIDENTIFIED CONFLICTS PRIOR TO CONSTRUCTION.
 4. UTILITIES IDENTIFIED AS "ABANDON" OR "ABANDONED" THAT CONFLICT WITH CONSTRUCTION ARE TO BE REMOVED BY CONTRACTOR.

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO
		CALCULATED-DESIGNED BY	CHECKED BY
E. MCPHERSON		DES. CHK	
REVISOR	DATE REVISED	GM	2/13/2018



UTILITY DETAIL
SCALE: 1" = 20'

UD-1

DATE PLOTTED: Friday, February 16, 2018 TIME PLOTTED: 3:35:44 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	32	69

REGISTERED CIVIL ENGINEER DATE
 REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

65% SUBMITTAL

NOTE:
 1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.



SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	REVISOR
	MARK RENO	E. MCPHERSON
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CHECKED BY	DATE REVISED
	G. MCLAUGHLIN	
	CALCULATED-DESIGNED BY	

BORDER LAST REVISED 7/2/2010

USERNAME Garrettm
 DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rma002.dwg



UNIT UNIT

PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

SC-2


DATE PLOTTED: Friday, February 16, 2018 3:36:22 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	33	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING

11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181


65% SUBMITTAL

NOTE:
1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.

LEGEND:

STAGE 2A PHASE 1

STAGE 2A PHASE 2



STAGE 2:

1. SHIFT SOUTHBOUND TRAFFIC TO NEW EASTERN BRIDGE PORTION AND ROADWAY CONSTRUCTED IN STAGE 1.
2. SHIFT NORTHBOUND TRAFFIC TO EXISTING SOUTHBOUND LANE.
3. CONSTRUCT ROADWAY NORTHERN APPROACH FROM "E" LINE 10+40 TO 20+40.
4. CONSTRUCT RIGHT HAND LANE OF ASUNCION, WHILE UTILIZING TEMPORARY ROAD CONSTRUCTED IN STAGE 1.
5. CONSTRUCT DRIVEWAYS #1, #2, #3, #4, AND #5

MATCH LINE STA "E" 24+50 SEE SHEET SC-4

STAGE 2A
STAGE CONSTRUCTION
SCALE: 1" = 50'

SC-3

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO	CALCULATED-DESIGNED BY	CHECKED BY	E. MCPHERSON	G. MCLAUGHLIN	REVISOR	DATE
		REVISOR	DATE	REVISOR	DATE	REVISOR	DATE	REVISOR	DATE

BORDER LAST REVISED 7/2/2010

USERNAME Garrettm
DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rma003.dwg

RELATIVE BORDER SCALE IS IN INCHES

UNIT UNIT PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:36:47 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	31	69

REGISTERED CIVIL ENGINEER _____ DATE _____
 REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. **C67687**
 CIVIL
 STATE OF CALIFORNIA


PLANS APPROVAL DATE _____
 THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

65% SUBMITTAL

NOTE:
 1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	CONSULTANT PROJECT MANAGER	CALCULATED-DESIGNED BY	E. MCPHERSON	REVISOR
	MARK RENO	CHECKED BY	G. MCLAUGHLIN	DATE REVISED
SANTA MARGARITA CREEK BRIDGE REPLACEMENT				






STAGE 2A
STAGE CONSTRUCTION
 SCALE: 1" = 50'

SC-4

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER
 MARK RENO
 CALCULATED-DESIGNED BY
 CHECKED BY
 E. MCPHERSON
 G. MCLAUGHLIN
 REVISED BY
 DATE REVISED

LEGEND:

-  STAGE 2B, PHASE 1
-  STAGE 2B, PHASE 2
-  STAGE 2B, PHASE 3

NOTE:


1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	32	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING

11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

65% SUBMITTAL



STAGE 2B:

1. PLACE TEMPORARY RAILING (TYPE K), FOR ASUNCION ROAD.
2. BUILD REMAINDER OF ASUNCION ROAD.
3. CONSTRUCT REMAINING SOUTHERN ROADWAY APPROACH FROM "E" LINE STATION 20+40 TO BB.
4. REMOVE TEMPORARY STREAM DIVERSION AND SUSPEND CONSTRUCTION UNTIL NEXT SEASON.

STAGE 2B
STAGE CONSTRUCTION
 SCALE: 1" = 50'

SC-5




Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	33	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING


11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181

65% SUBMITTAL

NOTE:
1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.

LEGEND:

STAGE 3



- STAGE 3:**
1. INSTALL TEMPORARY STREAM DIVERSION.
 2. SHIFT NORTHBOUND TRAFFIC EAST TO ROADWAY CONSTRUCTED IN STAGE 2.
 3. REMOVE REMAINING BRIDGE STRUCTURE AND BUILD MIDDLE PORTION OF NEW STRUCTURE, SEE BRIDGE PLANS.
 4. CONSTRUCT REMAINING PORTION OF ROADWAY APPROACHES.
 5. REMOVE TEMPORARY STREAM DIVERSION.
 6. CONSTRUCT BRIDGE CLOSURE POURS.
 7. REMOVE ALL TEMPORARY RAILING (TYPE K) AND SHIFT TRAFFIC TO FINAL CONFIGURATION, SEE PAVEMENT DELINEATION PLANS.
 8. PLACE FINAL LIFT OF HMA FOR PROJECT LIMITS UNDER DAILY TRAFFIC CONTROL.
 9. PLACE FINAL PAVEMENT DELINEATION.

MATCH LINE STA "E" 24+50 SEE SHEET SC-7

**STAGE 3
STAGE CONSTRUCTION**
SCALE: 1" = 50'

SC-6

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO
	CALCULATED-DESIGNED BY	CHECKED BY
	REVISOR	DATE
	REVISION	DATE

BORDER LAST REVISED 7/2/2010

USERNAME: GarrettM
DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rma006.dwg



DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:37:55 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	34	69

REGISTERED CIVIL ENGINEER DATE
 REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

NOTE:
 1. THIS PLAN IS ACCURATE FOR STAGE CONSTRUCTION WORK ONLY.



SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO	CALCULATED-DESIGNED BY	E. MCPHERSON	REVISOR	DATE
			CHECKED BY	G. MCLAUGHLIN		



STAGE 3
STAGE CONSTRUCTION
 SCALE: 1"=50'

SC-7


REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL





GENERAL NOTES:

1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.
2. ALL SIGNS AND DEVICES SHOWN AS PART OF STANDARD PLANS.
3. FROM STATION EB TO CONFORM, BUILD ROADWAY SECTION SO LONGITUDINAL GRADE DIFFERENCE IS NO GREATER THAN 2".
4. SEE CONSTRUCTION DETAILS FOR ASUNCION RD STRUCTURAL SECTION.
5. SEE STAGE CONSTRUCTION FOR WORK AREA LOCATIONS.
6. SIGN LOCATIONS SHOWN ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY THE ENGINEER.



CURVE DATA

NO.	R	Δ	T	L
C1	80.00	48° 37' 35"	36.14'	67.90'
C2	80.00	46° 11' 08"	34.11'	64.49'



ABBREVIATIONS:
 PPS PLACED IN PREVIOUS STAGE
 TL-3 TEST LEVEL 3

- LEGEND:**
- ➔ DIRECTION OF TRAFFIC
 - • • CHANNELIZER (SURFACE MOUNTED) @ 20' O.C.
 - XX TEMPORARY TRAFFIC STRIPE (PAINT) LINE DETAIL No.
 - TEMPORARY RAILING (TYPE K) - 20'
 - TEMPORARY RAILING (TYPE K) - 10'
 - ⊣ ROADSIDE SIGN - ONE POST
 - ⊣ TYPE III BARRICADE
 - ▨▨▨▨▨ TEMPORARY CRASH CUSHION (ABSORB 350, TL-3)

LINE DATA

NO.	BEARING	DISTANCE
L1	N 48°50'45" E	39.70'
L2	N 00°13'10" E	53.44'
L3	N 46°24'18" E	46.04'

STAGE 1 - PHASE 1 & 2 TRAFFIC HANDLING
 1" = 50'

TH-1

REVISOR: E. MCPHERSON, G. MCLAUGHLIN
 CALCULATED/DESIGNED BY: E. MCPHERSON, G. MCLAUGHLIN
 CHECKED BY: G. MCLAUGHLIN
 CONSULTANT PROJECT MANAGER: MARK RENO
 SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

DATE PLOTTED: Friday, February 16, 2018 3:38:39 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	36	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

- NOTE:**
1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.
 2. ACCESS TO DRIVEWAY # 6 SHALL BE MAINTAINED AT ALL TIMES.

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER MARK RENO	CALCULATED-DESIGNED BY E. MCPHERSON	REVISOR E. MCPHERSON
	SEE SHEET TH-1 MATCH LINE STA "E" 24+50	CHECKED BY G. MCLAUGHLIN	DATE REVISED



**STAGE 1 - PHASE 1 & 2
 TRAFFIC HANDLING**
 1" = 50'

TH-2

DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:39:02 PM, Garrett McLaughlin

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	38	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

QUINCY ENGINEERING


11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

65% SUBMITTAL

- NOTE:**
- THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.
 - ACCESS TO DRIVEWAY # 6 SHALL BE MAINTAINED AT ALL TIMES.



SECTION A-A
NO SCALE



STAGE 1 - PHASE 3
TRAFFIC HANDLING
 1" = 50'

TH-4

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	REVISOR	DATE
	REVISOR	DATE
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY
CONSULTANT PROJECT MANAGER	PROJECT MANAGER	DATE
	PROJECT MANAGER	DATE
SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY

BORDER LAST REVISED 7/2/2010

USERNAME Garrettm
 DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rmd004.dwg



UNIT UNIT PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

DATE PLOTTED: Friday, February 16, 2018 3:39:47 PM, Garrett McLaughlin


Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	39	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE





THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181



65% SUBMITTAL

NOTES:
1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.



MATCH LINE STA "E" 24+50 SEE SHEET TH-6

STAGE 2A TRAFFIC HANDLING
1" = 50'

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
SANTA MARGARITA CREEK BRIDGE REPLACEMENT

REVISOR: E. MCPHERSON
DATE: G. MCLAUGHLIN
CALCULATED-DESIGNED BY: MARK RENO
CHECKED BY:

BORDER LAST REVISED 7/2/2010

USERNAME: Garrett
DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rmd005.dwg

RELATIVE BORDER SCALE IS IN INCHES
0 1 2 3

UNIT UNIT PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:40:19 PM, Garrett McLaughlin

TH-5

NOTE:

1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.
2. ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	40	69

REGISTERED CIVIL ENGINEER DATE


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL

REGISTERED PROFESSIONAL ENGINEER
Garrett McLaughlin
 No. C67687
 CIVIL
 STATE OF CALIFORNIA



SECTION D-D
NO SCALE




STAGE 2A
TRAFFIC HANDLING
1" = 50'

TH-6


REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS	REVISIONS

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS	REVISOR	DATE
	REVISOR	DATE
SANTA MARGARITA CREEK BRIDGE REPLACEMENT	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY
CONSULTANT PROJECT MANAGER	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY
MARK RENO	DESIGNED BY	CHECKED BY
	DESIGNED BY	CHECKED BY


NOTE:
 1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.
 2. FOR STAGE 2B PHASE 3, ONE WAY TRAFFIC CONTROL WITH FLAGGING WILL BE NEEDED UNTIL GRADE AT ASUNCION ROAD IS ACCEPTABLE TO FACILITATE LEFT HAND TURN ONTO EL CAMINO REAL. NIGHT WORK MAY BE NEEDED.



SECTION A-A
NO SCALE



SECTION B-B
NO SCALE



Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	41	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL

REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

MATCH LINE STA "E" 24+50 SEE SHEET TH-6

STAGE 2B
TRAFFIC HANDLING
 1"=50'


TH-7

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	42	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE



THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING
11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181

65% SUBMITTAL

NOTE:
1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.



MATCH LINE STA "E" 24+50 SEE SHEET TH-9

STAGE 3
TRAFFIC HANDLING
1"=50'

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
SANTA MARGARITA CREEK BRIDGE REPLACEMENT

CONSULTANT PROJECT MANAGER
MARK RENO

CALCULATED-DESIGNED BY
CHECKED BY

E. MCPHERSON
G. MCLAUGHLIN

REVISED BY
DATE REVISED

BORDER LAST REVISED 7/2/2010

USERNAME Garrettm
DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201rmd008.dwg

RELATIVE BORDER SCALE IS IN INCHES

UNIT UNIT PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

TH-8

DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:41:43 PM, Garrett McLaughlin

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER MARK RENO	CALCULATED-DESIGNED BY CHECKED BY	E. MCPHERSON G. MCLAUGHLIN	REVISED BY DATE REVISED


NOTE:
1. THIS PLAN ACCURATE FOR TRAFFIC HANDLING WORK ONLY.

DIST	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	43	69

REGISTERED CIVIL ENGINEER DATE _____



PLANS APPROVAL DATE _____

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P. 916.368.9181

65% SUBMITTAL



**STAGE 3
TRAFFIC HANDLING**
1"=50'

TH-9



DATE PLOTTED: Friday, February 16, 2018
TIME PLOTTED: 3:42:12 PM, Garrett McLaughlin

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

REVISOR
 E. MCPHERSON
 G. MCLAUGHLIN



REVISOR
 DATE REVISOR

DESIGNER
 CALCULATED-DESIGNED BY
 CHECKED BY

PROJECT MANAGER
 CONSULTANT PROJECT MANAGER
 MARK RENO

DATE
 7/2/2010

NOTE:
 1. SIGN LOCATIONS SHOWN ARE APPROXIMATE. EXACT LOCATIONS TO BE DETERMINED BY THE ENGINEER.



- LEGEND:**
- ➔ DIRECTION OF DETOUR TRAFFIC
 - ⊣ STATIONARY MOUNTED CAS - ONE POST
 - WORK AREA (CLOSED TO TRAFFIC)
 - ⊗ CONSTRUCTION AREA SIGN NUMBER

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	44	69

REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE


REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

SIGN No.	SIGN CODE	PANEL SIZE (IN X IN)	SIGN MESSAGE	POST SIZE (IN X IN)	No. OF POSTS (EA)	No. OF SIGNS (EA)	DESCRIPTION
1	W20-2	48 X 48	DETOUR AHEAD	4 x 4	1	1	BLACK ON ORANGE
2	M4-8	30 X 15	DETOUR	4 x 4	1	3	BLACK ON ORANGE
3	M4-8a	24 X 18	END DETOUR	4 x 4	1	1	BLACK ON ORANGE
4	M6-3	21 X 15	STRAIGHT ARROW			1	BLACK ON ORANGE
5	M6-1 (LT)	21 X 15	LEFT ARROW				BLACK ON ORANGE
6	M6-1 (RT)	21 X 15	RIGHT ARROW			2	BLACK ON ORANGE
7	SP-1		WALNUT AVE CLOSED AT EL CAMINO REAL	4 x 6	2	4	BLACK ON ORANGE
SUBTOTAL							
TOTAL							



⊗ **SP-1**
 NO SCALE

DETOUR PLAN
 NO SCALE

DE-1

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

REVISOR: E. MCPHERSON
 DATE: G. MCLAUGHLIN

REVISOR: E. MCPHERSON
 DATE: G. MCLAUGHLIN



CALCULATED-DESIGNED BY: E. MCPHERSON
 CHECKED BY: G. MCLAUGHLIN

CONSULTANT PROJECT MANAGER: MARK RENO

DATE: 7/2/2010

NOTE:
 1. SIGN LOCATIONS SHOWN ARE APPROXIMATE. EXACT LOCATIONS ARE TO BE DETERMINED BY THE ENGINEER.

CONSTRUCTION AREA SIGN (STATIONARY MOUNTED)							
SIGN No.	SIGN CODE	PANEL SIZE (IN X IN)	SIGN MESSAGE	POST SIZE (IN X IN)	No. OF POSTS (EA)	No. OF SIGNS (EA)	DESCRIPTION
1	W20-2	48 X 48	DETOUR AHEAD	4 x 4	1	3	BLACK ON ORANGE
2	M4-8	30 X 15	DETOUR	4 x 4	1	9	BLACK ON ORANGE
3	M4-8a	24 X 18	END DETOUR	4 x 4	1	2	BLACK ON ORANGE
4	M6-3	21 X 15	STRAIGHT ARROW			2	BLACK ON ORANGE
5	M6-1 (LT)	21 X 15	LEFT ARROW			5	BLACK ON ORANGE
6	M6-1 (RT)	21 X 15	RIGHT ARROW			2	BLACK ON ORANGE
8	W20-3	48 X 48	ROAD CLOSED AHEAD	4 x 4	1	1	BLACK ON ORANGE
9	SP-2		SANTA MARGARITA RD CLOSED AT EL CAMINO REAL	4 x 6	2	2	BLACK ON ORANGE
SUBTOTAL							
TOTAL							



Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	45	69

REGISTERED CIVIL ENGINEER: **Garrett McLaughlin**
 No. C67687
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE: _____ DATE: _____

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL

DETOUR PLAN
 SCALE

DE-2

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT

REVISOR
 E. MCPHERSON
 G. MCLAUGHLIN

DATE REVISOR
 DATE REVISOR

CALCULATED-DESIGNED BY
 CHECKED BY

CONSULTANT PROJECT MANAGER
 MARK RENO

BORDER LAST REVISED 7/2/2010

USERNAME: GarrettM
 DWG FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\roadway\AutoCad Civil 3D 2015\S13201ma001.dwg

RELATIVE BORDER SCALE IS IN INCHES
 0 1 2 3

UNIT UNIT

PROJECT NUMBER & PHASE S13201 - 65% SUBMITTAL

NOTES:

1. THIS PLAN ACCURATE FOR PAVEMENT DELINEATION WORK ONLY.
2. ALL PAVEMENT MARKINGAS AT INTERSECTIONS SHALL BE PLACED 6' BEHIND LIMIT LINE.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	46	69

REGISTERED CIVIL ENGINEER DATE


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL

REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA



- LEGEND:**
- BICYCLE DIRECTION ARROW (THERMOPLASTIC PAVEMENT MARKING)
 - TRAFFIC ARROW (TYPE 3) (THERMOPLASTIC PAVEMENT MARKING)
 - TRAFFIC ARROW (TYPE 6) (THERMOPLASTIC PAVEMENT MARKING)
 - BICYCLE LANE SYMBOL (THERMOPLASTIC PAVEMENT MARKING)
 - STOP (THERMOPLASTIC PAVEMENT MARKING)
 - OBJECT MARKER (TYPE P)
 - PAVEMENT DELINEATION DETAIL NUMBER
 - LIMIT LINE W/ LENGTH (THERMOPLASTIC PAVEMENT MARKING)

PAVEMENT DELINEATION
 SCALE: 1" = 50'

MATCH LINE STA "E" 24+50 SEE SHEET PD-2

PD-1

DATE PLOTTED: Friday, February 16, 2018
 TIME PLOTTED: 3:43:24 PM, Garrett McLaughlin

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO	CALCULATED-DESIGNED BY	E. MCPHERSON	REVISOR	
			CHECKED BY	G. MCLAUGHLIN	DATE REVISED	

- NOTES:**
1. THIS PLAN ACCURATE FOR PAVEMENT DELINEATION WORK ONLY.
 2. FOR NOTES AND LEGEND, SEE DRAWING PD-1.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	47	69



REGISTERED CIVIL ENGINEER DATE

PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL



PAVEMENT DELINEATION
SCALE: 1" = 50'

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS
 SANTA MARGARITA CREEK BRIDGE REPLACEMENT
 CONSULTANT PROJECT MANAGER: MARK RENO
 C. POLGLASE
 G. MCLAUGHLIN
 REVISOR: G. MCLAUGHLIN
 DATE REVISOR: []
 CALCULATED-DESIGNED BY: []
 CHECKED BY: []
 BORDER LAST REVISED 7/2/2010


NOTES:
 1. THIS PLAN ACCURATE FOR SIGN WORK ONLY.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	48	69

REGISTERED CIVIL ENGINEER DATE
 REGISTERED PROFESSIONAL ENGINEER
 No. C67687
 CIVIL
 STATE OF CALIFORNIA
 PLANS APPROVAL DATE
 THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P. 916.368.9181

65% SUBMITTAL



- LEGEND:**
- (CA) CALIFORNIA SIGN CODE
 - (X-X) CODE(S) ROADSIDE SIGN (SHEET NUMBER - SIGN NUMBER) W/ SIGN CODE(S)
 - ▲ EXISTING ROADSIDE SIGN TO REMAIN
 - REMOVE ROADSIDE SIGN
 - RELOCATE ROADSIDE SIGN
 - ↑ ROADSIDE SIGN SINGLE POST
 - ↓ EXISTING ROADSIDE SIGN
 - ☒ EXISTING MAILBOX
 - ☒ MAILBOX

SIGN PLAN
 SCALE: 1" = 50'

MATCH LINE STA "E" 24+50 SEE SHEET PD-2

SAN LUIS OBISPO - DEPARTMENT OF PUBLIC WORKS SANTA MARGARITA CREEK BRIDGE REPLACEMENT	CONSULTANT PROJECT MANAGER	MARK RENO	CALCULATED-DESIGNED BY	C. POLGLASE	REVISOR	DATE
			CHECKED BY	MCLAUGHLIN		

- NOTES:**
1. THIS PLAN ACCURATE FOR SIGN WORK ONLY.
 2. FOR NOTES AND LEGEND, SEE DRAWING S-1.

Dist	COUNTY	PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	SANTA MARGARITA CREEK BRIDGE ON EL CAMINO REAL	49	69

REGISTERED CIVIL ENGINEER DATE


PLANS APPROVAL DATE

THE COUNTY OF SAN LUIS OBISPO OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

65% SUBMITTAL

REGISTERED PROFESSIONAL ENGINEER
 No. **C67687**
 CIVIL
 STATE OF CALIFORNIA




SIGN PLAN
SCALE: 1" = 50'

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	50	68


65% SUBMITTAL
 REGISTERED CIVIL ENGINEER DATE
 Jason H Chou
 No. C74835
 Exp. 12/31/19
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181




PROFILE GRADE
NO SCALE




- LEGEND**
- ← Indicates direction of travel
 - Indicates direction of flow
 - ▽ Indicates 100 Year Water Surface Elev
 - Indicates existing structure

- ① Point "Br. No. 49C0474"
- ② Point "Santa Margarita Creek Bridge"
- ③ RSP, see Road Plans




TYPICAL SECTION
1"=5'

ELEVATION
1"=20'



PLAN
1"=20'



STAGE CONSTRUCTION
1"=5'

- NOTES:**
- For Index to Plans, General Notes, Hydraulic Summary, and Quantities, see "General Notes" sheets.
 - For Pile Data Tables, and Utilities not shown, see "Foundation Plan" sheet.
 - For Stage 2 traffic handling, see Road Plans.

DESIGN OVERSIGHT	DESIGN BY J. Chou	CHECKED DES CHK	LOAD & RESISTANCE FACTOR DESIGN	LIVE LOADING: HL93 W/"LOW-BOY" AND PERMIT DESIGN VEHICLE	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT		
SIGN OFF DATE	DETAILS BY R. Kotey	CHECKED DET CHK	LAYOUT BY LAYOUT BY	CHECKED LAYOUT CHECK	Mario Quest PROJECT ENGINEER	POST MILE ---			
	QUANTITIES BY QTY BY	CHECKED QTY CHK	SPECIFICATIONS BY SPECS BY	PLANS AND SPECS COMPARED SPEC CHECK	UNIT: UNIT PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	GENERAL PLAN		
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)						DISREGARD PRINTS BEARING EARLIER REVISION DATES		REVISION DATES	SHEET 1 OF 19

DATE PLOTTED 11/1/2018 4:05:15 PM TIME PLOTTED 4:05:15 PM USERNAME: Saifm

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	51	68

65% SUBMITTAL
REGISTERED CIVIL ENGINEER DATE _____

PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

JASON H. CHOU
REGISTERED PROFESSIONAL ENGINEER
No. C74835
Exp. 12/31/19
CIVIL
STATE OF CALIFORNIA

GENERAL NOTES
LOAD AND RESISTANCE FACTOR DESIGN

DESIGN: AASHTO LRFD Bridge Design Specifications 6th edition with interims through 2013 and the Caltrans Amendments V13 except that Standard Plans dated 2010 and Standard Bridge Details XS sheets are designed using Bridge Design Specifications ('96 AASHTO w/Revisions by Caltrans).

SEISMIC DESIGN: Caltrans Seismic Design Criteria (SDC), Version 1.7 dated April 2013.

DEAD LOAD: Includes 35 psf for future wearing surface.

LIVE LOADING: HL93 and Permit design load.

SEISMIC LOADING: Soil Profile D = 328 m/s
Moment Magnitude Mmax = 7.4
Peak Ground Acceleration = 0.59 g

REINFORCED CONCRETE: $f_y = 60$ ksi
 $f'_c = 3.6$ ksi, unless otherwise noted
 $n = 8$
Transverse Deck Slabs (Working Stress Design)
 $f_s = 20,000$ psi
 $f_c = 1,200$ psi
 $n = 10$

PRESTRESSED CONCRETE: See "Prestressing Notes" on "Superstructure Details No.1" sheet.

QUANTITIES


Bridge Removal	LS
Structure Excavation (Bridge)	CY
Structure Excavation (Bridge)	CY
Structure Backfill (Bridge)	CY
24" Cast-In-Drilled-Hole Concrete Piling	LF
48" Cast-In-Drilled-Hole Concrete Piling	LF
Structural Concrete, Bridge Footing	CY
Structural Concrete, Bridge	CY
Structural Concrete, Approach Slab (Type EQ)	CY
Joint Seal (MR 2")	LF
Bar Reinforcing Steel (Bridge)	LB
Tubular Bicycle Railing	LF
6" Welded Steel Pipe Casing (Bridge)	LF
Concrete Barrier (Type 80, Mod)	LF

INDEX TO PLANS

Sheet No.	Title
1	General Plan
2	General Notes
3	Deck Contours
4	Foundation Plan
5	Abutment 1 Layout
6	Abutment 4 Layout
7	Abutment Details No.1
8	Abutment Details No.2
9	Abutment Details No.3
10	Pier Details No.1
11	Pier Details No.2
12	Typical Section
13	Superstructure Details No.1
14	Superstructure Details No.2
15	Superstructure Details No.3
16	Tubular Bicycle Railing Details
17	Log of Test Borings No. 1
18	Log of Test Borings No. 2

STANDARD PLANS DATED 2015

A3A	Abbreviations (Sheet 1 of 3)
A3B	Abbreviations (Sheet 2 of 3)
A3C	Abbreviations (Sheet 3 of 3)
A10A	Legend - Lines and Symbols (Sheet 1 of 5)
RSP A10B	Legend - Lines and Symbols (Sheet 2 of 5)
A10C	Legend - Lines and Symbols (Sheet 3 of 5)
A10D	Legend - Lines and Symbols (Sheet 4 of 5)
A10E	Legend - Lines and Symbols (Sheet 5 of 5)
A10F	Legend - Soil (Sheet 1 of 2)
A10G	Legend - Soil (Sheet 2 of 2)
A10H	Legend - Rock
A62C	Limits of Payment for Excavation and Backfill- Bridge
RSP B0-1	Bridge Details
RSP B0-3	Bridge Details
B0-5	Bridge Details
B0-13	Bridge Details
B6-21	Joint Seals (Max Movement R=2")
B7-10	Utility Opening - Box Girder
RSP B8-5	Cast-in-Place Post-Tensioned Girder Details
B11-60	Concrete Barrier Type 80 (Sheet 1 of 2)
B11-61	Concrete Barrier Type 80 (Sheet 1 of 2)
T3A	Temporary Railing (Type K)



SCOUR DATA TABLE

SUPPORT No.	LONG TERM (DEGRADATION AND CONTRACTION) SCOUR ELEVATION (ft)	SHORT TERM (LOCAL) SCOUR DEPTH (ft)
Abut 1	921.0*	*
Pier 2	903.0	2.0
Pier 3	903.0	2.0
Abut 4	919.0**	**


* Scour resistant material is present at elevation 924; the abutment footing has been set 3 ft below the top of scour resistant material.
** Scour resistant material is present at elevation 922; the abutment footing has been set 3 ft below the top of scour resistant material.

HYDROLOGIC SUMMARY


Drainage area: 22.4 Square Miles

	Design Flood	Base Flood
Frequency (years)	50	100
Discharge (cubic feet per second)	7,850	9,435
Water Surface Elev at Bridge (ft)	931.8	933.2

Flood plain data based upon information available when the plans were prepared and are shown to meet Federal requirements. The accuracy of said information is not warranted by the County and interested or affected parties should make their own investigations.



ACCELERATION RESPONSE SPECTRA CURVE
No Scale



- Structural Concrete, Bridge ($f'_c = 4.0$ ksi at 28 days)
- Structural Concrete, Bridge ($f'_c = 5.0$ ksi at 28 days)
- Structural Concrete, Bridge Footing
- Structural Concrete, Approach Slab Type EQ(10)
- Cast-In-Drilled-Hole Concrete Piling ($f'_c = 4.0$ ksi at 28 days)


CONCRETE STRENGTH AND TYPE LIMITS

No Scale

DESIGN OVERSIGHT	DESIGN BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	MARIO QUEST PROJECT ENGINEER	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT
SIGN OFF DATE	DETAILS BY R. KOTEY	CHECKED DET CHK		PROJECT NUMBER & PHASE: S13201	POST MILE ---	
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	QUANTITIES BY QTY BY	CHECKED QTY CHK		CONTRACT NO.: CONTRACT	REVISION DATES 10/28/15	

UNIT: UNIT
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS: 0 1 2 3
DISREGARD PRINTS BEARING EARLIER REVISION DATES
SHEET 2 OF 19
FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\bridge\S13201a-b-gnote01.dwg

DATE PLOTTED 11/1/2018 4:05:24 PM TIME PLOTTED 4:05:24 PM USERNAME Salim



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	52	68

65% SUBMITTAL


REGISTERED CIVIL ENGINEER DATE



PLANS APPROVAL DATE


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181




PLAN
1"=10'

Notes:
X = 0.10' intervals along station line
Contour Intervals = 0.10'
Contours do not include camber




Note: Does not include allowance for falsework settlement

CAMBER DIAGRAM
NO SCALE



- ▨ Indicates Structure Excavation (Bridge)
- ▨ Indicates Backfill (Compaction not required)

LIMITS OF PAYMENT FOR EARTHWORK AT PIERS
No Scale



- ▨ Indicates Structure Excavation (Bridge)
- ▨ Indicates Structure Backfill (Bridge)

LIMITS OF PAYMENT FOR EARTHWORK AT ABUTMENTS
No Scale

DESIGN OVERSIGHT SIGN OFF DATE	DESIGN BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT
	DETAILS BY R. KOTEY	CHECKED DET CHK		PROJECT ENGINEER Mario Quest	
	QUANTITIES BY QTY BY	CHECKED QTY CHK		POST MILE -----	
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			UNIT: UNIT PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT
				REVISION DATES	SHEET 3 OF 19

DATE PLOTTED 11/1/2018 4:05:39 PM TIME PLOTTED 4:05:39 PM USERNAME Correttm

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	53	68


65% SUBMITTAL
 REGISTERED CIVIL ENGINEER DATE _____

PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181



- Legend:**
- X.XX Indicates bottom of footing elevation
 - Indicate 24" CIDH Concrete Piling, no all piles shown
 - Indicate 48" CIDH Concrete Piling
 - Indicate direction of flow
 - w-w- Indicates existing potable waterline
 - tc-tc- Indicates existing AT&T
 - (OH) t Indicates existing AT&T
 - fo-(UG)- Indicates existing fiber optic
 - FO-(OH)- Indicates relocated fiber optic
 - gs-gs- Indicates existing gas
 - GS- Indicates relocated gas

PILE DATA TABLE

LOCATION	PILE TYPE	NOMINAL RESISTANCE		DESIGN TIP ELEVATION (ft)	SPECIFIED TIP ELEVATION (ft)
		COMPRESSION	TENSION		
Abut 1	24" CIDH	2190	N/A	887(a), 886(a-I), 902(a-II), 889(c)	886
Pier 2	48" CIDH	3120	N/A	872(a), 861(a-I), 881(a-II), 872(c)	860
Pier 3	48" CIDH	3030	N/A	873(a), 861(a-I), 881(a-II), 873(c)	860
Abut 4	24" CIDH	2110	N/A	887(a), 884(a-I), 900(a-II), 887(c)	884

Notes:

- Design tip elevations are controlled by: (a) Compression (Service Limit), (b) Tension (Service Limit), (a-I) Compression (Strength Limit), (b-I) Tension (Strength Limit), (a-II) Compression (Extreme Event), (b-II) Tension (Extreme Event), (c) Settlement, (d) Lateral Load - to be determined by designer.
- The design tip elevations assume long term channel degradation elevation of 903 feet.

PLAN
1"=10'

PROJECT CONTROL COORDINATE TABLE

No.	NORTHING	EASTING	ELEVATION	LINE	STATION	OFFSET	DESCRIPTION
600	2,352,370.9302	5,785,486.7945	934.51	"E"	22+94.07	22.55' Rt	FDBM (C-25) Reset 1937
613	2,352,478.8500	5,785,415.5400	933.86	"E"	24+22.22	39.92' Rt	FDBCWPCP5.5
3	2,352,311.7582	5,785,424.1119	928.55	"E"	22+90.77	63.59' Lt	set-5/8-rbar-cp3
4	2,352,304.2516	5,785,545.5594	935.25	"E"	22+05.20	22.22' Rt	set-spk-cp4
6	2,352,437.2806	5,785,467.4013	919.78	"E"	23+56.79	51.61' Rt	rbar4cp6
58	2,352,262.0903	5,785,440.1649	918.04	"E"	23+18.12	18.40' Lt	fdn

Curve Table

Curve #	R	Δ	T	L
C23B	30.00	89° 21' 56"	29.67	46.79

DESIGN OVERSIGHT	DESIGN	BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO.	SANTA MARGARITA CREEK BRIDGE REPLACEMENT
	DETAILS	BY R. KOTEY	CHECKED DET CHK		MARIO QUEST PROJECT ENGINEER	
SIGN OFF DATE	QUANTITIES	BY QTY BY	CHECKED QTY CHK	UNIT: UNIT	POST MILE	FOUNDATION PLAN
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	0 1 2 3	PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES
						10/28/19
						SHEET 4 OF 19

FILE S:\Client\SLO-County\S13-201-El Camino Real\CAD\bridge\S13201a-e-fp01.dwg

DATE PLOTTED 11/1/2018 4:05:55 PM USER:NAME Salim

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	54	68

65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE _____
 Jason H. Chou
 No. C74835
 Exp. 12/31/19
 CIVIL
 STATE OF CALIFORNIA





PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.
QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181

NOTES:

- For sections and details not shown, see "Abutment 4 Layout" and Abutment Details sheets.
 - All abutment and footing reinforcement through construction joint shall be joined by mechanical couplers.
 - For soil nail details, see "Abutment Details No. 2" sheet.
- * Denotes bars to be extended beyond construction joint to be lap spliced with Stage II.

Legend:

- ⊙ Indicates vertical pile
- ⊕ Brg Abut =
- ⊕ Footing



DESIGN OVERSIGHT _____
 SIGN OFF DATE _____
 DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)

DESIGN	BY J. Chou	CHECKED DES CHK
DETAILS	BY R. Kotey	CHECKED DET CHK
QUANTITIES	BY QTY BY	CHECKED QTY CHK

PREPARED FOR THE
SAN LUIS OBISPO
 DEPARTMENT OF PUBLIC WORKS

Mario Quest
 PROJECT ENGINEER

BRIDGE NO. 49C0474
 POST MILE _____

SANTA MARGARITA CREEK BRIDGE REPLACEMENT
ABUTMENT 1 LAYOUT

UNIT: UNIT
 PROJECT NUMBER & PHASE: S13201 CONTRACT NO.: CONTRACT _____

REVISION DATES
 10/28/15

SHEET 5 OF 19


ORIGINAL SCALE IN INCHES FOR REDUCED PLANS

DATE PLOTTED 11/1/2018 4:06:00 PM USERNAME Solimb TIME PLOTTED 4:06:00 PM

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	55	68

65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670 P: 916.368.9181

NOTES:


- For sections and details not shown, see "Abutment 1 Layout" and Abutment Details sheets.
 - All abutment and footing reinforcement through construction joint shall be joined by mechanical couplers.
 - For soil nail details, see "Abutment Details No. 2" sheet.
- * Denotes bars to be extended beyond construction joint to be lap spliced with Stage II.

Legend:


⊙ Indicates vertical pile




PLAN
1/4" = 1'-0"



ELEVATION
1/4" = 1'-0"




FOOTING PLAN
1/4" = 1'-0"



TYPICAL WINGWALL ELEVATION
1/4" = 1'-0"

Note: Abutment 4 Wingwalls show, Abutment 1 Left similar. For Abutment 1 Right Wingwall, see "Abutment 1 Right Wingwall Elevation" on "Abutment Details No.2" sheet.



SECTION C-C
1/2" = 1'-0"

DESIGN OVERSIGHT _____
 SIGN OFF DATE _____

DESIGN	BY J. Chou	CHECKED DES CHK
DETAILS	BY R. Kotey	CHECKED DET CHK
QUANTITIES	BY QTY BY	CHECKED QTY CHK

PREPARED FOR THE
SAN LUIS OBISPO
 DEPARTMENT OF PUBLIC WORKS

Mario Quest
 PROJECT ENGINEER

BRIDGE NO. 49C0474
 POST MILE _____
SANTA MARGARITA CREEK BRIDGE REPLACEMENT
ABUTMENT 4 LAYOUT

DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)

ORIGINAL SCALE IN INCHES FOR REDUCED PLANS

UNIT: UNIT PROJECT NUMBER & PHASE: S13201 CONTRACT NO.: CONTRACT


REVISION DATES	SHEET	OF
10/28/15	6	19

DATE PLOTTED 11/1/2018 4:06:10 PM TIME PLOTTED 4:06:10 PM USERNAME Solimb


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	57	68

65% SUBMITTAL


REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181




DEVELOPED VIEW G-G
 1/4" = 1'-0"




SECTION J-J
 1/2" = 1'-0"




SECTION F-F
 1/2" = 1'-0"




ABUTMENT 1 LEFT & ABUTMENT 4 WINGWALL ELEVATION
 1/4" = 1'-0"



SOIL WALL ELEVATION
 1/4" = 1'-0"



SECTION H-H
 3/4" = 1'-0"



SECTION I-I
 3/4" = 1'-0"

DESIGN OVERSIGHT SIGN OFF DATE	DESIGN BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT				
	DETAILS BY R. KOTEY	CHECKED DET CHK		PROJECT ENGINEER Mario Quest		ABUTMENT DETAILS NO.2			
	QUANTITIES BY QTY BY	CHECKED QTY CHK		CONTRACT NO.: CONTRACT					
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			UNIT: UNIT PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 8	OF 19


DATE PLOTTED 11/1/2018 4:06:30 PM TIME PLOTTED 4:06:30 PM USERNAME Solimb

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	58	68


65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE _____
 REGISTERED PROFESSIONAL ENGINEER
Jason H Chou
 No. C74835
 Exp. 12/31/19
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.
QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181




RETAINING WALL AT ABUT 1
 3/4" = 1'-0"



RETAINING WALL AT ABUT 4
 3/4" = 1'-0"


- Rock Texture
- Timber Beam Texture
- Prepare and Stain Concrete

Exclude stain and texture on inside faces of joint posts



INTERIOR TRANSITION ELEVATION

EXTERIOR TRANSITION ELEVATION



SECTION VIEW

INTERIOR ELEVATION

EXTERIOR ELEVATION

CONCRETE BARRIER (TYPE 80) (MOD) ARCHITECTURAL TREATMENT DETAILS
 3/4" = 1'-0"

DESIGN OVERSIGHT SIGN OFF DATE	DESIGN	BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO.	49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT				
	DETAILS	BY R. Kotey	CHECKED DET CHK		PROJECT ENGINEER	Mario Quest		ABUTMENT DETAILS NO.3			
	QUANTITIES	BY QTY BY	CHECKED QTY CHK		POST MILE	-----					
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS				UNIT: UNIT	PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET	OF
	0	1	2	3					10/28/15	9	19

DATE PLOTTED 11/1/2018 4:06:40 PM TIME PLOTTED 4:06:40 PM USERNAME Salim




Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	59	68

65% SUBMITTAL


REGISTERED CIVIL ENGINEER DATE _____
 REGISTERED PROFESSIONAL ENGINEER
Jason H. Chou
 No. C74835
 Exp. 12/31/19
 CIVIL
 STATE OF CALIFORNIA

PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.
QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100 RANCHO CORDOVA, CA 95670 P: 916.368.9181




PLAN
 3/8" = 1'-0"

- NOTES:
- No splice allowed in #8 top and bottom cap reinforcement within each construction stage.
- Denotes closure pour
 - PS Ducts
 - Utilities



ELEVATION
 3/8" = 1'-0"



SECTION L-L
 1" = 1'-0"

Note:
 For reinforcement not shown, see "Typical Section" sheet.

DESIGN OVERSIGHT SIGN OFF DATE	DESIGN BY G. MCLAUGHLIN	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT		
	DETAILS BY R. KOTEY	CHECKED DET CHK		POST MILE -----		PIER DETAILS No.1	
	QUANTITIES BY QTY BY	CHECKED QTY CHK		CONTRACT NO.: CONTRACT			
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			UNIT: UNIT PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	REVISION DATES	SHEET 10 OF 19

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	60	68


65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE _____



PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181




- NOTES:
1. Terminate 5 bars of the 10 main column bars at the location show.
 2. All hoops shall be "Ultimate" butt splice continuous.
 3. No splices allowed in any region of main column reinforcement.
 4. Inspection tube must be no more than 1" clear of outer most hoop.
 5. Splices in main CIDH reinforcement shall be "Ultimate" butt splices and in the lower 1/3" of the shaft.




ELEVATION
3/4" = 1'-0"




SECTION M-M
3/4" = 1'-0"



SECTION P-P
3/4" = 1'-0"



SECTION N-N
3/4" = 1'-0"



SECTION Q-Q
3/4" = 1'-0"


DESIGN OVERSIGHT SIGN OFF DATE	DESIGN	BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO.	SANTA MARGARITA CREEK BRIDGE REPLACEMENT			
	DETAILS	BY R. KOTEY	CHECKED DET CHK		PROJECT ENGINEER		49C0474		
	QUANTITIES	BY QTY BY	CHECKED QTY CHK		PROJECT NUMBER & PHASE: S13201		CONTRACT NO.: CONTRACT		
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS				UNIT: UNIT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 11	OF 19

DATE PLOTTED 11/1/2018 4:06:50 PM TIME PLOTTED 4:06:50 PM USERNAME Solimb

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	61	68







65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE _____
 PLANS APPROVAL DATE _____
 THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



QUINCY ENGINEERING
 11017 COBBLEROCK DRIVE, SUITE 100
 RANCHO CORDOVA, CA 95670
 P: 916.368.9181

- NOTES:
- For Prestressing Notes, see "Superstructure Details No.1" sheet.
 - For addition reinforcement, see "Super Structure Details No.2" sheet.




DESIGN OVERSIGHT	DESIGN BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT	
SIGN OFF DATE	DETAILS BY R. KOTEY	CHECKED DET CHK		PROJECT ENGINEER Mario Quest		TYPICAL SECTION
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	QUANTITIES BY QTY BY	CHECKED QTY CHK		POST MILE -----		
ORIGINAL SCALE IN INCHES FOR REDUCED PLANS	0 1 2 3	UNIT: UNIT PROJECT NUMBER & PHASE: S13201 CONTRACT NO.: CONTRACT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 12 OF 19	

DATE PLOTTED 11/1/2018 4:06:56 PM TIME PLOTTED 4:06:56 PM USERNAME Solimb

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	62	68

65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE




PLANS APPROVAL DATE


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.




11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181



LONGITUDINAL SECTION
No Scale



EXISTING BRIDGE REMOVAL PORTION
NO SCALE



TEMPORARY RAILING
1"=1'-0"

PRESTRESSING NOTES

270 KSI Low Relaxation Strand:

	Stage 1 Left Structure	Stage 1 Right Structure	Stage 3
P_{jack}	= 2,390 kips	= 2,390 kips	= 3,820 kips
Anchor set	= $\frac{3}{8}$ in	= $\frac{3}{8}$ in	= $\frac{3}{8}$ in
Total Number of P/S ducts	= 5	= 5	= 8

Distribution of prestress force (P_{jack}) between ducts shall not exceed the ratio of 10:9.

Maximum final force variation between ducts shall not exceed 300 kips.

Concrete: $f'_c = 4500$ psi @ 28 days

$f'_{ci} = 4000$ psi @ time of stressing

Contractor shall submit elongation calculations based on initial stress at

= 0.93 times jacking stress.

$\mu = 15$ K=0.0002

Jacking shall be performed from both ends.


DESIGN OVERSIGHT	DESIGN	BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO.	SANTA MARGARITA CREEK BRIDGE REPLACEMENT
	DETAILS	BY R. KOTÉY	CHECKED DET CHK		49C0474	
	QUANTITIES	BY QTY BY	CHECKED QTY CHK		POST MILE	
SIGN OFF DATE	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			UNIT: UNIT	PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	0 1 2 3			DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 13 OF 19

DATE PLOTTED 11/1/2018 4:07:05 PM TIME PLOTTED 4:07:05 PM USERNAME Solimb

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	63	68

65% SUBMITTAL

REGISTERED CIVIL ENGINEER DATE




PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181

NOTES:


- No splices permitted in additional slab reinforcement.



TOP SLAB ADDITIONAL REINFORCEMENT (PIERS 2 & 3)
3/16" = 1'-0"


PLAN

#5 @ 12 not shown for clarity



BOTTOM SLAB ADDITIONAL REINFORCEMENT (PIERS 2 & 3)
3/16" = 1'-0"

PLAN



ANCHORAGE REINFORCEMENT DETAIL

NO SCALE

B8-5

DESIGN OVERSIGHT SIGN OFF DATE	DESIGN BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO. 49C0474	SANTA MARGARITA CREEK BRIDGE REPLACEMENT				
	DETAILS BY R. KOTEY	CHECKED DET CHK		PROJECT ENGINEER Mario Quest		SUPERSTRUCTURE DETAILS NO.2			
	QUANTITIES BY QTY BY	CHECKED QTY CHK		CONTRACT NO.: CONTRACT					
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS 0 1 2 3			UNIT: UNIT PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT	DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES 10/28/15	SHEET 14	OF 19


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	-----	64	68

65% SUBMITTAL


REGISTERED CIVIL ENGINEER DATE _____

PLANS APPROVAL DATE _____


THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.





QUINCY ENGINEERING 11017 COBBLEROCK DRIVE, SUITE 100
RANCHO CORDOVA, CA 95670
P: 916.368.9181



UTILITY OPENING DETAIL
NO SCALE



DETAIL 1
NO SCALE



UTILITY LAYOUT PLAN (B7-10 U-8)
1"=10'






- Legend:
- tc---tc--- Indicates AT&T
 - fo---(UG)--- Indicates fiber optic
 - Future----- Indicates future utility
 - GS----- Indicates gas line
 - w---w--- Indicates 18" waterline

DESIGN OVERSIGHT	DESIGN	BY J. CHOU	CHECKED DES CHK	PREPARED FOR THE SAN LUIS OBISPO DEPARTMENT OF PUBLIC WORKS	BRIDGE NO.	SANTA MARGARITA CREEK BRIDGE REPLACEMENT
	DETAILS	BY R. Kotey	CHECKED DET CHK		49C0474	
	QUANTITIES	BY QTY BY	CHECKED QTY CHK		POST MILE	
SIGN OFF DATE	ORIGINAL SCALE IN INCHES FOR REDUCED PLANS			UNIT: UNIT	PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT
DESIGN DETAIL SHEET (ENGLISH) (REV.7/16/10)	0 1 2 3			DISREGARD PRINTS BEARING EARLIER REVISION DATES	REVISION DATES	SHEET 15 OF 19

DATE PLOTTED 11/1/2018 4:07:22 PM USERNAME Solimb TIME PLOTTED 4:07:22 PM

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
5	SLO	CR	---	65	68




65% SUBMITTAL X
 REGISTERED CIVIL ENGINEER DATE _____
 REGISTERED PROFESSIONAL ENGINEER
 Jason H. Chou
 No. C74835
 Exp. 12/31/19
 CIVIL
 STATE OF CALIFORNIA
 PLANS APPROVAL DATE _____
 The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



NOTE: For details not shown, see "TYPE 732 OR 736"

NOTE: For details not shown, see "TYPE 732 OR 736"

- NOTES:
1. Post must be normal to railing.
 2. Rail tubes must be shop bent or fabricated to fit horizontal curve when radius is less than 950'.
 3. Tube expansion joints must be located in the tubes spanning deck or wall joints. Increase joint width in tubes to match expansion joint width and increase sleeve length correspondingly.
 4. Top rail tube must be continuous over not less than two posts except a short post spacing is permitted near deck or wall joints, electroliers, or other rail discontinuities as noted.
 5. See Project Plans for limits of tubular bicycle railing.



SANTA MARGARITA CREEK BRIDGE REPLACEMENT
CONCRETE BARRIER TYPE 80, 732 & 736
TUBULAR BICYCLE RAILING DETAILS


STANDARD DRAWING	FILE NO. xs16-035	APPROVAL DATE October 2014
------------------	-------------------	----------------------------

STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION	DIVISION OF ENGINEERING SERVICES	BRIDGE NO. 49C0474 POST MILE
---	----------------------------------	---------------------------------

UNIT: UNIT	PROJECT NUMBER & PHASE: S13201	CONTRACT NO.: CONTRACT
------------	--------------------------------	------------------------

NOTES:

1. 1.4-INCH DIAMETER SAMPLES WERE TAKEN USING A STANDARD PENETRATION TEST (SPT) SPLIT BARREL SAMPLER WITH AN INSIDE DIAMETER (ID) OF 1.4 INCHES AND AN OUTSIDE DIAMETER (OD) OF 2.0 INCHES.
2. 2.4-INCH DIAMETER RING SAMPLES WERE TAKEN USING A CALIFORNIA SPLIT BARREL SAMPLER WITH AN ID OF 2.4 INCHES AND AN OD OF 3.0 INCHES.
3. ALL DRIVE SAMPLES WERE DRIVEN WITH 140 LB HAMMER WITH A FALLING HEIGHT OF 30 INCHES.



PLAN
SCALE: 1"=40'

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No	TOTAL SHEETS
X	X	X		X	


REGISTERED CIVIL ENGINEER	DATE
David L. Pearson	
No. 674	
Exp. 12/31/15	
REGISTERED PROFESSIONAL ENGINEER GEOTECHNICAL STATE OF CALIFORNIA	

PLANS APPROVAL DATE _____

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.

PLOTTED: 28 Sep 2015, 11:38pm, MGriffin

ATTACHED IMAGES: Images: Draft_PlanBridgeView_9-28-15.png
ATTACHED XREFS: CAD FILE: C:\CADD\2015\20143900\SantaMargaritaCk-Bridge_9-2015_LAYOUT: 2



SANTA MARGARITA STREET

PROFILE


SCALE: 1"=10' HORIZONTAL
SCALE: 1"=5' VERTICAL

 Bright People. Right Solutions. 3880 Lemon Street, Suite 300 Riverside, CA 92501 PH. 951.801.3681 FAX. 951.682.0192 www.kleinfelder.com	PROJECT NO. 20143900	LOG OF TEST BORINGS	PLATE 2
	DRAWN: 9/2015		
	DRAWN BY: MRG		
	CHECKED BY: TD		
	FILE NAME: 20143900p2-3_LOTB-SM.dwg	SANTA MARGARITA CREEK BRIDGE EL CAMINO REAL ATACADERO, CALIFORNIA	

The information on this graphic representation has been prepared from a copy of the original and is subject to change without notice. Therefore, users are responsible for verifying the accuracy of the information presented. The user of this graphic representation is advised that the user of this graphic representation is not to be used as a substitute for a professional design or engineering drawing. The user of this graphic representation is advised that the user of this graphic representation is not to be used as a substitute for a professional design or engineering drawing.

NOTES:

1. 1.4-INCH DIAMETER SAMPLES WERE TAKEN USING A STANDARD PENETRATION TEST (SPT) SPLIT BARREL SAMPLER WITH AN INSIDE DIAMETER (ID) OF 1.4 INCHES AND AN OUTSIDE DIAMETER (OD) OF 2.0 INCHES.
2. 2.4-INCH DIAMETER RING SAMPLES WERE TAKEN USING A CALIFORNIA SPLIT BARREL SAMPLER WITH AN ID OF 2.4 INCHES AND AN OD OF 3.0 INCHES.
3. ALL DRIVE SAMPLES WERE DRIVEN WITH 140 LB HAMMER WITH A FALLING HEIGHT OF 30 INCHES.




PLAN
SCALE: 1"=40'

DIST	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No	TOTAL SHEETS
X	X	X		X	

REGISTERED CIVIL ENGINEER	DATE
David L. Pearson	
No. 674	
Exp. 12/31/15	
STATE OF CALIFORNIA	

PLANS APPROVAL DATE _____

The State of California or its officers or agents shall not be responsible for the accuracy or completeness of electronic copies of this plan sheet.



SANTA MARGARITA STREET

PROFILE

SCALE: 1"=10' HORIZONTAL
SCALE: 1"=5' VERTICAL

PROJECT NO.	20143900
DRAWN:	9/2015
DRAWN BY:	MRG
CHECKED BY:	TD
FILE NAME:	20143900p2-3_LOTB-SM.dwg

LOG OF TEST BORINGS	
SANTA MARGARITA CREEK BRIDGE EL CAMINO REAL ATACADERO, CALIFORNIA	

PLATE
3

ATTACHED IMAGES: Images: Draft_PlanBridgeView_9-28-15.png
 ATTACHED XREFS: CAD FILE: C:\CADD\2015\20143900\SantaMargaritaCk-Bridge_9-2015_LAYOUT: 3
 PLOTTED: 28 Sep 2015, 8:55am, MGriffin

Attachment B

Table B-1
Sample Location Coordinates
Santa Margarita Creek Bridge at El Camino Real

Sample ID	Latitude	Longitude
ADL-1	35.428955	-120.606147
ADL-2	35.429466	-120.606763
ADL-3	35.430306	-120.608031
ADL-4	35.428488	-120.605317
ADL-5	35.427927	-120.604961
ADL-6	35.427524	-120.604655
ADL-7	35.426210	-120.604273
ADL-8	35.426675	-120.604144

Attachment C

ANALYTICAL REPORT

Eurofins Calscience LLC
7440 Lincoln Way
Garden Grove, CA 92841
Tel: (714)895-5494

Laboratory Job ID: 570-9994-1

Client Project/Site: Santa Margarita Creek Bridge

For:

HARO Environmental
PO BOX 7002
Los Osos, California 93412

Attn: Mr. Elliot Haro



Authorized for release by:
10/23/2019 7:30:35 AM

Don Burley, Senior Project Manager
(714)895-5494
donaldburley@eurofinsus.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.



Table of Contents

Cover Page	1
Table of Contents	2
Definitions/Glossary	3
Case Narrative	4
Detection Summary	5
Client Sample Results	7
QC Sample Results	9
QC Association Summary	10
Lab Chronicle	11
Certification Summary	15
Method Summary	16
Sample Summary	17
Chain of Custody	18
Receipt Checklists	20

Definitions/Glossary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Qualifiers

Metals

Qualifier	Qualifier Description
L	A negative instrument reading had an absolute value greater than the reporting limit

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
▫	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Case Narrative

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Job ID: 570-9994-1

Laboratory: Eurofins Calscience LLC

Narrative

**Job Narrative
570-9994-1**

Comments

No additional comments.

Receipt

The samples were received on 10/12/2019 9:30 AM; the samples arrived in good condition. The temperature of the cooler at receipt was 20.1° C.

Metals

Method 6010B: The absolute response for Lead was greater than the method reporting limit (RL) in the following samples: ADL-5-0.5 (570-9994-9) and ADL-6-0.5 (570-9994-11). The instrument raw data has been manually reviewed and the result can be reported as ND.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Detection Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-1-0.5

Lab Sample ID: 570-9994-1

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	18.8		0.490	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-1-2

Lab Sample ID: 570-9994-2

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	62.2		0.503	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-2-0.5

Lab Sample ID: 570-9994-3

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	18.7		0.500	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-2-2

Lab Sample ID: 570-9994-4

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	3.30		0.498	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-3-0.5

Lab Sample ID: 570-9994-5

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	6.55		0.500	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-3-2

Lab Sample ID: 570-9994-6

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	2.98		0.505	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-4-0.5

Lab Sample ID: 570-9994-7

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	9.84		0.505	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-4-2

Lab Sample ID: 570-9994-8

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	46.4		0.498	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-5-0.5

Lab Sample ID: 570-9994-9

No Detections.

Client Sample ID: ADL-5-1

Lab Sample ID: 570-9994-10

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	0.598		0.500	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-6-0.5

Lab Sample ID: 570-9994-11

No Detections.

Client Sample ID: ADL-6-1

Lab Sample ID: 570-9994-12

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	1.26		0.498	mg/Kg	1		6010B	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Calscience LLC

Detection Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-7-0.5

Lab Sample ID: 570-9994-13

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	289		0.498	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-7-2

Lab Sample ID: 570-9994-14

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	71.6		0.498	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-8-0.5

Lab Sample ID: 570-9994-15

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	14.6		0.505	mg/Kg	1		6010B	Total/NA

Client Sample ID: ADL-8-2

Lab Sample ID: 570-9994-16

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	18.9		0.500	mg/Kg	1		6010B	Total/NA

This Detection Summary does not include radiochemical test results.

Eurofins Calscience LLC

Client Sample Results

Client: HARO Environmental
 Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Method: 6010B - Metals (ICP)

Client Sample ID: ADL-1-0.5						Lab Sample ID: 570-9994-1			
Date Collected: 10/11/19 10:45						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	18.8		0.490	mg/Kg		10/16/19 19:34	10/19/19 00:45	1	
Client Sample ID: ADL-1-2						Lab Sample ID: 570-9994-2			
Date Collected: 10/11/19 10:55						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	62.2		0.503	mg/Kg		10/16/19 19:34	10/19/19 01:34	1	
Client Sample ID: ADL-2-0.5						Lab Sample ID: 570-9994-3			
Date Collected: 10/11/19 11:05						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	18.7		0.500	mg/Kg		10/16/19 19:34	10/19/19 01:36	1	
Client Sample ID: ADL-2-2						Lab Sample ID: 570-9994-4			
Date Collected: 10/11/19 11:15						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	3.30		0.498	mg/Kg		10/16/19 19:34	10/19/19 00:51	1	
Client Sample ID: ADL-3-0.5						Lab Sample ID: 570-9994-5			
Date Collected: 10/11/19 11:25						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	6.55		0.500	mg/Kg		10/16/19 19:34	10/19/19 01:01	1	
Client Sample ID: ADL-3-2						Lab Sample ID: 570-9994-6			
Date Collected: 10/11/19 11:28						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	2.98		0.505	mg/Kg		10/16/19 19:34	10/19/19 01:03	1	
Client Sample ID: ADL-4-0.5						Lab Sample ID: 570-9994-7			
Date Collected: 10/11/19 11:33						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	9.84		0.505	mg/Kg		10/16/19 19:34	10/19/19 01:05	1	
Client Sample ID: ADL-4-2						Lab Sample ID: 570-9994-8			
Date Collected: 10/11/19 11:37						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	46.4		0.498	mg/Kg		10/16/19 19:34	10/19/19 01:07	1	
Client Sample ID: ADL-5-0.5						Lab Sample ID: 570-9994-9			
Date Collected: 10/11/19 11:44						Matrix: Solid			
Date Received: 10/12/19 09:30									
Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac	
Lead	ND	L	0.503	mg/Kg		10/16/19 19:34	10/19/19 01:09	1	

Client Sample Results

Client: HARO Environmental
 Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Method: 6010B - Metals (ICP)

Client Sample ID: ADL-5-1
Date Collected: 10/11/19 11:55
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-10
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	0.598		0.500	mg/Kg		10/16/19 19:34	10/19/19 01:11	1

Client Sample ID: ADL-6-0.5
Date Collected: 10/11/19 12:08
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-11
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND	L	0.495	mg/Kg		10/16/19 19:34	10/19/19 01:13	1

Client Sample ID: ADL-6-1
Date Collected: 10/11/19 12:16
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-12
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	1.26		0.498	mg/Kg		10/16/19 19:34	10/19/19 01:16	1

Client Sample ID: ADL-7-0.5
Date Collected: 10/11/19 12:37
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-13
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	289		0.498	mg/Kg		10/16/19 19:34	10/19/19 01:18	1

Client Sample ID: ADL-7-2
Date Collected: 10/11/19 12:44
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-14
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	71.6		0.498	mg/Kg		10/16/19 19:34	10/19/19 01:20	1

Client Sample ID: ADL-8-0.5
Date Collected: 10/11/19 12:23
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-15
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	14.6		0.505	mg/Kg		10/16/19 19:34	10/19/19 01:29	1

Client Sample ID: ADL-8-2
Date Collected: 10/11/19 12:30
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-16
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	18.9		0.500	mg/Kg		10/16/19 19:34	10/19/19 01:32	1

QC Sample Results

Client: HARO Environmental
 Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Method: 6010B - Metals (ICP)

Lab Sample ID: MB 570-26499/1-A
Matrix: Solid
Analysis Batch: 26686

Client Sample ID: Method Blank
Prep Type: Total/NA
Prep Batch: 26499

Analyte	MB Result	MB Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND		0.505	mg/Kg		10/16/19 19:34	10/17/19 13:20	1

Lab Sample ID: LCS 570-26499/2-A
Matrix: Solid
Analysis Batch: 26686

Client Sample ID: Lab Control Sample
Prep Type: Total/NA
Prep Batch: 26499

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	24.4	27.40		mg/Kg		112	80 - 120

Lab Sample ID: LCSD 570-26499/3-A
Matrix: Solid
Analysis Batch: 26686

Client Sample ID: Lab Control Sample Dup
Prep Type: Total/NA
Prep Batch: 26499

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Lead	25.0	28.04		mg/Kg		112	80 - 120	2	20

Lab Sample ID: 570-9994-1 MS
Matrix: Solid
Analysis Batch: 27150

Client Sample ID: ADL-1-0.5
Prep Type: Total/NA
Prep Batch: 26499

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	18.8		24.6	39.39		mg/Kg		83	75 - 125

Lab Sample ID: 570-9994-1 MSD
Matrix: Solid
Analysis Batch: 27150

Client Sample ID: ADL-1-0.5
Prep Type: Total/NA
Prep Batch: 26499

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Lead	18.8		25.6	40.85		mg/Kg		86	75 - 125	4	20

QC Association Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Metals

Prep Batch: 26499

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-1	ADL-1-0.5	Total/NA	Solid	3050B	
570-9994-2	ADL-1-2	Total/NA	Solid	3050B	
570-9994-3	ADL-2-0.5	Total/NA	Solid	3050B	
570-9994-4	ADL-2-2	Total/NA	Solid	3050B	
570-9994-5	ADL-3-0.5	Total/NA	Solid	3050B	
570-9994-6	ADL-3-2	Total/NA	Solid	3050B	
570-9994-7	ADL-4-0.5	Total/NA	Solid	3050B	
570-9994-8	ADL-4-2	Total/NA	Solid	3050B	
570-9994-9	ADL-5-0.5	Total/NA	Solid	3050B	
570-9994-10	ADL-5-1	Total/NA	Solid	3050B	
570-9994-11	ADL-6-0.5	Total/NA	Solid	3050B	
570-9994-12	ADL-6-1	Total/NA	Solid	3050B	
570-9994-13	ADL-7-0.5	Total/NA	Solid	3050B	
570-9994-14	ADL-7-2	Total/NA	Solid	3050B	
570-9994-15	ADL-8-0.5	Total/NA	Solid	3050B	
570-9994-16	ADL-8-2	Total/NA	Solid	3050B	
MB 570-26499/1-A	Method Blank	Total/NA	Solid	3050B	
LCS 570-26499/2-A	Lab Control Sample	Total/NA	Solid	3050B	
LCSD 570-26499/3-A	Lab Control Sample Dup	Total/NA	Solid	3050B	
570-9994-1 MS	ADL-1-0.5	Total/NA	Solid	3050B	
570-9994-1 MSD	ADL-1-0.5	Total/NA	Solid	3050B	

Analysis Batch: 26686

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 570-26499/1-A	Method Blank	Total/NA	Solid	6010B	26499
LCS 570-26499/2-A	Lab Control Sample	Total/NA	Solid	6010B	26499
LCSD 570-26499/3-A	Lab Control Sample Dup	Total/NA	Solid	6010B	26499

Analysis Batch: 27150

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-1	ADL-1-0.5	Total/NA	Solid	6010B	26499
570-9994-2	ADL-1-2	Total/NA	Solid	6010B	26499
570-9994-3	ADL-2-0.5	Total/NA	Solid	6010B	26499
570-9994-4	ADL-2-2	Total/NA	Solid	6010B	26499
570-9994-5	ADL-3-0.5	Total/NA	Solid	6010B	26499
570-9994-6	ADL-3-2	Total/NA	Solid	6010B	26499
570-9994-7	ADL-4-0.5	Total/NA	Solid	6010B	26499
570-9994-8	ADL-4-2	Total/NA	Solid	6010B	26499
570-9994-9	ADL-5-0.5	Total/NA	Solid	6010B	26499
570-9994-10	ADL-5-1	Total/NA	Solid	6010B	26499
570-9994-11	ADL-6-0.5	Total/NA	Solid	6010B	26499
570-9994-12	ADL-6-1	Total/NA	Solid	6010B	26499
570-9994-13	ADL-7-0.5	Total/NA	Solid	6010B	26499
570-9994-14	ADL-7-2	Total/NA	Solid	6010B	26499
570-9994-15	ADL-8-0.5	Total/NA	Solid	6010B	26499
570-9994-16	ADL-8-2	Total/NA	Solid	6010B	26499
570-9994-1 MS	ADL-1-0.5	Total/NA	Solid	6010B	26499
570-9994-1 MSD	ADL-1-0.5	Total/NA	Solid	6010B	26499

Lab Chronicle

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-1-0.5

Date Collected: 10/11/19 10:45

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-1

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.04 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 00:45	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-1-2

Date Collected: 10/11/19 10:55

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-2

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			1.99 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:34	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-2-0.5

Date Collected: 10/11/19 11:05

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-3

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.00 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:36	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-2-2

Date Collected: 10/11/19 11:15

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-4

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 00:51	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-3-0.5

Date Collected: 10/11/19 11:25

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-5

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.00 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:01	OYW3	ECL 1
Instrument ID: ICP8										

Lab Chronicle

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-3-2

Date Collected: 10/11/19 11:28

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-6

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			1.98 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:03	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-4-0.5

Date Collected: 10/11/19 11:33

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-7

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			1.98 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:05	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-4-2

Date Collected: 10/11/19 11:37

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-8

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:07	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-5-0.5

Date Collected: 10/11/19 11:44

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-9

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			1.99 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:09	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-5-1

Date Collected: 10/11/19 11:55

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-10

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.00 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:11	OYW3	ECL 1
Instrument ID: ICP8										

Lab Chronicle

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-6-0.5

Date Collected: 10/11/19 12:08

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-11

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.02 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:13	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-6-1

Date Collected: 10/11/19 12:16

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-12

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:16	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-7-0.5

Date Collected: 10/11/19 12:37

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-13

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:18	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-7-2

Date Collected: 10/11/19 12:44

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-14

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.01 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:20	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-8-0.5

Date Collected: 10/11/19 12:23

Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-15

Matrix: Solid

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			1.98 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:29	OYW3	ECL 1
Instrument ID: ICP8										

Lab Chronicle

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Client Sample ID: ADL-8-2

Lab Sample ID: 570-9994-16

Date Collected: 10/11/19 12:30

Matrix: Solid

Date Received: 10/12/19 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Prep	3050B			2.00 g	100 mL	26499	10/16/19 19:34	MD3A	ECL 1
Total/NA	Analysis	6010B		1			27150	10/19/19 01:32	OYW3	ECL 1

Instrument ID: ICP8

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Accreditation/Certification Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Laboratory: Eurofins Calscience LLC

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arizona	State	AZ0781	03-13-20
California	SCAQMD LAP	17LA0919	11-30-19
California	State	2944	09-29-20
Guam	State	19-004R	10-31-19
Hawaii	State	<cert No.>	07-02-20
Nevada	State	CA00111	07-31-20
Oregon	NELAP	CA300001	01-29-20

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Method Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Method	Method Description	Protocol	Laboratory
6010B	Metals (ICP)	SW846	ECL 1
3050B	Preparation, Metals	SW846	ECL 1

Protocol References:

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494



Sample Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
570-9994-1	ADL-1-0.5	Solid	10/11/19 10:45	10/12/19 09:30	
570-9994-2	ADL-1-2	Solid	10/11/19 10:55	10/12/19 09:30	
570-9994-3	ADL-2-0.5	Solid	10/11/19 11:05	10/12/19 09:30	
570-9994-4	ADL-2-2	Solid	10/11/19 11:15	10/12/19 09:30	
570-9994-5	ADL-3-0.5	Solid	10/11/19 11:25	10/12/19 09:30	
570-9994-6	ADL-3-2	Solid	10/11/19 11:28	10/12/19 09:30	
570-9994-7	ADL-4-0.5	Solid	10/11/19 11:33	10/12/19 09:30	
570-9994-8	ADL-4-2	Solid	10/11/19 11:37	10/12/19 09:30	
570-9994-9	ADL-5-0.5	Solid	10/11/19 11:44	10/12/19 09:30	
570-9994-10	ADL-5-1	Solid	10/11/19 11:55	10/12/19 09:30	
570-9994-11	ADL-6-0.5	Solid	10/11/19 12:08	10/12/19 09:30	
570-9994-12	ADL-6-1	Solid	10/11/19 12:16	10/12/19 09:30	
570-9994-13	ADL-7-0.5	Solid	10/11/19 12:37	10/12/19 09:30	
570-9994-14	ADL-7-2	Solid	10/11/19 12:44	10/12/19 09:30	
570-9994-15	ADL-8-0.5	Solid	10/11/19 12:23	10/12/19 09:30	
570-9994-16	ADL-8-2	Solid	10/11/19 12:30	10/12/19 09:30	



eurofins

Calscience

9994

CHAIN OF CUSTODY RECORD

DATE: 10/11/19

PAGE: 1 OF 2



570-9994 Chain of Custody

LABORATORY CLIENT: HARGO ENVIRONMENTAL, INC.

7440 Lincoln Way, Garden Grove, CA 92841-1427 • (714) 895-5494

For courier service / sample drop off information, contact us26_sales@eurofins.com or call us.

CLIENT PROJECT NAME / NUMBER: SANTA MARGARITA CREEK BRIDGE

PROJECT CONTACT: ELIOT HARGO

LABORATORY CLIENT: HARGO ENVIRONMENTAL, INC.

ADDRESS: PO BOX 7007

CITY: LOS OSOS

STATE: CA

ZIP: 93402

TEL: 805.264.4403

E-MAIL: eliot.hargo@hargoenv.com

TURNAROUND TIME (Rush surcharges may apply to any TAT not "STANDARD")

SAME DAY 24 HR 48 HR 72 HR 5 DAYS STANDARD

COELT EDF

GLOBAL ID:

SPECIAL INSTRUCTIONS: NOID STUC / TCIP RENDIN - TOTAL LEAD RESULTS

CLIENT PROJECT NAME / NUMBER: SANTA MARGARITA CREEK BRIDGE

PROJECT CONTACT: ELIOT HARGO

LABORATORY CLIENT: HARGO ENVIRONMENTAL, INC.

ADDRESS: PO BOX 7007

CITY: LOS OSOS

STATE: CA

ZIP: 93402

TEL: 805.264.4403

E-MAIL: eliot.hargo@hargoenv.com

TURNAROUND TIME (Rush surcharges may apply to any TAT not "STANDARD")

SAME DAY 24 HR 48 HR 72 HR 5 DAYS STANDARD

COELT EDF

GLOBAL ID:

SPECIAL INSTRUCTIONS: NOID STUC / TCIP RENDIN - TOTAL LEAD RESULTS

LAB USE ONLY	SAMPLE ID	SAMPLING		MATRIX	NO. OF CONT.	LOG CODE:	
		DATE	TIME			Unpreserved	Preserved
1	ADL-1-0.5	10/11/19	1046	SL	1	X	
2	ADL-2-0.5		1055				
3	ADL-2-0.5		1105				
4	ADL-2-2		1115				
5	ADL-3-0.5		1125				
6	ADL-3-2		1128				
7	ADL-4-0.5		1133				
8	ADL-4-2		1137				
9	ADL-5-0.5		1144				
10	ADL-5-1		1155				

REQUESTED ANALYSES

Please check box or fill in blank as needed.

TPH	
TPH □ C6-C38 □ C6-C44	
□ TPH(g) □ GRO	
□ TPH(d) □ DRO	
BTEX / MTBE □ 8260 □	
VOCs (8260)	
Oxygenates (8260)	
Prep (5035) □ En Core □ Terra Core	
SVOCs (8270)	
Pesticides (8081)	
PCBs (8082)	
PAHs □ 8270 □ 8270 SIM	
T22 Metals □ 6010/747X □ 6020/747X	
Cr(VI) □ 7196 □ 7199 □ 218.6	

Received by: (Signature/Affiliation) *[Signature]* Date: 10/11/19 Time: 1530

Received by: (Signature/Affiliation) *[Signature]* Date: 10/12/19 Time: 9:30

Received by: (Signature/Affiliation) *[Signature]* Date: _____ Time: _____



10/10/10.1 sc6

Login Sample Receipt Checklist

Client: HARO Environmental

Job Number: 570-9994-1

Login Number: 9994

List Source: Eurofins Calscience

List Number: 1

Creator: Ramos, Maribel

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	False	Thermal preservation not required.
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

ANALYTICAL REPORT

Eurofins Calscience LLC
7440 Lincoln Way
Garden Grove, CA 92841
Tel: (714)895-5494

Laboratory Job ID: 570-9994-2

Client Project/Site: Santa Margarita Creek Bridge

For:

HARO Environmental
PO BOX 7002
Los Osos, California 93412

Attn: Mr. Elliot Haro



Authorized for release by:
10/29/2019 2:33:42 PM

Don Burley, Senior Project Manager
(714)895-5494
donaldburley@eurofinsus.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.



Table of Contents

Cover Page	1
Table of Contents	2
Definitions/Glossary	3
Case Narrative	4
Detection Summary	5
Client Sample Results	6
QC Sample Results	8
QC Association Summary	10
Lab Chronicle	12
Certification Summary	13
Method Summary	14
Sample Summary	15
Chain of Custody	16
Receipt Checklists	18

Definitions/Glossary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains No Free Liquid
DER	Duplicate Error Ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL	Detection Limit (DoD/DOE)
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision Level Concentration (Radiochemistry)
EDL	Estimated Detection Limit (Dioxin)
LOD	Limit of Detection (DoD/DOE)
LOQ	Limit of Quantitation (DoD/DOE)
MDA	Minimum Detectable Activity (Radiochemistry)
MDC	Minimum Detectable Concentration (Radiochemistry)
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not Detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative Error Ratio (Radiochemistry)
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Case Narrative

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Job ID: 570-9994-2

Laboratory: Eurofins Calscience LLC

Narrative

Job Narrative
570-9994-2

Comments

No additional comments.

Receipt

The samples were received on 10/12/2019 9:30 AM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 20.1° C.

Metals

No analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Detection Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Client Sample ID: ADL-1-2

Lab Sample ID: 570-9994-2

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	0.693		0.500	mg/L	1		6010B	STLC Citrate

Client Sample ID: ADL-7-0.5

Lab Sample ID: 570-9994-13

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	2.20		0.500	mg/L	1		6010B	STLC Citrate

Client Sample ID: ADL-7-2

Lab Sample ID: 570-9994-14

Analyte	Result	Qualifier	RL	Unit	Dil Fac	D	Method	Prep Type
Lead	4.31		0.500	mg/L	1		6010B	STLC Citrate

This Detection Summary does not include radiochemical test results.

Eurofins Calscience LLC

Client Sample Results

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Method: 6010B - Metals (ICP) - TCLP

Client Sample ID: ADL-7-0.5
Date Collected: 10/11/19 12:37
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-13
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND		0.500	mg/L		10/24/19 14:30	10/25/19 22:14	1

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Client Sample Results

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Method: 6010B - Metals (ICP) - STLC Citrate

Client Sample ID: ADL-1-2
Date Collected: 10/11/19 10:55
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-2
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	0.693		0.500	mg/L		10/25/19 17:30	10/28/19 14:15	1

Client Sample ID: ADL-7-0.5
Date Collected: 10/11/19 12:37
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-13
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	2.20		0.500	mg/L		10/25/19 17:30	10/26/19 21:58	1

Client Sample ID: ADL-7-2
Date Collected: 10/11/19 12:44
Date Received: 10/12/19 09:30

Lab Sample ID: 570-9994-14
Matrix: Solid

Analyte	Result	Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	4.31		0.500	mg/L		10/25/19 17:30	10/28/19 13:45	1

QC Sample Results

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Method: 6010B - Metals (ICP)

Lab Sample ID: LB 570-28164/1-B
Matrix: Solid
Analysis Batch: 28800

Client Sample ID: Method Blank
Prep Type: TCLP
Prep Batch: 28381

Analyte	LB Result	LB Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND		0.500	mg/L		10/24/19 14:30	10/25/19 21:58	1

Lab Sample ID: LCS 570-28164/2-B
Matrix: Solid
Analysis Batch: 28800

Client Sample ID: Lab Control Sample
Prep Type: TCLP
Prep Batch: 28381

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	5.00	5.098		mg/L		102	80 - 120

Lab Sample ID: LCSD 570-28164/3-B
Matrix: Solid
Analysis Batch: 28800

Client Sample ID: Lab Control Sample Dup
Prep Type: TCLP
Prep Batch: 28381

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	5.00	5.150		mg/L		103	80 - 120	1	20

Lab Sample ID: 570-9994-13 MS
Matrix: Solid
Analysis Batch: 28800

Client Sample ID: ADL-7-0.5
Prep Type: TCLP
Prep Batch: 28381

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	ND		5.00	5.398		mg/L		108	84 - 120

Lab Sample ID: 570-9994-13 MSD
Matrix: Solid
Analysis Batch: 28800

Client Sample ID: ADL-7-0.5
Prep Type: TCLP
Prep Batch: 28381

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	ND		5.00	5.452		mg/L		109	84 - 120	1	7

Lab Sample ID: LB4 570-28135/1-B
Matrix: Solid
Analysis Batch: 29060

Client Sample ID: Method Blank
Prep Type: STLC Citrate
Prep Batch: 28709

Analyte	LB4 Result	LB4 Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND		0.500	mg/L		10/25/19 17:30	10/28/19 12:59	1

Lab Sample ID: LCS 570-28135/2-B
Matrix: Solid
Analysis Batch: 29060

Client Sample ID: Lab Control Sample
Prep Type: STLC Citrate
Prep Batch: 28709

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	5.00	5.117		mg/L		102	80 - 120

Lab Sample ID: LCSD 570-28135/3-B
Matrix: Solid
Analysis Batch: 29060

Client Sample ID: Lab Control Sample Dup
Prep Type: STLC Citrate
Prep Batch: 28709

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	5.00	5.101		mg/L		102	80 - 120	0	20

Eurofins Calscience LLC

QC Sample Results

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Method: 6010B - Metals (ICP)

Lab Sample ID: 570-9223-A-8-F MS
Matrix: Solid
Analysis Batch: 29060

Client Sample ID: Matrix Spike
Prep Type: STLC Citrate
Prep Batch: 28709

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	ND		5.00	5.651		mg/L		104	84 - 120

Lab Sample ID: 570-9223-A-8-G MSD
Matrix: Solid
Analysis Batch: 29060

Client Sample ID: Matrix Spike Duplicate
Prep Type: STLC Citrate
Prep Batch: 28709

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	ND		5.00	5.818		mg/L		107	84 - 120	3	7

Lab Sample ID: LB4 570-28135/1-C
Matrix: Solid
Analysis Batch: 29038

Client Sample ID: Method Blank
Prep Type: STLC Citrate
Prep Batch: 28722

Analyte	LB4 Result	LB4 Qualifier	RL	Unit	D	Prepared	Analyzed	Dil Fac
Lead	ND		0.500	mg/L		10/25/19 17:30	10/26/19 21:27	1

Lab Sample ID: LCS 570-28135/2-C
Matrix: Solid
Analysis Batch: 29038

Client Sample ID: Lab Control Sample
Prep Type: STLC Citrate
Prep Batch: 28722

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	5.00	5.211		mg/L		104	80 - 120

Lab Sample ID: LCSD 570-28135/3-C
Matrix: Solid
Analysis Batch: 29038

Client Sample ID: Lab Control Sample Dup
Prep Type: STLC Citrate
Prep Batch: 28722

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	5.00	5.017		mg/L		100	80 - 120	4	20

Lab Sample ID: 570-9696-A-37-F MS
Matrix: Solid
Analysis Batch: 29038

Client Sample ID: Matrix Spike
Prep Type: STLC Citrate
Prep Batch: 28722

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Lead	7.74		5.00	13.04		mg/L		106	84 - 120

Lab Sample ID: 570-9696-A-37-G MSD
Matrix: Solid
Analysis Batch: 29038

Client Sample ID: Matrix Spike Duplicate
Prep Type: STLC Citrate
Prep Batch: 28722

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	Limit
Lead	7.74		5.00	13.07		mg/L		107	84 - 120	0	7

QC Association Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Metals

Leach Batch: 28135

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-2	ADL-1-2	STLC Citrate	Solid	CA WET Citrate	
570-9994-13	ADL-7-0.5	STLC Citrate	Solid	CA WET Citrate	
570-9994-14	ADL-7-2	STLC Citrate	Solid	CA WET Citrate	
LB4 570-28135/1-B	Method Blank	STLC Citrate	Solid	CA WET Citrate	
LB4 570-28135/1-C	Method Blank	STLC Citrate	Solid	CA WET Citrate	
LCS 570-28135/2-B	Lab Control Sample	STLC Citrate	Solid	CA WET Citrate	
LCS 570-28135/2-C	Lab Control Sample	STLC Citrate	Solid	CA WET Citrate	
LCSD 570-28135/3-B	Lab Control Sample Dup	STLC Citrate	Solid	CA WET Citrate	
LCSD 570-28135/3-C	Lab Control Sample Dup	STLC Citrate	Solid	CA WET Citrate	
570-9223-A-8-F MS	Matrix Spike	STLC Citrate	Solid	CA WET Citrate	
570-9223-A-8-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	CA WET Citrate	
570-9696-A-37-F MS	Matrix Spike	STLC Citrate	Solid	CA WET Citrate	
570-9696-A-37-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	CA WET Citrate	

Leach Batch: 28164

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-13	ADL-7-0.5	TCLP	Solid	1311	
LB 570-28164/1-B	Method Blank	TCLP	Solid	1311	
LCS 570-28164/2-B	Lab Control Sample	TCLP	Solid	1311	
LCSD 570-28164/3-B	Lab Control Sample Dup	TCLP	Solid	1311	
570-9994-13 MS	ADL-7-0.5	TCLP	Solid	1311	
570-9994-13 MSD	ADL-7-0.5	TCLP	Solid	1311	

Prep Batch: 28381

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-13	ADL-7-0.5	TCLP	Solid	3010A	28164
LB 570-28164/1-B	Method Blank	TCLP	Solid	3010A	28164
LCS 570-28164/2-B	Lab Control Sample	TCLP	Solid	3010A	28164
LCSD 570-28164/3-B	Lab Control Sample Dup	TCLP	Solid	3010A	28164
570-9994-13 MS	ADL-7-0.5	TCLP	Solid	3010A	28164
570-9994-13 MSD	ADL-7-0.5	TCLP	Solid	3010A	28164

Prep Batch: 28709

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-2	ADL-1-2	STLC Citrate	Solid	Dilution	28135
570-9994-14	ADL-7-2	STLC Citrate	Solid	Dilution	28135
LB4 570-28135/1-B	Method Blank	STLC Citrate	Solid	Dilution	28135
LCS 570-28135/2-B	Lab Control Sample	STLC Citrate	Solid	Dilution	28135
LCSD 570-28135/3-B	Lab Control Sample Dup	STLC Citrate	Solid	Dilution	28135
570-9223-A-8-F MS	Matrix Spike	STLC Citrate	Solid	Dilution	28135
570-9223-A-8-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	Dilution	28135

Prep Batch: 28722

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-13	ADL-7-0.5	STLC Citrate	Solid	Dilution	28135
LB4 570-28135/1-C	Method Blank	STLC Citrate	Solid	Dilution	28135
LCS 570-28135/2-C	Lab Control Sample	STLC Citrate	Solid	Dilution	28135
LCSD 570-28135/3-C	Lab Control Sample Dup	STLC Citrate	Solid	Dilution	28135
570-9696-A-37-F MS	Matrix Spike	STLC Citrate	Solid	Dilution	28135
570-9696-A-37-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	Dilution	28135

Eurofins Calscience LLC

QC Association Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Metals

Analysis Batch: 28800

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-13	ADL-7-0.5	TCLP	Solid	6010B	28381
LB 570-28164/1-B	Method Blank	TCLP	Solid	6010B	28381
LCS 570-28164/2-B	Lab Control Sample	TCLP	Solid	6010B	28381
LCSD 570-28164/3-B	Lab Control Sample Dup	TCLP	Solid	6010B	28381
570-9994-13 MS	ADL-7-0.5	TCLP	Solid	6010B	28381
570-9994-13 MSD	ADL-7-0.5	TCLP	Solid	6010B	28381

Analysis Batch: 29038

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-13	ADL-7-0.5	STLC Citrate	Solid	6010B	28722
LB4 570-28135/1-C	Method Blank	STLC Citrate	Solid	6010B	28722
LCS 570-28135/2-C	Lab Control Sample	STLC Citrate	Solid	6010B	28722
LCSD 570-28135/3-C	Lab Control Sample Dup	STLC Citrate	Solid	6010B	28722
570-9696-A-37-F MS	Matrix Spike	STLC Citrate	Solid	6010B	28722
570-9696-A-37-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	6010B	28722

Analysis Batch: 29060

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
570-9994-2	ADL-1-2	STLC Citrate	Solid	6010B	28709
570-9994-14	ADL-7-2	STLC Citrate	Solid	6010B	28709
LB4 570-28135/1-B	Method Blank	STLC Citrate	Solid	6010B	28709
LCS 570-28135/2-B	Lab Control Sample	STLC Citrate	Solid	6010B	28709
LCSD 570-28135/3-B	Lab Control Sample Dup	STLC Citrate	Solid	6010B	28709
570-9223-A-8-F MS	Matrix Spike	STLC Citrate	Solid	6010B	28709
570-9223-A-8-G MSD	Matrix Spike Duplicate	STLC Citrate	Solid	6010B	28709

Lab Chronicle

Client: HARO Environmental
 Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Client Sample ID: ADL-1-2

Lab Sample ID: 570-9994-2

Date Collected: 10/11/19 10:55

Matrix: Solid

Date Received: 10/12/19 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
STLC Citrate	Leach	CA WET Citrate			50.01 g	500 mL	28135	10/23/19 17:00	UY73	ECL 3
STLC Citrate	Prep	Dilution			5 mL	50 mL	28709	10/25/19 17:30	UY73	ECL 1
STLC Citrate	Analysis	6010B		1			29060	10/28/19 14:15	ULPF	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-7-0.5

Lab Sample ID: 570-9994-13

Date Collected: 10/11/19 12:37

Matrix: Solid

Date Received: 10/12/19 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
STLC Citrate	Leach	CA WET Citrate			50.05 g	500 mL	28135	10/23/19 17:00	UY73	ECL 3
STLC Citrate	Prep	Dilution			5 mL	50 mL	28722	10/25/19 17:30	UY73	ECL 1
STLC Citrate	Analysis	6010B		1			29038	10/26/19 21:58	ULPF	ECL 1
Instrument ID: ICP8										
TCLP	Leach	1311			100.05 g	2000 mL	28164	10/23/19 19:00	UY73	ECL 3
TCLP	Prep	3010A			5 mL	50 mL	28381	10/24/19 14:30	UY73	ECL 1
TCLP	Analysis	6010B		1			28800	10/25/19 22:14	OYW3	ECL 1
Instrument ID: ICP8										

Client Sample ID: ADL-7-2

Lab Sample ID: 570-9994-14

Date Collected: 10/11/19 12:44

Matrix: Solid

Date Received: 10/12/19 09:30

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
STLC Citrate	Leach	CA WET Citrate			50.02 g	500 mL	28135	10/23/19 17:00	UY73	ECL 3
STLC Citrate	Prep	Dilution			5 mL	50 mL	28709	10/25/19 17:30	UY73	ECL 1
STLC Citrate	Analysis	6010B		1			29060	10/28/19 13:45	ULPF	ECL 1
Instrument ID: ICP8										

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

ECL 3 = Eurofins Calscience LLC Knott, 11380 Knott Street, Garden Grove, CA 92841, TEL (714)895-5494

Accreditation/Certification Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Laboratory: Eurofins Calscience LLC

All accreditations/certifications held by this laboratory are listed. Not all accreditations/certifications are applicable to this report.

Authority	Program	Identification Number	Expiration Date
Arizona	State	AZ0781	03-13-20
California	SCAQMD LAP	17LA0919	11-30-19
California	State	2944	09-29-20
Guam	State	19-004R	10-31-19
Hawaii	State	<cert No.>	07-02-20
Nevada	State	CA00111	07-31-20
Oregon	NELAP	CA300001	01-29-20

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14

Method Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Method	Method Description	Protocol	Laboratory
6010B	Metals (ICP)	SW846	ECL 1
1311	TCLP Extraction	SW846	ECL 3
3010A	Preparation, Total Metals	SW846	ECL 1
CA WET Citrate	California - Waste Extraction Test with Citrate Leach	CA-WET	ECL 3
Dilution	Preparation / Dilution Process	None	ECL 1

Protocol References:

CA-WET = California Waste Extraction Test, from Title 22

None = None

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

ECL 1 = Eurofins Calscience LLC Lincoln, 7440 Lincoln Way, Garden Grove, CA 92841, TEL (714)895-5494

ECL 3 = Eurofins Calscience LLC Knott, 11380 Knott Street, Garden Grove, CA 92841, TEL (714)895-5494


Sample Summary

Client: HARO Environmental
Project/Site: Santa Margarita Creek Bridge

Job ID: 570-9994-2

Lab Sample ID	Client Sample ID	Matrix	Collected	Received	Asset ID
570-9994-2	ADL-1-2	Solid	10/11/19 10:55	10/12/19 09:30	
570-9994-13	ADL-7-0.5	Solid	10/11/19 12:37	10/12/19 09:30	
570-9994-14	ADL-7-2	Solid	10/11/19 12:44	10/12/19 09:30	

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14



Calscience

7440 Lincoln Way, Garden Grove, CA 92841-1427 • (714) 895-5494
For courier service / sample drop off information, contact us26_sales@eurofins.com or call us.

LABORATORY CLIENT:

HABO ENVIRONMENTAL, INC.

ADDRESS: PO Box 7007

CITY: LOS ANGELES

STATE: CA

ZIP: 90002

E-MAIL: info@habo.com

LABORATORY CLIENT: SANTA MARGARITA CREEK BRIDGE

CLIENT PROJECT NAME / NUMBER:

SANTA MARGARITA CREEK BRIDGE

PROJECT CONTACT:

ELIOT HARO

SAMPLER(S): (PRINT)

ELIOT HARO

P.O. NO.:

7

DATE: 10/11/19

PAGE: 1 OF 2

570-9994 Chain of Custody



9994

CHAIN OF CUSTODY RECORD

REQUESTED ANALYSES

Please check box or fill in blank as needed.

TPH	
TPH □ C6-C38 □ C6-C44	
□ TPH(g) □ GRO	
□ TPH(d) □ DRO	
BTEX / MTBE □ 8260 □	
VOCs (8260)	
Oxygenates (8260)	
Prep (5035) □ En Core □ Terra Core	
SVOCs (8270)	
Pesticides (8081)	
PCBs (8082)	
PAHs □ 8270 □ 8270 SIM	
T22 Metals □ 6010/747X □ 6020/747X	
Cr(VI) □ 7196 □ 7199 □ 218.6	

LAB USE ONLY	SAMPLE ID	SAMPLING		MATRIX	NO. OF CONT.	LOG CODE:	
		DATE	TIME			Unpreserved	Preserved
1	ADL-1-0.5	10/11/19	1046	SL	1	X	
2	ADL-2-0.5		1055				
3	ADL-2-0.5		1105				
4	ADL-2-2		1115				
5	ADL-3-0.5		1125				
6	ADL-3-2		1128				
7	ADL-4-0.5		1133				
8	ADL-4-2		1137				
9	ADL-5-0.5		1144				
10	ADL-5-1		1155				

Field Filtered

Received by: (Signature/Affiliation) *[Signature]* Date: 10/11/19 Time: 1530

Received by: (Signature/Affiliation) *[Signature]* Date: 10/12/19 Time: 9:30

Received by: (Signature/Affiliation) *[Signature]* Date: _____ Time: _____

NOID STUC / TCIP RENDIN-
TOTAL LEAD RESULTS

Relinquished by: (Signature) *[Signature]*
Relinquished by: (Signature) *[Signature]*
Relinquished by: (Signature) *[Signature]*



101.0/10.1 SCO

Login Sample Receipt Checklist

Client: HARO Environmental

Job Number: 570-9994-2

Login Number: 9994

List Source: Eurofins Calscience

List Number: 1

Creator: Ramos, Maribel

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	False	Thermal preservation not required.
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time (excluding tests with immediate HTs)	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <math><6\text{mm}</math> (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Attachment D

	A	B	C	D	E	F	G	H	I	J	K	L
1	UCL Statistics for Data Sets with Non-Detects											
2												
3	User Selected Options											
4	Date/Time of Computation		ProUCL 5.111/13/2019 1:37:32 PM									
5	From File		Santa Margarita Creek Bridge Data Tables_c.xls									
6	Full Precision		OFF									
7	Confidence Coefficient		95%									
8	Number of Bootstrap Operations		2000									
9												
10	lead - 0.5											
11												
12	General Statistics											
13	Total Number of Observations			8		Number of Distinct Observations			8			
14	Number of Detects			6		Number of Non-Detects			2			
15	Number of Distinct Detects			6		Number of Distinct Non-Detects			2			
16	Minimum Detect			6.55		Minimum Non-Detect			0.495			
17	Maximum Detect			289		Maximum Non-Detect			0.503			
18	Variance Detects			12655		Percent Non-Detects			25%			
19	Mean Detects			59.58		SD Detects			112.5			
20	Median Detects			16.65		CV Detects			1.888			
21	Skewness Detects			2.439		Kurtosis Detects			5.961			
22	Mean of Logged Detects			3.063		SD of Logged Detects			1.339			
23												
24	Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use											
25	guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.											
26	For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).											
27	Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.1											
28												
29	Normal GOF Test on Detects Only											
30	Shapiro Wilk Test Statistic			0.538		Shapiro Wilk GOF Test						
31	5% Shapiro Wilk Critical Value			0.788		Detected Data Not Normal at 5% Significance Level						
32	Lilliefors Test Statistic			0.475		Lilliefors GOF Test						
33	5% Lilliefors Critical Value			0.325		Detected Data Not Normal at 5% Significance Level						
34	Detected Data Not Normal at 5% Significance Level											
35												
36	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs											
37	KM Mean			44.81		KM Standard Error of Mean			35.84			
38	KM SD			92.54		95% KM (BCA) UCL			115.8			
39	95% KM (t) UCL			112.7		95% KM (Percentile Bootstrap) UCL			113.9			
40	95% KM (z) UCL			103.8		95% KM Bootstrap t UCL			630.9			
41	90% KM Chebyshev UCL			152.3		95% KM Chebyshev UCL			201			
42	97.5% KM Chebyshev UCL			268.6		99% KM Chebyshev UCL			401.4			
43												
44	Gamma GOF Tests on Detected Observations Only											
45	A-D Test Statistic			1.093		Anderson-Darling GOF Test						
46	5% A-D Critical Value			0.73		Detected Data Not Gamma Distributed at 5% Significance Level						
47	K-S Test Statistic			0.45		Kolmogorov-Smirnov GOF						
48	5% K-S Critical Value			0.346		Detected Data Not Gamma Distributed at 5% Significance Level						
49	Detected Data Not Gamma Distributed at 5% Significance Level											
50												
51	Gamma Statistics on Detected Data Only											
52	k hat (MLE)			0.603		k star (bias corrected MLE)			0.412			
53	Theta hat (MLE)			98.88		Theta star (bias corrected MLE)			144.5			

	A	B	C	D	E	F	G	H	I	J	K	L
54					nu hat (MLE)	7.231					nu star (bias corrected)	4.949
55					Mean (detects)	59.58						
56												
57	Gamma ROS Statistics using Imputed Non-Detects											
58	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs											
59	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)											
60	For such situations, GROS method may yield incorrect values of UCLs and BTVs											
61	This is especially true when the sample size is small.											
62	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates											
63					Minimum	0.01					Mean	44.69
64					Maximum	289					Median	12.22
65					SD	99					CV	2.215
66					k hat (MLE)	0.265					k star (bias corrected MLE)	0.249
67					Theta hat (MLE)	168.6					Theta star (bias corrected MLE)	179.5
68					nu hat (MLE)	4.242					nu star (bias corrected)	3.984
69					Adjusted Level of Significance (β)	0.0195						
70					Approximate Chi Square Value (3.98, α)	0.716					Adjusted Chi Square Value (3.98, β)	0.438
71					95% Gamma Approximate UCL (use when $n \geq 50$)	248.8					95% Gamma Adjusted UCL (use when $n < 50$)	406.8
72												
73	Estimates of Gamma Parameters using KM Estimates											
74					Mean (KM)	44.81					SD (KM)	92.54
75					Variance (KM)	8564					SE of Mean (KM)	35.84
76					k hat (KM)	0.234					k star (KM)	0.23
77					nu hat (KM)	3.751					nu star (KM)	3.678
78					theta hat (KM)	191.1					theta star (KM)	194.9
79					80% gamma percentile (KM)	63.02					90% gamma percentile (KM)	135.2
80					95% gamma percentile (KM)	222.3					99% gamma percentile (KM)	457
81												
82	Gamma Kaplan-Meier (KM) Statistics											
83					Approximate Chi Square Value (3.68, α)	0.599					Adjusted Chi Square Value (3.68, β)	0.358
84					95% Gamma Approximate KM-UCL (use when $n \geq 50$)	275.3					95% Gamma Adjusted KM-UCL (use when $n < 50$)	460.3
85												
86	Lognormal GOF Test on Detected Observations Only											
87					Shapiro Wilk Test Statistic	0.777					Shapiro Wilk GOF Test	
88					5% Shapiro Wilk Critical Value	0.788					Detected Data Not Lognormal at 5% Significance Level	
89					Lilliefors Test Statistic	0.372					Lilliefors GOF Test	
90					5% Lilliefors Critical Value	0.325					Detected Data Not Lognormal at 5% Significance Level	
91	Detected Data Not Lognormal at 5% Significance Level											
92												
93	Lognormal ROS Statistics Using Imputed Non-Detects											
94					Mean in Original Scale	44.93					Mean in Log Scale	2.295
95					SD in Original Scale	98.87					SD in Log Scale	1.816
96					95% t UCL (assumes normality of ROS data)	111.2					95% Percentile Bootstrap UCL	114.1
97					95% BCA Bootstrap UCL	146.4					95% Bootstrap t UCL	642.6
98					95% H-UCL (Log ROS)	2442						
99												
100	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution											
101					KM Mean (logged)	2.121					KM Geo Mean	8.341
102					KM SD (logged)	1.944					95% Critical H Value (KM-Log)	5.977
103					KM Standard Error of Mean (logged)	0.753					95% H-UCL (KM -Log)	4457
104					KM SD (logged)	1.944					95% Critical H Value (KM-Log)	5.977
105					KM Standard Error of Mean (logged)	0.753						
106												

	A	B	C	D	E	F	G	H	I	J	K	L
107	DL/2 Statistics											
108	DL/2 Normal						DL/2 Log-Transformed					
109	Mean in Original Scale				44.75		Mean in Log Scale				1.95	
110	SD in Original Scale				98.96		SD in Log Scale				2.351	
111	95% t UCL (Assumes normality)				111		95% H-Stat UCL				62969	
112	DL/2 is not a recommended method, provided for comparisons and historical reasons											
113												
114	Nonparametric Distribution Free UCL Statistics											
115	Data do not follow a Discernible Distribution at 5% Significance Level											
116												
117	Suggested UCL to Use											
118	95% KM (Chebyshev) UCL				201							
119												
120	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.											
121	Recommendations are based upon data size, data distribution, and skewness.											
122	These recommendations are based upon the results of the simulation studies summarized in Singh, Maichle, and Lee (2006).											
123	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.											
124												

	A	B	C	D	E	F	G	H	I	J	K	L
1	UCL Statistics for Uncensored Full Data Sets											
2												
3	User Selected Options											
4	Date/Time of Computation		ProUCL 5.111/13/2019 1:42:54 PM									
5	From File		Santa Margarita Creek Bridge Data Tables_d.xls									
6	Full Precision		OFF									
7	Confidence Coefficient		95%									
8	Number of Bootstrap Operations		2000									
9												
10												
11	lead - 2											
12												
13	General Statistics											
14	Total Number of Observations			8			Number of Distinct Observations			8		
15							Number of Missing Observations			0		
16	Minimum			0.598			Mean			25.9		
17	Maximum			71.6			Median			11.1		
18	SD			29.66			Std. Error of Mean			10.49		
19	Coefficient of Variation			1.145			Skewness			0.706		
20												
21	Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use											
22	guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.											
23	For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).											
24	Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.1											
25												
26	Normal GOF Test											
27	Shapiro Wilk Test Statistic			0.811			Shapiro Wilk GOF Test					
28	5% Shapiro Wilk Critical Value			0.818			Data Not Normal at 5% Significance Level					
29	Lilliefors Test Statistic			0.277			Lilliefors GOF Test					
30	5% Lilliefors Critical Value			0.283			Data appear Normal at 5% Significance Level					
31	Data appear Approximate Normal at 5% Significance Level											
32												
33	Assuming Normal Distribution											
34	95% Normal UCL						95% UCLs (Adjusted for Skewness)					
35	95% Student's-t UCL			45.77			95% Adjusted-CLT UCL (Chen-1995)			45.95		
36							95% Modified-t UCL (Johnson-1978)			46.21		
37												
38	Gamma GOF Test											
39	A-D Test Statistic			0.477			Anderson-Darling Gamma GOF Test					
40	5% A-D Critical Value			0.758			Detected data appear Gamma Distributed at 5% Significance Level					
41	K-S Test Statistic			0.252			Kolmogorov-Smirnov Gamma GOF Test					
42	5% K-S Critical Value			0.308			Detected data appear Gamma Distributed at 5% Significance Level					
43	Detected data appear Gamma Distributed at 5% Significance Level											
44												
45	Gamma Statistics											
46	k hat (MLE)			0.563			k star (bias corrected MLE)			0.436		
47	Theta hat (MLE)			45.97			Theta star (bias corrected MLE)			59.48		
48	nu hat (MLE)			9.016			nu star (bias corrected)			6.968		
49	MLE Mean (bias corrected)			25.9			MLE Sd (bias corrected)			39.25		
50							Approximate Chi Square Value (0.05)			2.153		
51	Adjusted Level of Significance			0.0195			Adjusted Chi Square Value			1.542		
52												
53	Assuming Gamma Distribution											

	A	B	C	D	E	F	G	H	I	J	K	L
54	95% Approximate Gamma UCL (use when n>=50))					83.84	95% Adjusted Gamma UCL (use when n<50)					117.1
55												
56	Lognormal GOF Test											
57	Shapiro Wilk Test Statistic					0.897	Shapiro Wilk Lognormal GOF Test					
58	5% Shapiro Wilk Critical Value					0.818	Data appear Lognormal at 5% Significance Level					
59	Lilliefors Test Statistic					0.194	Lilliefors Lognormal GOF Test					
60	5% Lilliefors Critical Value					0.283	Data appear Lognormal at 5% Significance Level					
61	Data appear Lognormal at 5% Significance Level											
62												
63	Lognormal Statistics											
64	Minimum of Logged Data					-0.514	Mean of logged Data					2.148
65	Maximum of Logged Data					4.271	SD of logged Data					1.879
66												
67	Assuming Lognormal Distribution											
68	95% H-UCL					3056	90% Chebyshev (MVUE) UCL					96.92
69	95% Chebyshev (MVUE) UCL					125.9	97.5% Chebyshev (MVUE) UCL					166.1
70	99% Chebyshev (MVUE) UCL					245.1						
71												
72	Nonparametric Distribution Free UCL Statistics											
73	Data appear to follow a Discernible Distribution at 5% Significance Level											
74												
75	Nonparametric Distribution Free UCLs											
76	95% CLT UCL					43.15	95% Jackknife UCL					45.77
77	95% Standard Bootstrap UCL					42.12	95% Bootstrap-t UCL					51.83
78	95% Hall's Bootstrap UCL					39.69	95% Percentile Bootstrap UCL					42.17
79	95% BCA Bootstrap UCL					43.23						
80	90% Chebyshev(Mean, Sd) UCL					57.37	95% Chebyshev(Mean, Sd) UCL					71.62
81	97.5% Chebyshev(Mean, Sd) UCL					91.4	99% Chebyshev(Mean, Sd) UCL					130.3
82												
83	Suggested UCL to Use											
84	95% Student's-t UCL					45.77						
85												
86	When a data set follows an approximate (e.g., normal) distribution passing one of the GOF test											
87	When applicable, it is suggested to use a UCL based upon a distribution (e.g., gamma) passing both GOF tests in ProUCL											
88												
89	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.											
90	Recommendations are based upon data size, data distribution, and skewness.											
91	These recommendations are based upon the results of the simulation studies summarized in Singh, Maichle, and Lee (2006).											
92	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.											
93												

	A	B	C	D	E	F	G	H	I	J	K	L
1	UCL Statistics for Data Sets with Non-Detects											
2												
3	User Selected Options											
4	Date/Time of Computation		ProUCL 5.111/13/2019 1:22:48 PM									
5	From File		Santa Margarita Creek Bridge Data Tables_b.xls									
6	Full Precision		OFF									
7	Confidence Coefficient		95%									
8	Number of Bootstrap Operations		2000									
9												
10	lead											
11												
12	General Statistics											
13	Total Number of Observations			16		Number of Distinct Observations			16			
14	Number of Detects			14		Number of Non-Detects			2			
15	Number of Distinct Detects			14		Number of Distinct Non-Detects			2			
16	Minimum Detect			0.598		Minimum Non-Detect			0.495			
17	Maximum Detect			289		Maximum Non-Detect			0.503			
18	Variance Detects			5640		Percent Non-Detects			12.5%			
19	Mean Detects			40.34		SD Detects			75.1			
20	Median Detects			16.65		CV Detects			1.862			
21	Skewness Detects			3.194		Kurtosis Detects			10.92			
22	Mean of Logged Detects			2.54		SD of Logged Detects			1.676			
23												
24	Normal GOF Test on Detects Only											
25	Shapiro Wilk Test Statistic			0.542		Shapiro Wilk GOF Test						
26	5% Shapiro Wilk Critical Value			0.874		Detected Data Not Normal at 5% Significance Level						
27	Lilliefors Test Statistic			0.327		Lilliefors GOF Test						
28	5% Lilliefors Critical Value			0.226		Detected Data Not Normal at 5% Significance Level						
29	Detected Data Not Normal at 5% Significance Level											
30												
31	Kaplan-Meier (KM) Statistics using Normal Critical Values and other Nonparametric UCLs											
32	KM Mean		35.36		KM Standard Error of Mean			17.89				
33	KM SD		68.97		95% KM (BCA) UCL			71.13				
34	95% KM (t) UCL		66.72		95% KM (Percentile Bootstrap) UCL			68.3				
35	95% KM (z) UCL		64.79		95% KM Bootstrap t UCL			128.3				
36	90% KM Chebyshev UCL		89.03		95% KM Chebyshev UCL			113.3				
37	97.5% KM Chebyshev UCL		147.1		99% KM Chebyshev UCL			213.4				
38												
39	Gamma GOF Tests on Detected Observations Only											
40	A-D Test Statistic		0.456		Anderson-Darling GOF Test							
41	5% A-D Critical Value		0.789		Detected data appear Gamma Distributed at 5% Significance Level							
42	K-S Test Statistic		0.223		Kolmogorov-Smirnov GOF							
43	5% K-S Critical Value		0.241		Detected data appear Gamma Distributed at 5% Significance Level							
44	Detected data appear Gamma Distributed at 5% Significance Level											
45												
46	Gamma Statistics on Detected Data Only											
47	k hat (MLE)		0.542		k star (bias corrected MLE)			0.473				
48	Theta hat (MLE)		74.43		Theta star (bias corrected MLE)			85.2				
49	nu hat (MLE)		15.18		nu star (bias corrected)			13.26				
50	Mean (detects)		40.34									
51												
52	Gamma ROS Statistics using Imputed Non-Detects											
53	GROS may not be used when data set has > 50% NDs with many tied observations at multiple DLs											

	A	B	C	D	E	F	G	H	I	J	K	L
54	GROS may not be used when kstar of detects is small such as <1.0, especially when the sample size is small (e.g., <15-20)											
55	For such situations, GROS method may yield incorrect values of UCLs and BTVs											
56	This is especially true when the sample size is small.											
57	For gamma distributed detected data, BTVs and UCLs may be computed using gamma distribution on KM estimates											
58		Minimum	0.01		Mean	35.3						
59		Maximum	289		Median	12.22						
60		SD	71.26		CV	2.019						
61		k hat (MLE)	0.351		k star (bias corrected MLE)	0.327						
62		Theta hat (MLE)	100.7		Theta star (bias corrected MLE)	108.1						
63		nu hat (MLE)	11.22		nu star (bias corrected)	10.45						
64		Adjusted Level of Significance (β)	0.0335									
65		Approximate Chi Square Value (10.45, α)	4.225		Adjusted Chi Square Value (10.45, β)	3.784						
66		95% Gamma Approximate UCL (use when $n \geq 50$)	87.3		95% Gamma Adjusted UCL (use when $n < 50$)	97.47						
67												
68	Estimates of Gamma Parameters using KM Estimates											
69		Mean (KM)	35.36		SD (KM)	68.97						
70		Variance (KM)	4756		SE of Mean (KM)	17.89						
71		k hat (KM)	0.263		k star (KM)	0.255						
72		nu hat (KM)	8.411		nu star (KM)	8.167						
73		theta hat (KM)	134.5		theta star (KM)	138.5						
74		80% gamma percentile (KM)	51.72		90% gamma percentile (KM)	106						
75		95% gamma percentile (KM)	170.1		99% gamma percentile (KM)	340.3						
76												
77	Gamma Kaplan-Meier (KM) Statistics											
78		Approximate Chi Square Value (8.17, α)	2.832		Adjusted Chi Square Value (8.17, β)	2.486						
79		95% Gamma Approximate KM-UCL (use when $n \geq 50$)	102		95% Gamma Adjusted KM-UCL (use when $n < 50$)	116.1						
80												
81	Lognormal GOF Test on Detected Observations Only											
82		Shapiro Wilk Test Statistic	0.983		Shapiro Wilk GOF Test							
83		5% Shapiro Wilk Critical Value	0.874		Detected Data appear Lognormal at 5% Significance Level							
84		Lilliefors Test Statistic	0.12		Lilliefors GOF Test							
85		5% Lilliefors Critical Value	0.226		Detected Data appear Lognormal at 5% Significance Level							
86	Detected Data appear Lognormal at 5% Significance Level											
87												
88	Lognormal ROS Statistics Using Imputed Non-Detects											
89		Mean in Original Scale	35.33		Mean in Log Scale	2.05						
90		SD in Original Scale	71.24		SD in Log Scale	2.057						
91		95% t UCL (assumes normality of ROS data)	66.55		95% Percentile Bootstrap UCL	66.22						
92		95% BCA Bootstrap UCL	85.83		95% Bootstrap t UCL	139.1						
93		95% H-UCL (Log ROS)	731.5									
94												
95	Statistics using KM estimates on Logged Data and Assuming Lognormal Distribution											
96		KM Mean (logged)	2.134		KM Geo Mean	8.452						
97		KM SD (logged)	1.853		95% Critical H Value (KM-Log)	4.192						
98		KM Standard Error of Mean (logged)	0.481		95% H-UCL (KM -Log)	349.7						
99		KM SD (logged)	1.853		95% Critical H Value (KM-Log)	4.192						
100		KM Standard Error of Mean (logged)	0.481									
101												
102	DL/2 Statistics											
103	DL/2 Normal						DL/2 Log-Transformed					
104		Mean in Original Scale	35.33		Mean in Log Scale	2.049						
105		SD in Original Scale	71.24		SD in Log Scale	2.058						
106		95% t UCL (Assumes normality)	66.55		95% H-Stat UCL	735.7						

	A	B	C	D	E	F	G	H	I	J	K	L
107	DL/2 is not a recommended method, provided for comparisons and historical reasons											
108												
109	Nonparametric Distribution Free UCL Statistics											
110	Detected Data appear Gamma Distributed at 5% Significance Level											
111												
112	Suggested UCL to Use											
113	Adjusted KM-UCL (use when $k \leq 1$ and $15 < n < 50$ but $k > 1$)	116.1										
114												
115	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.											
116	Recommendations are based upon data size, data distribution, and skewness.											
117	These recommendations are based upon the results of the simulation studies summarized in Singh, Maichle, and Lee (2006).											
118	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.											
119												